



DORLING KINDERSLEY
— HANDBOOKS —

BUTTERFLIES AND MOTHS

David Carter



Common Clubtail



Orange Sulphur



Common Aeneas



Comma



Verdant
Sphinx



Schulze's Agrias



Adonis Blue



Cairns
Birdwing



Blue Night Butterfly



Shane's Uraniid Moth



Virgin Tiger-moth



Basker



Madagascan Sunset Moth

The clearest recognition guides available

DORLING KINDERSLEY
— HANDBOOKS —
BUTTERFLIES AND MOTHS





DORLING KINDERSLEY
— HANDBOOKS —

BUTTERFLIES AND MOTHS

Authoritative text, crystal-clear photography and a systematic approach make the *Dorling Kindersley Handbook of Butterflies and Moths* the most comprehensive and concise pocket guide to butterflies and moths of the world. Packed with more than 600 full-colour photographs of over 500 species, this handy pocket guide is designed to cut through the complex process of identification to enable you to recognize a species instantly.

PHOTO-ENCYCLOPEDIA APPROACH

Thoroughly researched and expertly written, each species entry combines a precise description with annotated photographs to highlight the chief characteristics and distinguishing features of each butterfly or moth. A distribution map, showing the geographical range of the species, as well as colour-coded bands providing at-a-glance facts for quick reference, complete every entry.

IDENTIFICATION MADE EASY

For beginners and established enthusiasts alike, the *Dorling Kindersley Handbook of Butterflies and Moths* explains what a butterfly or moth is, how butterflies and moths are classified, how to observe them and how to record species you have seen. The book provides a visual identity key that photographically lists

the families you will find in each region, and guides you to the correct entries. A concise glossary explains all technical and scientific terms used in the book.





 DORLING KINDERSLEY
— HANDBOOKS —

BUTTERFLIES AND MOTHS







DORLING KINDERSLEY
—HANDBOOKS—

BUTTERFLIES —AND— MOTHS

DAVID CARTER



Photography by
FRANK GREENAWAY



A Dorling Kindersley Book

Dorling Kindersley

**LONDON, NEW YORK, DELHI, JOHANNESBURG,
MUNICH, PARIS and SYDNEY**

Editors Alison Edmonds, Heather Dewhurst

Art Editors Elaine Hewson

Consultant Editor Dr John D. Bradley

Production Caroline Webber

Caterpillar illustrations by John Still

**First published in Great Britain in 1992
by Dorling Kindersley Limited, London
9 Henrietta St, London WC2E 8PS
Reprinted with corrections in 2000**

Copyright © 1992 Dorling Kindersley Limited

Text copyright © 1992 David J. Carter

**All rights reserved. No part of this publication may be reproduced,
stored in a retrieval system, or transmitted in any form or by any means,
electronic, mechanical, photocopying, recording or otherwise, without
the prior written permission of the copyright owners.**

**A CIP catalogue record for this book is available
from the British Library
ISBN 0 7513 2707 7**

**Computer page make-up by
The Cooling Brown Partnership, Great Britain**

Text film output by The Right Type, Great Britain

Reproduced by Colourscan, Singapore

Printed and bound by Kyodo Printing Co., Singapore

**see our complete
catalogue at
www.dk.com**

CONTENTS

INTRODUCTION • 10

- Author's Introduction 6
- How This Book Works 9
- Butterfly or Moth? 10
 - Life-Cycle 12
 - Early Stages 14
 - Survival 16
- Conservation 18
- Observation 20
- Rearing 22
- Butterfly Garden 24
- Zoogeographical Regions 26



BUTTERFLIES • 36

- Hesperiidae 36
- Papilionidae 46
- Pieridae 62
- Lycaenidae 76
- Nymphalidae 106



MOTHS • 188

- Thyrididae 188
- Drepanidae 189
- Uraniidae 190
- Geometridae 192
- Lasiocampidae 204
- Eupterotidae 210
- Anthelidae 212
- Bombycidae 214
- Brahmaeidae 216
- Saturniidae 218
- Sphingidae 236
- Notodontidae 246
- Noctuidae 252
- Agaristidae 266
- Lymantriidae 267
- Arctiidae 273
- Castniidae 284
- Sesiidae 286
- Limacodidae 287
- Zygaenidae 288
- Cossidae 291
- Hepialidae 294



- Glossary 298
- Index 299
- Acknowledgments 304


AUTHOR'S INTRODUCTION

Of all the insects, butterflies and moths are the most celebrated. Butterflies are probably the most popular because they are active by day, and are renowned for their beautiful colours and graceful flight. Moths are often regarded as less engaging, but with their diversity of shapes, sizes, and colours, they are as fascinating as butterflies.

BUTTERFLIES AND MOTHS are known scientifically as Lepidoptera (meaning scaly wings), because their wings are covered with thousands of tiny, overlapping scales. These scales are often quite brilliantly

coloured and account for the distinctive patterns that can be found on both butterflies and moths.

There are approximately 170,000 known species of Lepidoptera: about one tenth of these are butterflies, and the rest are moths. Butterflies and moths are amazing in their variety of size, shape, and colour. Their immense diversity, and ability to adapt to virtually any climate, has made them some of the most



THE SMALLEST

*With a tiny wingspan of around 1.5cm (5/8 in), the western pygmy blue (*Brephidium exilis*, see p.97) is one of the smallest butterflies in the world. These specimens are shown in proportion to one another.*

THE LARGEST

*The atlas moth (*Attacus atlas* see p.221) is the world's largest moth in overall size, with a wingspan of up to 30cm (12in).*

successful creatures on earth, with habitats ranging from arctic tundra to alpine mountain summits, as well as the warmer tropical rainforests and coastal mangrove swamps.

FLOWER ASSOCIATION

As adult butterflies are only able to feed on fluids, flower nectar is the major source of sustenance for most species. (Other butterfly foods range from fermenting sap, to liquids from dung and decaying carrion.) Plants benefit from these associations

because, while feeding, the insects transfer pollen from one plant to another.

Butterflies and moths

feed by means of a long, hollow feeding tube or proboscis. This remains coiled up beneath the head when not in use, but when extended it can probe the depths of a flower in search of nectar. Different species have different lengths of tongue, a feature that is influenced by the particular flowers on which they feed.

SELECTION

The 500 or more species described and illustrated in this book have been selected to represent as wide a range of different types of butterflies and moths as possible.

Emphasis has been placed on common species, or those with interesting features. It would have been impossible to include all the interesting and common examples of butterflies and moths when the range is so enormous, so I have chosen a selection that I hope will stimulate your interest.



HABITATS

Watching butterflies and moths in their natural habitats is always rewarding for the interested amateur. Learn to recognize the species in your area, and you will build up an understanding of their flight times, habits, and foodplants.

HOUSE MOTH




With a wingspan of about 2cm (3/16in), the common brown house moth or false clothes-moth (*Hyalophora pseudotsugella*), is one representative of many thousands of small moth species including the notorious clothes moths that belong to Microlepidoptera. The smallest Microlepidoptera have a wingspan of just a few millimetres.

Despite their small size, many Microlepidoptera are significant pests. Two of the most common are the codling moth, or apple maggot, (*Cydia pomonella*), and the diamond back moth (*Plutella maculipennis*) which attacks vegetables. I have not been able to cover Microlepidoptera in this book, but a vast number of small species exist, often with colours and shapes that are as beautiful as their larger consins.

LEPIDOPTERA EVOLUTION

The earliest moth fossils are estimated to be between 100 and 140 million years old; butterflies have a fossil record that goes back 40 million years. Lepidoptera originated when flowering plants were beginning to proliferate, and have developed in close association with them. Caddis flies (Trichoptera), the most closely related group of insects to butterflies and moths, are believed to have originated about 250 million years ago, but transitional forms have yet to be identified.



FOSSILIZED MOTH

This early example of a moth has been preserved in amber (the fossilized resin of an ancient plant)



HEDYLID MOTH

BUTTERFLY OR MOTH?

Until very recently South American *Hedylid* "moths" were believed to belong to the moth family Geometridae, but detailed study has revealed that they are more closely related to butterflies. Superficially they resemble moths, but many of their internal and external body features are like those of butterflies.

THE NAMING SYSTEM

Common names vary from country to country. Thus, scientists usually use the system established in the eighteenth century by the Swedish naturalist, Carl von Linné (his name is commonly latinized as Linnaeus). The generic name, which always appears first, groups the species with others sharing similar features. The second, or specific name, differentiates the species from other members of the genus. About 170,000 described species of butterflies and moths exist, but there are at least as many species yet to be described. When a new species is named, it is usually described from a number of specimens. A single specimen, the type, is then selected as the one upon which the identity of the species is judged for all time.



TAGORA PALLIDA



HYLES LINEATA

NAMED SPECIMEN

Type specimens are distinctively labelled with a red dot

LINNAEUS

One of many species named by Linnaeus.

BUTTERFLY OR MOTH?

BUTTERFLY CHARACTERISTICS

Butterflies are a group of specialized, day flying Lepidoptera. Generally, they can be recognized by their bright colours and clubbed antennae, but also by the way they rest, with the wings held together over the back. In butterflies, the base of the hindwing is expanded and strengthened, supporting and coupling with the forewing when in flight.

typical scale-covered wings of butterfly




ORANGE TIP



COMMON IMPERIAL BLUE

WING SHAPE

Butterflies have a wide variety of wing shapes as shown by these two specimens



antennae thickened at the tips

bright colours of typical day-flying butterfly

characteristic large and rounded wings

BUTTERFLY ANATOMY

Orange-barred giant sulphur (*Phoebis philea*, see right) has all the features common to a typical butterfly

ORANGE-BARRED GIANT

RESTING BUTTERFLY

This butterfly from the family Nymphalid is seen here resting in the typical butterfly posture, with its wings held together above its back (see left).

HINDWING COUPLING

A close look at the underside of a common blue butterfly (*Polyommatus icarus*) shows the expanded hindwing base typical of butterflies (see right).



MOTH CHARACTERISTICS

Moths are so diverse that it is difficult to give a general description. There are even many day-flying species. Moths can be distinguished by their antennae, which lack clubbed tips, and are filamentous or feathered. Most moths have a wing-coupling device consisting of bristles on the base of the hindwing that engage with a flap or "catch" on the forewing. Males have single stout bristles, whereas females have a number of slender bristles.



FILMY CAMPYLOPTIS


• elongated wings typical of moths



OWL MOTH

WING SHAPE
Moth wings vary in size, shape and colour.

most moths have feathered antennae



A TYPICAL MOTH

The acacia carpenter moth (*Xylocopa encalypti*) is a fairly typical moth with dull camouflage colours and a robust body.

• hook and bristle wing coupling device hidden behind wings

• characteristically robust moth body

ACACIA CARPENTER MOTH

RESTING MOTH

The white ermine moth (*Spilosoma lubricipeda*), resting in a characteristic moth posture with its wings folded, roof like, over the back (see left).

WING-COUPLING

A closer look at the underside of the wings of the Jersey tiger (*Euplagia quadripunctaria*) reveals the typical moth wing-coupling device (see right).




LIFE-CYCLE

BUTTERFLIES AND MOTHS have a complex life-cycle consisting of four phases: egg, caterpillar (larva), pupa, and adult. In the egg stage, a caterpillar develops within a protective envelope. The caterpillar stage is the main feeding period. In order to grow, the cater-

pillar must shed its skin several times. During the pupa phase the body components are broken down and reformed into an adult butterfly or moth. This life-cycle is called a complete metamorphosis.

1 EGG The egg darkens and you can see the young caterpillar moving about inside, shortly before emergence time. It first cuts a circular "lid" in the tough egg shell (A), and then pulls its body free of the egg with wriggling movements (B and C). This is one of the most vulnerable stages. Once it has emerged (D), the caterpillar usually eats its empty egg-shell (E). This provides the nutrients for it to survive until it can locate its foodplant.



caterpillar rupturing
its environment
• first insect




a full-
emerged
caterpillar
pulls
toward
the egg to
• eat it

SOUTH AMERICAN OWL BUTTERFLY

the caterpillar finally
breaks free of its egg

CHEQUERED SWALLOWTAIL

4 ADULT Some choose the upper surface of leaves (D) on which to lay their eggs, while others choose the undersides where the eggs may be better protected. Certain species lay their eggs in crevices or inside plant tissues. Females avoid plants that already have eggs laid on them. This ensures that food is there for her eggs only. The female usually glues the eggs to the surface of a leaf, or a similar support, with a viscous secretion from her body. Some butterflies lay their eggs singly, while others lay them in large batches. Butterflies and moths whose caterpillars feed on a wide range of plants often scatter eggs in flight.



butterflies
select the
right plant
to lay eggs
on by sight,
smell, taste,
• and touch

eggs on
underside
• of leaf

caterpillar
spinning its
girdle for
support •

fine,
fern
girdle •

2 CATERPILLAR In the case of the citrus swallowtail, the caterpillar selects a suitable stem and spins a silken pad to which it attaches its tail (F). The caterpillar next spins a loop or "girdle" of silk that passes around the middle of the body and is attached to the plant stem as a support (G). The caterpillar's skin splits along the back and the pupa begins to emerge (H). A series of wriggling movements

forces the old caterpillar skin towards the tail (I). The old skin is released and a series of hooks on the tail are engaged into the silken support pad. The pupa now takes on its final shape.

the caterpillar
is protected by
an effective
camouflage

discarded skin
of caterpillar

CITRUS SWALLOWTAIL

at the final
stage the
pupa hardens

wings of butterfly
will fold out

proboscis of butterfly
folded under head •

the butterfly holds
onto the empty case
with claws at the tip
of its legs

butterfly
stretching its wings
to form correctly

3 PUPA Shortly before emergence, the colour of the butterfly becomes faintly visible (J). The pupa case splits and the butterfly starts to struggle out (K). When completely free (L), the butterfly releases a fluid called meconium from the tip of its abdomen.

This contains the waste materials accumulated during the pupa phase. After emergence, the butterfly rests with its crumpled wings hanging down and expands them by pumping blood into the wing veins (M). It is important that the wings expand fairly rapidly before they harden, or they will be permanently deformed.

EARLY STAGES

EACH STAGE of the development of a butterfly or moth is specially adapted to enable it to carry out particular functions. As many species of butterflies and moths spend most of their

lives as soft bodied caterpillars, they have developed a wide range of devices to protect themselves from predators. The pupa stage is immobile and therefore even more vulnerable to attack.

CATERPILLARS

Caterpillars often blend into the background or mimic an object such as a dead leaf to conceal themselves. Looper caterpillars of the moth family Geometridae mimic twigs so that they are safe when at rest. Other caterpillars are covered with hairs or spines that make an unpleasant mouthful for a bird or small mammal. (Cuckoos are one of the few birds that will eat hairy caterpillars.) The hairs of some species are poisonous and can cause a rash if handled. Those caterpillars that are poisonous or distasteful advertise the fact with bright and distinctive wing patterns.

TWIG MIMIC

The purple thorn (Selenia tetralunaria) caterpillar has a highly developed camouflage that is hard to distinguish it from the twig on which it rests.



• even bark textures are accurately reproduced




SPINY CATERPILLAR

The bright pattern on this saddle (Sibine sp.) caterpillar warns that it has stinging spines.

POISONOUS MOUTHFUL

Most predators will avoid the pine lappet (Dendrolimus pini) caterpillar as its hairs have irritant properties.



LEAF MIMIC

This green Lycaenid caterpillar (Castalius rosimon), blends with a leaf of its foodplant



WARNING PATTERN

This strongly patterned magpie moth (Abraxas grossulariata) caterpillar, is distasteful to birds.



FRIGHT TACTIC

The lobster moth (Stauropus fagi) caterpillar raises its head and scorpion-like tail when alarmed



• this caterpillar needs no camouflage since it is such a fearsome sight

PUPA

The pupa of a butterfly is commonly called a chrysalis, a term derived from the greek word for gold, since a number of butterfly pupae have metallic markings. Although pupae have hard, protective, outer shells, they are still vulnerable to birds, mice, and other creatures that regard them as tasty morsels. Like caterpillars, many gain protection by merging into the background, and some are even able to change their colour to match the surface on which they are resting. Others resemble dead leaves or pieces of twig, while poisonous pupae are usually quite conspicuous and brightly coloured. Moth pupae are often formed in a protective silken case called a cocoon.

LEAF MIMIC

The chrysalis of the owl butterfly (Caligo beltrao) resembles a dead leaf



dark
yellow
markings
on pupa

FRUIT MIMIC

A berry-like chrysalis of a blue morpho (Morpho sp.) butterfly.



DISTASTEFUL SPECIES

The pupae of the queen butterfly (Danaus gilippus) are poisonous to predators.



the poison of this pupa comes from the plant on which it feeds

WING VEINS

The chrysalis of the cloudless giant sulphur (Phoebis sennae) shows the developing wing veins.



the head is at this end of the pupa

butterfly's
developing
wing veins

SILKEN SUPPORT

The giant swallowtail (Papilio cresphontes) chrysalis is supported by a silken girdle, which was spun by the caterpillar at an earlier stage



BRIGHT GREEN

The chrysalis of the common bluebottle (Graphium sarpedon), varies in colour from green to brown.



SURVIVAL

BUTTERFLIES AND MOTHS have always been depicted as fragile creatures, and objects of great beauty: as such they have to survive in a hostile world. They have no offensive weapons such

as stings, or biting jaws to defend themselves, unlike so many other insects. To protect themselves from birds and other predators they have had to adopt defensive strategies.

CAMOUFLAGE

The most universal defence tactic among adult butterflies and moths is to blend into the background, a feat achieved in various ways. When resting, butterflies hold their wings together so that only the dull underside shows. Thus, a brightly coloured butterfly seems to disappear as it lands in a hedge and closes its wings. Many moths avoid birds by flying at night, but they are then in danger from bats. However, many species are able to hear the cries of bats and therefore avoid them. Most night-flying moths have dull coloured wings that provide good camouflage when they rest on tree trunks. Other species have elaborate patterns that break up the wing and body shape so that it is difficult to recognize. Moths, in particular, are good mimics of a wide range of objects from dead twigs and leaves to wasps and spiders.

BARK MIMIC

Like many moths, this carpenter moth (Cossidae) has wings that blend with the bark on which it rests.



LEAF BUTTERFLY

So called because of its remarkable camouflage, even the leaf veins and blemishes are accurately reproduced by the Indian leaf butterfly (Kalima inachus).



hindwing tip of the butterfly is just visible

wing underside resembles dead leaf

WARNING COLOURS

Most butterflies and moths defend themselves by camouflage, but those species that are poisonous advertise their defense mechanism with bright colours. Inexperienced predators, such as young birds, soon learn to leave insects with warning colours alone. Some moths have dull forewing colours that provide good camouflage when the moth is resting. If the moth is threatened, it reveals brightly coloured hindwings in a startling flash. In addition, some species have false eyespots, that create a face to startle the attacker.

FLASH COLORATION

The sila underwing (Catocala ilia), scares would-be attackers with the flash of bright colour.



forewing dull - a comparison to hindwing

SILA UNDERWING

yellow of hindwing presents flash of colour

EYESPOTS

The twin-spotted sphinx (Smerinthus jamaicensis) displays large eyespots on its brightly coloured hindwings to warn off predators.



double, black-ringed, metallic blue hindwing eyespots

TWIN-SPOTTED SPHINX

unusual jagged shape of hindwing margins

MIMICRY

Poisonous butterflies of the same species often fly together so that their warning colours are more easily recognized. A number of poisonous species even share a similar warning pattern. In this way, birds have only to learn that one species is poisonous to avoid all the rest. Some non-poisonous species mimic poisonous species so that they too are left alone. In the past, these mimicry associations have confused entomologists who have only recognized one species where several in fact existed.

MIMICRY ASSOCIATIONS

These two species of distasteful butterfly are difficult to tell apart. By sharing the same pattern, they help to protect each other.



vivid red of inner margin is a deterrent to would-be predators

SMALL POSTMAN BUTTERFLY



these butterflies are very difficult to tell apart and would fool most hungry birds

POSTMAN BUTTERFLY

CONSERVATION

IN MANY PARTS of the world, butterfly and moth numbers have decreased alarmingly in recent times and many species have become extinct. It is essential that we take steps to find out what is going wrong before it is too late to save these fascinating creatures for future generations. In the Victorian era, when collectors had their hey-day, their activities had little effect on butterfly and moth populations. This is hardly surprising since each insect lays many, and often hundreds, of eggs in the expectation that only one or two will survive to maturity. However, today when the numbers of some species are dangerously low, even collecting a few specimens of a rare species may be enough to tip the balance against survival. Some conservation organisations are recommending that certain species should be protected from

collection. There is little that can be done to save our butterflies and moths if their habitats are destroyed, so it is important that we manage our environment, and avoid further damaging the already fragile, balance of nature.

APOLLO BUTTERFLY



LARGE COPPER



EXTINCTION

These two butterflies are at risk from changes in their habitats, the large copper due to drainage of wetlands for farming, and the apollo because of tourism in mountainous areas

BUTTERFLIES, MOTHS, AND MAN

Butterflies and moths can be both allies and enemies of man. When we grow vast areas of the same type of plants, for example fields of wheat and rice or plantations of conifers, we create the ideal conditions for certain species to build up huge populations and become pests. In some cases, an insect may be accidentally introduced to another country and become a pest because its natural predators and competition are absent. Butterflies are valuable pollinators when they move from plant to plant gathering nectar. Some caterpillars feed on weeds and are agents of control. Other species have been cultivated for centuries for their silk.

PEACOCK




GYPSY MOTH



FRIEND OR FOE?

The peacock (Inachis io), pollinates plants, thus indirectly helping man. The gypsy moth, (Lymantria dispar), is a common pest in fruit orchards.



MARSH
FRITILLARY

The countryside is now an environment controlled by man. Many butterfly and moth habitats have been destroyed by clearing and draining of land to cultivate crops. The marsh fritillary (above) is at risk from land-drainage.

INSECTICIDES


The use of sprays and herbicides has become a great threat to the habitats of butterflies and moths. Not only insects, but other animals too are killed, which interferes with the balance of nature



AFRICAN GIANT
SWALLOWTAIL

TROPICAL FORESTS

Destruction of the world's tropical forests imperils the many varied species that live within them



Tropical rainforests, with their huge variety of plants and wonderful fauna, are the richest habitats for butterflies, providing homes for some of the most spectacular species. Their continued destruction for growing crops and the logging industry threatens these species. Much has yet to be learned about the complex communities of insects that live in tropical forests. Butterflies and moths are now an integral part of this research, because they are relatively easy to recognize, and are already well-documented. Threatened species of birdwing are being farmed in an effort to ensure their survival.

OBSERVATION

THE STUDY of butterflies and moths in their natural environment is always rewarding. The first close-up view of a live butterfly through a magnifying glass is an amazing experience that can never be matched by looking at preserved specimens.


As butterflies and day-flying moths are such active creatures, it is best to observe them when they are feeding or drinking. The flower garden is one of the easiest places to start butterfly watching. Patience is essential. Stand close to a group of nectar-bearing flowers and wait for a butterfly to visit.

When it is well settled, it is possible to approach without disturbing it.

Remember that butterflies are very sensitive to

even the slightest movement, and take care not to cast your shadow over them.

With experience, you soon learn to recognize a good butterfly site. Hedgerows, forest margins, and any sheltered, sunny spot will usually



WHERE TO LOOK

Butterflies often gather to drink from puddles on muddy ground, and this is an ideal opportunity to study these beautiful creatures.


• these larvae conceal several spores from the *Papilionidae* family, but at this early stage they are hard to identify

• by looking like bird droppings these caterpillars are not attracting the attention of birds or other predators

these caterpillars are all tropical species

FINDING SPECIMENS

When looking for caterpillars remember the effectiveness of their camouflage. These swallowtail caterpillars disguise themselves by resembling bird droppings



prove to be fruitful. Damp areas by streams and puddles can be popular drinking places for butterflies, particularly in the tropics.

Many butterflies and moths are attracted to fermenting fruit or to sap oozing from wounds in tree trunks. Moth hunters have taken advantage of this to attract moths for study. They smear a "treacle" of sugars, molasses, rum, and beer onto tree trunks or fenceposts at dusk and then visit at hourly intervals throughout the night.


By torchlight they can watch moths gorging themselves on the sweet alcoholic mixture.

Moths are dazzled and disorientated by lights, not, as many people think, attracted to them, so they often tend to fly


NIGHT LIGHT
Any ordinary lamp will attract moths at night, but mercury vapour lamps are by far the most efficient.

this paraffin lamp is easily portable

flat-bottom gives lamp stability, and prevents it from tipping over



towards them. Using this principle, many different forms of light traps have been devised, and these are used to enable scientists both to collect moths, and to monitor numbers and species, in biological surveys. However, a simple lantern or light bulb in front of a white sheet will attract many different species



BUTTERFLY FEEDING


This cracker butterfly (*Hamadryas feronia*) is feeding on the juices from a piece of fruit. Both butterflies and moths enjoy feeding on fruits.

EQUIPMENT FOR THE FIELD

One of the best ways to keep a record of butterflies and moths you have seen, is to take photographs of them. You can equip most modern single lens reflex cameras with a macro lens for butterfly close-ups, and achieve excellent results with practice and patience. A simple snap-shot camera is useful for recording butterfly habitats. Write down times of appearance, distribution, mating behaviour, and food-plants, to build up a picture of the species' habits. Many students have made important discoveries in this way.




• tape recorder



• notebook and field guides

short-focus telescope



• lantern



REARING

ONE OF THE BEST ways to learn more about butterflies and moths is to rear them from eggs. There are a number of large and spectacular exotic species, including silkmoths and moon moths that are relatively easily reared in captivity, as well as the more common and native species.

Keep eggs in small transparent plastic boxes until they hatch. If left in too large a container, they may dry up and die. As soon as the tiny caterpillars hatch, transfer them into a container that holds some of their foodplant. While small, you can keep most caterpillars in plastic boxes lined with absorbent paper. Provide

them with a regular supply of fresh foliage. At this stage, there is no need to punch holes in the lid for ventilation, as this causes the food to dry up too rapidly. Condensation can endanger small caterpillars, but the paper lining should prevent this from happening. As caterpillars grow, it will

be necessary to transfer them to larger containers or



leaves of oak are used to rear the oak (*Antheraea pernyi*) silkmoth

silkmoth caterpillar

foodplant must be changed regularly to ensure fresh food for the caterpillar

twigs reach down to ground, so that caterpillars can climb back on plant if they fall off

KEEPING CATERPILLARS
When rearing caterpillars on cut food it is essential to plug the neck of the water jar. Otherwise the caterpillars will crawl in and drown.

cages. Some caterpillars require a growing plant. Place a potted plant in the cage or make a cage by tying a sleeve of netting over the branch of a shrub.

PUPA STAGE

Many butterfly species will simply attach their pupae to the foodplant, but some moths form their pupae below ground or under bark.

To provide a pupation site, place a thick layer of slightly damp peat on the floor of the cage. Some pupae overwinter with the adults emerging in the following year. In the spring you

should transfer them to a spacious emergence cage, and spray them from time to time with a fine mist of water. The balance of moisture is critical at all stages of development, as too much will encourage mould. Cages should be cleaned regularly. It is essential to provide twigs for the newly emerged butterflies and moths to cling to while they are expanding their wings. Not all adults

will feed, but those that do will take nectar from cut flowers provided, or substitute nectar that can be made quite easily from a diluted honey or sugar solution.



a mesh fastener allows easy access to the cage

CAGE DESIGN

Where possible, cages should always provide the caterpillar with light and ventilation. They must also be easy to clean.

fresh or cut plants make suitable food for the caterpillars

mesh cage provides adequate ventilation

HANDLING CATERPILLARS



Try to avoid handling caterpillars but if it is necessary, move smaller ones with a fine paintbrush. Many caterpillar species have stinging hairs—these should be handled with caution. When caterpillars are about to moult, they usually look dull and shrunken. They must not be moved at this stage as any disturbance is likely to prevent moulting.



BUTTERFLY GARDEN

ONE WAY IN WHICH you can contribute towards conservation is to make your garden as attractive as possible to butterflies and moths. In doing this, you will encourage a range of other wildlife so that your garden will be an even more enjoyable place.

The first step is to grow flowers that provide a rich source of nectar. Night scented flowers, such as honeysuckle, are usually attractive to moths. Make sure that you grow plants that flower at different times of year to provide a continuous food supply throughout the seasons.

It is also desirable to grow caterpillar foodplants, as these will encourage female butterflies to lay their eggs in your garden. With a little research you can find out which butterfly and moth species inhabit your area so that you can provide them with a range of suitable plants. If space permits, you could

develop an area of wild garden for native plants to flourish.

If you plan to attract butterflies and moths to your garden, you should avoid using insecticides if possible. Those that kill aphids are said to be harmless to caterpillars, but all garden chemicals should be used with care.




PIPEVINE SWALLOWTAIL

BUDDLEIA

Also called the butterfly bush, the flowers of this shrub attract many butterfly and moth species, including the pipevine swallowtail.

long
scented
buddleia
bush flowers
in summer



ICEPLANT

Small tortoiseshells (*Aplais urticae*) enjoying the iceplant's nectar (see left).


HONEYSUCKLE

This attracts long tongued moths, like this hawk-moth (Macroglossum stellatarum).



APPLE

Moth caterpillars like the foliage of this tree; the fallen fruit attracts butterflies like the Camberwell beauty (Nymphalis antiopa).



CAMBERWELL
BEAUTY

HUMMINGBIRD HAWK-MOTH

MARJORAM

A herb that is attractive to butterflies such as the meadow brown (Maniola jurtina).



MEADOW
BROWN

HERB

This is a useful plant for attracting such butterflies as the peacock (Inachis io).



PEACOCK

WILD FLOWERS

A small area devoted to wild flowers and grasses will also attract butterflies and moths.

this plant attracts a wide variety of insects.



PALAEARCTIC REGION

THE PALAEARCTIC REGION is the largest of the zoogeographic regions, extending across the northern hemisphere from Europe to China and Japan, and extending southwards to north Africa, including the Sahara. The climate of this region is mainly temperate but ranges from arctic to subtropical. As temperature and climate are distinctly seasonal, butterflies and moths usually have a constant number of generations each year and their



ZOOGEOGRAPHICAL PALAEARCTIC REGION

Flight periods can be predicted with some accuracy. Butterflies and moths of the Palaearctic region are better known than those in any other part of the world because the study of these insects first started in Europe. The fauna in parts of this region, for instance central Asia, is still very poorly known.

AGRICULTURE

Many areas of the Palaearctic region have been subjected to intense agricultural activity for some centuries, and this has had a profound effect on the fauna



Maniola jurtina
(Nymphalidae)



Cerura vinata
(Notodontidae)




Gryllus antiqua
(Lymantriidae)



Arctia caja
(Arctiidae)



Sphinx ligustri
(Sphingidae)



Parnassius apollo
(Papilionidae)



Argynnis latheia
(Nymphalidae)



Orithides venustus
(Hesperiidae)



Inachis io
(Nymphalidae)



Polyommatus icarus
(Lycaenidae)



Pieris brassicae
(Pieridae)




Papilio machaon
(Papilionidae)



Boarmia roboraria
(Geometridae)



Zygaena filipendulae
(Zygaenidae)



Saturnia pyri
(Saturniidae)



Bombyx mori
(Bombycidae)



Lycaena dispar
(Lycaenidae)




Anthocharis cardamines
(Pieridae)



Lasiochlamys quercus
(Lasiocampidae)

AFROTROPICAL REGION

THE AFROTROPICAL REGION includes the whole of Africa south of the Sahara. Madagascar is normally placed in a zoogeographic region of its own because so many of its species occur nowhere else in the world. However, for the purposes of this book, it is included with the Afrotropical region. This region boasts more than 2,500 described species of butterflies, and many more species of moths, although little is known about the smaller




ZOOGEOGRAPHICAL AFROTROPICAL REGION

moths. The richest parts of the region are the lowland tropical rainforests, with those in west Africa having the most species. The other major habitat for Lepidoptera is grassland and savanna, which has a smaller but characteristic butterfly and moth fauna of its own.

SAVANNA


Grassland with trees and scrub is just one of the many habitats of the African continent



Lasiopates hirtella
(Lasiacinae)



Papilio demoleus
(Papilionidae)



Calotis damia
(Pieridae)


Anophe pando
(Noctuidae)



Lurcytesenia
(Brahmaeidae)



Poecilinix thelyse
(Lycaenidae)




Baeus elvane
(Saturniidae)

Dasyrhira pyrasoma
(Lymantriidae)



Lycrynia elvane
(Nymphalidae)



*Leucanodonta
negulureia*
(Castniidae)



Coelodes furcata
(Hesperiidae)



Anophe panda
(Notodontidae)



Chuplex plantaria
(Cecropiidae)



Catopsilia florella
(Pieridae)




Danaus chrysippus
(Nymphalidae)



Acherontia atropos
(Sphingidae)

INDO-AUSTRALIAN REGION

THE INDO-AUSTRALIAN region encompasses two zoogeographical areas known as the Oriental and Australian regions. It stretches from Pakistan and India to Australia and New Zealand. There are profound differences in the faunas of the two regions, but many butterfly species extend from the Oriental to the Australian region, and I have found it practical to consider them together. This is one of the richest parts of the world for butterflies and moths.



ZOOGEOGRAPHICAL INDO-AUSTRALIAN REGION




Virtually the whole of this region lies within the tropics, excepting parts of Australia and New Zealand. However, many habitats are represented, from tropical forest to plains, swamps, and mountains.

PADDY FIELDS

This is a typical man-made landscape in the Oriental region.



Daintia deus
(Lycaenidae)



Papilio paris
(Papilionidae)



Cethosia lubus
(Nymphalidae)



Darna hanksae
(Notodontidae)



Cryptophanes venturina
(Geometridae)



Ogrytes pinnatus
(Lycaenidae)



Caupera thersis
(Hesperiidae)



Iema anartoides
(Lymantriidae)



Lophocarenum
(Nymphalidae)




Appias nero
(Pieridae)



Actias solene
(Saturniidae)



Uthman species
(Aciidae)




Diglossa australis
(Lasiocampidae)



Achaon janata
(Nymphalidae)




Cremnophila triangularis
(Sphingidae)



Delias myas
(Pieridae)

NEARCTIC REGION

THE NEARCTIC REGION is largely temperate in climate but extends from arctic Canada and Alaska to subtropical Florida and southern California. It bears many resemblances in climate and fauna to the Palearctic region, and a number of species are common to both regions. Insects occurring in both the Nearctic and Palearctic regions, (of which there are many), are said to have a Holarctic distribution. About 700 species of butterfly occur in the



ZOOGEOGRAPHICAL NEARCTIC REGION

Nearctic region, but the moth fauna is very much more extensive than this. Probably the best known of all the butterflies occurring in this region, is the monarch, famed for its annual migration from Canada to Mexico.

FOREST

Many species in this region inhabit temperate forests, or areas bordering agricultural land.




Dioneus plexippus
(Nym, haridae)



Schizura ipomiae
(Neodanidae)



Prodenia transversata
(Cecropidae)



Apantesis cargo
(Arenidae)

Apantesis cargo
(Nymphalidae)



Hemargus isola
(Lycaenidae)



Prodoxystus rubrinus
(Cossidae)



Lerema accius
(Pieridae)



E. pargurus clarus
(Hesperiidae)



Peridroma saucia
(Noctuidae)




Atides hahns
(Lycaenidae)



Megathymus yucate
(Hesperiidae)



Eurides marcellus
(Papilionidae)



Agnus urgalis
(Spring Jac)

Malacosoma americanum
(Lasiocampidae)



Lymantria dispar
(Lymantriidae)



Hyalophora cecropia
(Saturniidae)



Junonia coenia
(Nymphalidae)



Silene stimulea
(Limenitidae)



Neophanes menapia
(Pieridae)

NEOTROPICAL REGION

THE NEOTROPICAL REGION extends from Mexico, to Tierra del Fuego in South America. It covers a wide range of habitats and climates, but the tropical rainforests of South America have the greatest diversity of species.

The Lycaenid butterflies, represented on p.35 by *Thecla coronata*, include some of the most beautiful and jewel-like species, yet they are so little studied that there is no reliable guide for their identification. The moths include




ZOOGEOGRAPHICAL NEOTROPICAL REGION

some distinctive species such as the giant agrippa (*Thysania agrippina*), and the giant grey sphinx (*Pseudosphinx tetrio*), but many of the smaller moth species have yet to be identified.

RAINFOREST

This area contains the richest butterfly and moth populations in the world.



*Pseudosphinx
tetrio*
(Sphinxidae)



Battus philenor
(Papilionidae)



Eupackardia cellata
(Saturniidae)



*Heliconius
charitonius*
(Nymphalidae)



Thecla coronata
(Lycenidae)



Pseudophlox tetrio
(Sphingidae)



Phycodonta aegyptiaca
(Noctuidae)




Dismerphia ampax
(Pieridae)



Exorista staudingeri
(Geometridae)



Heliconia erato
(Lycenidae)



Morpho rhetenor
(Nymphalidae)




Uranus sloanus
(Itraniidae)



Parnassius polybus
(Hesperiidae)



Chionochloa erias
(Noctuidae)



Urbanus proteus
(Hesperiidae)

BUTTERFLIES

HESPERIIDAE

THE FAMILY HesperIIDae, more familiarly referred to as skippers, is a large, primitive group of some 3,000 species occurring throughout the world. Although generally considered to be butterflies, they frequently lack butterfly-style clubs to the antennae. They can be recognized by their large heads, stout bodies, and rather short,

triangular-shaped forewings. They are mostly small- to medium-sized insects with drab colours, although a few of the larger species are quite brightly coloured, and attractively patterned.

Skippers earned their common name from the characteristic way they dart from flower to flower

Family	HESPERIIDAE	Species	<i>Urbanus proteus</i>	Author	Linnaeus
--------	-------------	---------	------------------------	--------	----------

LONG-TAILED SKIPPER

This is one of the most recognizable skippers, and can be distinguished from other North American long-tails by the iridescent green on the upperside of the wings and body. It is an erratic flier.

- **EARLY STAGES** The caterpillar is olive-green with brown lines and yellow and black spotting. The head is brown with two yellow spots. It often feeds on varieties of cultivated bean (*Phaseolus*)
- **DISTRIBUTION** Widespread in South America, from Argentina, extending northwards into the USA as far as Texas and Connecticut

distinctive curved tips to the antennae

extended hindwing tails

complex patterning on the hindwing underside

NEARCTIC
NEOTROPICAL

Time of Flight	☀	Habitat	☀ ☀ ☀ ☀	Wingspan	4-5cm (1½-2in)
----------------	---	---------	---------	----------	----------------

Family **HEPHERIDAE**Species *Zophopetes dymorphus*Author **Irmen**

PALM SKIPPER


The robust, chocolate-brown palm skipper is one of several similar species found in Africa. The underside of the hindwing is brown with scattered black dots and a purplish tinge. The adult palm skippers are active at dusk.

• **EARLY STAGES** The caterpillar is apparently undescribed, but feeds on date palm (*Phoenix dactylifera*) and other palms.

• **DISTRIBUTION** Widespread at low altitudes in savanna country, riversides, and forests, from South Africa to Eritrea and Senegal, south of the Sahara.



AFRICA



Time of Flight

Habitat

Wingspan 4-5 cm (1½-1¾ in)



Family **HEPHERIDAE**Species *Eupargyreus clarus*Author **Cramer**

SILVER-SPOTTED SKIPPER

This large skipper is dark brown with orange markings on the forewings, and a small cluster of white eyespots at the forewing tip.

• **EARLY STAGES** The caterpillar is light green with darker markings and has a reddish brown head. There is one generation a year in the temperate north, and two or three in warmer, southern regions.

• **DISTRIBUTION** Found in North America.

NEARCTIC
NEOTROPICAL

Time of Flight

Habitat

Wingspan 4.5-6 cm (1½-2¼ in)


Family	II SPERIDEAE	Species	<i>Euschemon rafflesia</i>	Author	Macleay
--------	--------------	---------	----------------------------	--------	---------

REGENT SKIPPER

This large black and yellow skipper is represented by two subspecies in Australia. Regent skippers visit the flowers of many plants, often feeding on Lantanas. They are active in bright sunlight and have a distinctive swift and jerky flight. They rest on leaves with their wings outspread. An unusual feature of the male is its wing-coupling mechanism, which is similar to that of many moths.

• **EARLY STAGES** The stout caterpillar is green, sh or bluish grey in colour, but yellow with two reddish black stripes behind the head. It feeds at night on *Wilkiea*.

• **DISTRIBUTION** Queensland to NSW in Australia.



red tip to the underside of the abdomen



NORTH-AUSTRALIAN

♀ ♂

Time of Flight	☀	Habitat	🌳	Wingspan	15-6cm (1 1/2-2 1/2 in)
----------------	---	---------	---	----------	-------------------------

Family	II HESPERIIDAE	Species	<i>Thoryx dunn</i>	Author	Cramer
--------	----------------	---------	--------------------	--------	--------

SOUTHERN CLOUDYWING

The arrangement of pale spots on the dark brown forewing distinguishes this species from other North American cloudywings. The adults are very active, and their erratic flight pattern serves to distinguish them from other species.

• **EARLY STAGES** The caterpillar is a dull purplish brown with a green tinge, and is covered with tiny, raised spots, each bearing a hair. The head is black. It feeds on wild bean (*Strophostyles*), butterfly pea (*Bradburya*) and related plants.

• **DISTRIBUTION** It can be found on roadsides, meadows, and open spaces in the USA, from Minnesota, Nebraska, and New England, south to Texas and Florida.



broken white lines on forewings



NEARCTIC

♂ ♀

Time of Flight	☀	Habitat	🌳	Wingspan	3-4.5cm (1 1/4-1 3/4 in)
----------------	---	---------	---	----------	--------------------------

Family **HESPERIIDAE**Species *Heteropterus melpomene*

Author Pallas

LARGE CHEQUERED SKIPPER

The underside of the hindwing has a chequered pattern.

• **EARLY STAGES** The caterpillar has a greyish white body and feeds on various grasses. There is one generation a year.

• **DISTRIBUTION** Widely distributed in scattered colonies from southern Scandinavia to the Mediterranean.



♀



PALARCTIC

♀ ♂



• large, ringed spots on the hindwing underside

Time of Flight ☀

Habitat 🌿

Wingspan 3-4cm (1 1/4-1 1/2 in)

Family **HESPERIIDAE**Species *Mnesteira mela*

Aut. or Linnaeus

GOLD-SPOTTED SYLPH

This group of small brown skippers has reddish orange spots on the uppersides of the fore- and hindwings. The species are difficult to distinguish from one another, and the sexes look similar.

• **EARLY STAGES** The caterpillar is dark green above, with white lines along the back, and pale green below. It feeds on various grasses.

• **DISTRIBUTION** Found by muddy streams in South Africa, from Cape Province and Natal to Transvaal.



AFROTROPICAL



♂

• unusually large rounded hindwings

Time of Flight ☀

Habitat 🌿

Wingspan 2.5-3cm (1-1 1/4 in)

Family **HESPERIIDAE**Species *Oreophranta montana*

Author (H. H.)


ALPINE SKIPPER

The dark brown uppersides of the wings of this butterfly are patterned with angular orange spots. The undersides are mainly yellow with dark brown markings.

• **EARLY STAGES** The caterpillar is striped with greenish grey. It feeds on sedge (*Carex*).

• **DISTRIBUTION**


Occurs in the mountains of south-east Australia, from NSW to Victoria and Tasmania.



INDO-AUSTRALIAN



♂ ♂



♂

• yellow underside goes camouflage when the skipper feeds from yellow plants

Time of Flight ☀

Habitat 🌿

Wingspan 2.5-3cm (1-1 1/4 in)

Family HESPERIIDAE	Species <i>Gangara thyrsis</i>	Author Fabricius
---------------------------	--------------------------------	-------------------------


GIANT REDEYE

One of the largest skippers, this species can be distinguished by its blood-red eyes. Females are slightly larger than males, and lack the characteristic male hair patches on the wing bases.

- **EARLY STAGES** The caterpillar is blood-red, covered with a filamentous, white, waxy coating which is easily rubbed off if touched. It feeds chiefly on banana leaves (*Musa*). The pupae, which are formed among the leaves, produce a rattling noise if disturbed.
- **DISTRIBUTION** Widely distributed from Sri Lanka and India to the Philippines and Sulawesi.



caterpillar
in a rolled
leaf



♂
distinctive
angular-shaped
hindwings

• elongate, dark
brown abdomen

• large,
translucent, pale
patches on the
forewings

CATERPILLAR OF
GANGARA THYRSIS



INDO-AUSTRALIAN

Time of flight ☀️ ⬛	Habitat 🌿	Wingspan 7-7.5cm (2 1/4-3in)
---------------------	-----------	------------------------------

Family HESPERIIDAE	Species <i>Hesperilla picta</i>	Author Leach
---------------------------	---------------------------------	---------------------

PAINTED SKIPPER

The wings of this skipper are dark brown, with yellow patches nearer the body. The forewings are yellow spotted, the hindwings have a central, orange patch.

- **EARLY STAGES** The caterpillar is yellow or green, with yellow markings, and has a dark stripe along its back edged by white lines. It feeds on sword-grasses.
- **DISTRIBUTION** Coastal areas in Australia from Queensland to Victoria, and the Blue Mountains in NSW.



♂
chequered
fringe on the
hindwings



♀
white patterning
on the hindwing
underside



INDO-AUSTRALIAN

Time of flight ☀️ ⬛	Habitat 🌿	Wingspan 3-4cm (1 1/4-1 1/2in)
---------------------	-----------	--------------------------------

Family HESPERIIDAE

Species *Carterocephalus palaemon*

Author Pallas

CHEQUERED SKIPPER


The wings of this aptly named skipper are dark chocolate-brown with a chequered pattern. The sexes look similar, but females are slightly larger. Chequered skippers make only short flights. The American common name for the butterfly is arctic skipper.

• **EARLY STAGES** The caterpillar is pale yellowish brown with pink stripes when fully grown. It feeds on grasses, such as false brome (*Brachypodium*)

• **DISTRIBUTION** North east to central Europe, and Canada, and northern America.

paler underside
markings still
show the chequered
pattern

♂ Δ



ARCTIC

Time of Flight 7)

Habitat 4

Wingspan 2-3cm (4-1 1/2 in)

Family HESPERIIDAE

Species *Netrocoryne repanda*

Author Felder



EASTERN FLAT

The broad wings of this skipper have a distinctly angular appearance. The forewings are brown with three or four prominent, translucent spots edged with brown. The sexes look similar, but females are larger with more extensive translucent spots. Butterflies are on the wing from late autumn to late winter.

• **EARLY STAGES** The stout caterpillar is bluish grey, except for a yellow first segment, and is striped with black and grey. The head is black. It feeds mostly on spun leaves of *Callitriche verrucifolia*.

• **DISTRIBUTION** Widely distributed in Australia, in north-east and central Queensland, to Victoria.

distinctively
curved tips to
the antennae



characteristic,
small white spot
on the hindwings



INDO-AUSTRALIAN

Time of Flight 6

Habitat 7 4


Wingspan 4-5cm (1 1/2-2 in)

Family HESPERIIDAE	Species <i>Phocides polybates</i>	Author Fabricius
---------------------------	-----------------------------------	-------------------------

GUAVA SKIPPER

A striking skipper, this species has sharply angled fore- and hindwings which are black with metallic, greenish blue streaks. Each forewing has two vermilion spots which distinguish this skipper from similar species. The upperside of the body is black with metallic-blue, the underside is black

- **EARLY STAGES** The young caterpillar is red with yellow rings, becoming white with a brown and yellow head as it develops. It feeds on guava (*Psidium guajava*) and related species.
- **DISTRIBUTION** South and Central America extending to Argentina.



NEOTROPICAL


Time of flight ☉	Habitat 🌿	Wingspan 5-6 cm (2-2 1/2 in)
------------------	-----------	------------------------------

Family HESPERIIDAE	Species <i>Leclades forestan</i>	Author S. I.
---------------------------	----------------------------------	---------------------

STRIPED POLICEMAN

This robust species has greyish brown, triangular forewings, which are centrally suffused with white on the undersides. The rounded hindwings with their broad, short tails are characteristic of this mainly African genus of skippers. Striped policemen have a rapid flight, and their habit of patrolling over their territory from dawn to dusk gives rise to their common name. They are attracted to the flowers of various low growing plants.

- **EARLY STAGES** The caterpillar is pale yellow with purplish red bands. Its head is red or yellow, with black spots. It feeds on geranium.
- **DISTRIBUTION** Found in Africa south of the Sahara, including Madagascar and the Seychelles.



AFROTROPICAL

Time of flight ☉	Habitat 🌿	Wingspan 4.5-5 cm (1 1/4-2 in)
------------------	-----------	--------------------------------

Family HESPERIIDAE

Species *Pyrrochalcia iphis*


Author Drury

GIANT AFRICAN SKIPPER

This is the largest skipper in Africa and probably in the world. The males are black and purplish blue, while the beautiful females are strongly rayed with metallic-bluish green. The undersides are more striking, males having dark blue forewings and brilliant metallic-blue hindwings. Females are a metallic-yellowish with black veins. These huge, slow-flying skippers are probably mimics of Agaristid moths. They often fly at night.

• **EARLY STAGES** The caterpillar is black with a chequered, creamy white pattern. It feeds on the foliage of cashew trees (*Anacardium occidentale*)

• **DISTRIBUTION** Gambia to Nigeria, Zaire and Angola



Time of Flight



Habitat



Wingspan 7-8cm (2¾-3¼in)

Family HESPERIIDAE

Species *Erynnis tages*

Author Linnæus


DINGY SKIPPER

The dingy skipper is dull-coloured, but it is nevertheless a distinctive species with delicate white patterning on a greyish brown background.

• **EARLY STAGES** The caterpillar is green with a dark line along its back, and has a black head. It feeds at night on bird's foot-trefoil (*Lotus corniculatus*), and other plants of the pea family.

• **DISTRIBUTION** Occurs on open heaths and downlands throughout Europe, extending into temperate Asia

small, white markings on the underside



Time of Flight



Habitat



Wingspan 2.5-3cm (1-1¼in)

Family	HESPERIIDAE	Species	<i>Calpodex ethlius</i>	Author	Stoll
--------	-------------	---------	-------------------------	--------	-------


BRAZILIAN SKIPPER

This skipper has dark brown wings, spotted with silvery white. The forewings are narrow and pointed in contrast with the broad, lobed hindwings. It can fly over large distances.


- **EARLY STAGES** The caterpillar is greyish green with a white line down the back and brown spots along the sides. The head is orange and black. It feeds on canna leaves (*Canna flaccida*), and sometimes damages cultivated forms of this plant. It is known as the canna leaf roller. The pale green pupa is camouflaged in a leaf roll.
- **DISTRIBUTION** Widely distributed in South America, and the West Indies. Occurs in southern parts of the USA.



NEOTROPICAL



CATERPILLAR OF
CALPODEX ETHLIUS



three white spots
on the hindwing

♂


Time of Flight	☉	Habitat	all yr.	Wingspan	4.5–5.5 cm (1 1/4–2 1/4 in.)
----------------	---	---------	---------	----------	------------------------------

Family	HESPERIIDAE	Species	<i>Heathianus yuccae</i>	Authors	Boisduval & Le Conte
--------	-------------	---------	--------------------------	---------	----------------------

YUCCA GIANT SKIPPER

Large-bodied and hairy, this skipper has blackish brown wings, which are characteristically patterned with yellow and white. Males are generally much smaller than females. They can be seen from midwinter to early summer. These skippers do not feed as adults, although related species have been observed drinking on moist ground.

- **EARLY STAGES** The caterpillar is large and grub-like with a small head. It feeds on yucca.
- **DISTRIBUTION** This is the most widespread of the North American giant skippers. It lives in various habitats, including forest margins where the foodplants grow. Its range extends from Utah and Kansas in the USA, south to Florida and Mexico.



yellow shading
to hindwing edge

♀



NEARCTIC

Time of Flight	☉	Habitat	all yr.	Wingspan	1.5–8 cm (1 1/4–3 1/4 in.)
----------------	---	---------	---------	----------	----------------------------

Family HERPIDIIDAE

Species *Deiodes cecilia*

Author Bremer & Grey

LARGE SKIPPER

The large skipper is easily distinguished from other European species by its large size and the lack of strong patterning on its wings.



• **EARLY STAGES** The caterpillar is bluish green with yellow lines along the sides.

It feeds on various grasses.

• **DISTRIBUTION**

Widespread in Europe, extending to Japan where there is a distinct subspecies.

broad, dark border to the hindwing



sex brand on forewing indicates this is the male



PALEARCTIC

Time of Flight ☀

Habitat 🌱 🌿

Wingspan 2-3cm (1-1.2in)

Family HERPIDIIDAE

Species *Pholisora caudalis*

Author Fabricius

COMMON SOOTYWING

This common skipper is the darkest of several similar species of North American sootywings.

It can be seen from early spring to late autumn.

• **EARLY STAGES** The caterpillar is pale green with a dark head. It feeds on common weeds.

• **DISTRIBUTION**

Occurs in North America, from central Canada to northern Mexico, but is absent from Florida.



NEARCTIC



white spotting on forewing in this species

characteristically large hindwings

Time of Flight ☀

Habitat 🌱 🌿

Wingspan 2-3cm (1-1.2in)

Family HERPIDIIDAE

Species *Pieris matrona*

Author Linnaeus

GRIZZLED SKIPPER

The grizzled skipper can be distinguished from other skippers by the white markings on its hindwings.

• **EARLY STAGES** The caterpillar is green, striped with brown, and has a large black head. It feeds on cinquefoil (*Potentilla*) and related plants.

• **DISTRIBUTION** Europe, extending into temperate Asia.



PALEARCTIC

prominent veins on the hindwing



hequered fringe on the wings



Time of Flight ☀

Habitat 🌱 🌿

Wingspan 2-2.5cm (1/2-1in)

PAPILIONIDAE

THIS LARGE family of butterflies contains some of the biggest and most beautiful species in the world. It is also the most widely studied and well known of all the butterfly groups.

Most species occur in the tropics, but some are also found in temperate climates. Because many Papilionidae

species have tailed hindwings, their popular name is swallowtail. However, not all Papilionids have tailed wings, for example the birdwings of tropical Australasia. Swallowtail butterflies can be recognized by their large, striking wings and by the fact that they have three fully developed pairs of legs. They are usually strong fliers.

Family PAPILIONIDAE

Species *Papilio uexens*


Author Donovan

ORCHARD SWALLOWTAIL

Male orchard swallowtails are distinguished by the small, oblique band of white spots on the back forewings, and the single red spot on the inner margin of each hindwing. There are several female forms but all of them have forewings marked with white, and hindwings patterned with a band of red spots along the outer margin. They have a strong, uneven flight pattern.

• **EARLY STAGES** When first hatched, the caterpillar is brownish with white markings, and resembles a bird's dropping. When grown, it is green with short, fleshy spines along the back. The caterpillar feeds on cultivated *Citrus* and *Microcitrus* plants.

• **DISTRIBUTION** Australia from Queensland to Victoria, and also in Papua New Guinea, and adjacent islands.



characteristic
tailed hindwings

females are much
larger than males

comma-shaped red
markings

faint
scalloping to
forewing edge

pale centre to
hindwings occurs
in both sexes



INDO-AUSTRALIAN

Time of flight



Habitat



Wingspan

7.5-9cm (3-3½in)

Family PAPILIONIDAE

Species *Papilio paris*

Author Linnaeus

PARIS PEACOCK

The striking patches of metallic colour found on the hindwings place this butterfly in a group called the glass papilios. Female Paris peacocks are usually yellower than the males.

• **EARLY STAGES** The caterpillar is green with white or yellow markings, and yellow scent horns. It feeds on a wide range of plants, including *Citrus*.


• **DISTRIBUTION** Mainly at low altitudes in India, Thailand, Sumatra, and Java, although absent from the Malay Peninsula. It occurs at higher altitudes in south-west China.



INDO-AUSTRALIAN

distinctive
curved shape
of hindwings

rich colour of the wings is
produced by green scales scattered
over a black background



eyespot and tails
create a false head
to confuse predators

Time of Flight ☀

Habitat 🌿

Wingspan 8–13.5cm (3–5 in)

Family PAPILIONIDAE

Species *Papilio polytes*

Author Linnaeus


COMMON MORMON

The very variable female has three different colour forms. One form resembles the male, the others mimic different species of swallowtail. Males have a swifter flight than females.

• **EARLY STAGES** The caterpillar is green with brown markings, very similar to that of the chequered swallowtail (*P. demoleus*, see p 48). It feeds on cultivated *Citrus*, especially orange (*C. sinensis*), and lime (*C. aurantifolia*), as well as on related native plants such as *Murraya* and *Triplasia*.

• **DISTRIBUTION**

Widespread throughout India and Sri Lanka to China, Japan, Malaysia, the Philippines, and the Moluccas.



INDO-AUSTRALIAN

pale hindwing markings
continue on the forewings



band of cream
spots on the
hindwings

Time of Flight ☀

Habitat 🌿

Wingspan 9–10cm (3½–4in)

Family PAPILIONIDAE

Species *Papilio demoleus*

Author Linnaeus


CHEQUERED SWALLOWTAIL

This distinctively patterned, black and yellow butterfly has an elongated, red eyespot on the inner corner of its hindwing. It has no tails on its hindwing. It is also called the lime swallowtail.

- **EARLY STAGES** At first, the caterpillar is dark brown with white markings and it resembles a bird's dropping. Later, it becomes green with dark brown markings, that give it good camouflage. It feeds on *Citrus* and plants of the pea family.
- **DISTRIBUTION** From Iran, India, and Malaysia, to Papua New Guinea and northern Australia.



INDO-AUSTRALIAN



Time of Flight

Habitat

Wingspan 4-11 cm (3/4-4 in)

Family PAPILIONIDAE

Species *Papilio anchisiades*

Author Esper


RUBY-SPOTTED SWALLOWTAIL

This largely black species can have pink, ruby, or purplish patches on the hindwings. The butterflies mimic swallowtails of the genus *Parides*.

- **EARLY STAGES** The caterpillar is green and brown with white markings and humps on its back. It feeds on cultivated *Citrus*.
- **DISTRIBUTION** Central America and tropical South America.



NEOTROPICAL



Time of Flight

Habitat

Wingspan 6-9.5 cm (2 1/2-3 1/2 in)

Family PAPILIONIDAE

Species *Papilio salmastis*

Author Hew tson


BLUE SWALLOWTAIL

This magnificent swallowtail varies from blue, to green or bronze. Females are smaller than males, with greyish blue hindwings tinged with yellow in the centre. Blue swallowtails are on the wing all year round.

- **EARLY STAGES** The caterpillar is undescribed.
- **DISTRIBUTION** Central Zaïre to Nigeria and Liberia.



AFROTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 14-17cm (5 1/2-4 in)

Family PAPILIONIDAE

Species *Papilio dardanus*

Author Brown


MOCKER SWALLOWTAIL

The males of this species are yellow or white, with black markings. There are several female forms which mimic various species of *Danaus* (see pp.182-84). The non-mimetic female form has hindwing tails and is similar in colour to the male.

- **EARLY STAGES** The caterpillar is plump and green with white markings and orange-red scent horns. It feeds on cultivated *Citrus* and related species.
- **DISTRIBUTION** Found in Africa, south of the Sahara; also in Madagascar and the Comoros.



AFROTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 9-10.8cm (3 1/2-4 1/2 in)

Family PAPILIONIDAE

Species *Papilio cresphontes*

Author Cramer

GIANT SWALLOWTAIL


A distinctive black and yellow-coloured swallowtail, this is one of the largest species to be found in North America.

• **EARLY STAGES** The caterpillar is brown with dirty white markings. It feeds on various wild plants.

• **DISTRIBUTION** Occurs from Central America to Mexico and southern parts of the USA.



NEARCTIC
NEOTROPICAL



Time of Flight ()

Habitat

Wingspan 10-14cm (4-5 1/2 in)

Family PAPILIONIDAE

Species *Papilio antiochus*

Author Drury

AFRICAN GIANT SWALLOWTAIL


This butterfly has distinctive black and orange patterning and is the largest of the African butterflies. Its coloration is due to the high levels of cardenolide poisons it contains. It is on the wing all year.

• **EARLY STAGES** The caterpillar is apparently undescribed.

• **DISTRIBUTION** Occurs from Uganda to Zaire, Angola, and Sierra Leone.



AFROTROPICAL



Time of Flight ()

Habitat

Wingspan 15-25cm (6-10 in)

Family PAPILIONIDAE

Species *Papilio demodocus*

Author Esper

CITRUS SWALLOWTAIL


This black and yellow butterfly is tailless. It is the African counterpart of *Papilio demoleus* (see p.48), but it is generally larger with a band of black on the hindwing. It is also called the Christmas butterfly.

• **EARLY STAGES** The caterpillar feeds on cultivated *Citrus* and legumes.

• **DISTRIBUTION** Occurs in tropical Africa, and is a pest in South Africa. Also found in Madagascar.



AFROTROP. CA.



Time of Flight ☉

Habitat 🌳 🌿 🏞️

Wingspan 9–12cm (3½–4½ in)

Family PAPILIONIDAE

Species *Papilio machaon*

Author Linnaeus

SWALLOWTAIL

This butterfly has a singular bold patterning of black on yellow. The hindwings have fairly short tails and are variably marked with orange patches. In the USA this species is also known as the old world swallowtail.

• **EARLY STAGES** The caterpillar has bright green and black bands, spotted with red. It feeds on milk parsley (*Peucedanum palustre*) and other related plants.

• **DISTRIBUTION** Found in fen and meadow and in Europe, across temperate Asia to Japan. Also occurs in subarctic and Arctic regions of Canada and the USA.



HOLARCTIC



Time of Flight ☉

Habitat 🌳 🌿 🏞️

Wingspan 7–10cm (2½–4 in)

Family PAPILIONIDAE

Species *Papilio glaucus*



Author Linnaeus

TIGER SWALLOWTAIL

Males and some females of this species are yellow with tiger stripes. A female form occurs in which the ground colour is dark brown or black. This form is found most frequently in the southern parts of the species' range, where it is believed to be a mimic of the poisonous pipevine swallowtail (*Battus philenor*, see p.55). Further north the butterfly becomes smaller and paler. Tiger swallowtails have a strong, sailing flight.

• **EARLY STAGES** The plump caterpillar is green with bright yellow and black eyespots. The caterpillars when they are young, resemble bird droppings. They feed on willows (*Salix*) and cottonwoods (*Populus*). There are one to three broods a year depending on location.

• **DISTRIBUTION** This is the most widely distributed North American swallowtail, extending south from Alaska, the USA, and Canada, to the Gulf of Mexico.



NEARCTIC

Time of Flight ☀

Habitat 🌿 🌳 🌲

Wingspan 9-16.5cm (3½-6½in)

Family PAPILIONIDAE

Species *Euryides marcellus*

Author Cramer

ZEBRA SWALLOWTAIL

With its distinctive black zebra stripes and long, sword-like tails, this butterfly cannot be confused with other North American swallowtails. It is the commonest of the kite swallowtails – so called because of their triangular wings and pointed tails. Early spring specimens are paler, smaller, and have shorter tails than those that appear in the summer.

- **EARLY STAGES** The caterpillar is yellowish green with fine yellow and black cross-bands. It feeds on paw paw (*Carica*)
- **DISTRIBUTION** Widespread from eastern Canada to Florida in the USA, and the Gulf of Mexico



NEARCTIC

strongly
scalloped
hindwing
margins

red and blue
hindwing markings

striping continues right
to base of the forewings
• and body



Time of Flight ☼

Habitat 🌳 🌿 🍄

Wingspan 5–7cm (2–2½in)

Family PAPILIONIDAE

Species *Parides mona*

Author Fabricius

COMMON CLUBTAIL

Common clubtails have distinctive black and yellow markings, signalling that they are distasteful to birds. Females look similar to the males, but have broader forewings and shorter hindwing tails.

- **EARLY STAGES** The caterpillar varies in colour from reddish grey to almost black, and is marked with black spots and stripes. It feeds on the foliage of *Apocynum tomentosum*

- **DISTRIBUTION** Mostly found in tropical rainforest, but also on the plains, throughout northern India and Burma to Malaysia, Sumatra, and Java, but absent in Borneo.



INDIA AUSTRALIAN

distinctive
elongated
forewings

bold
scalloping of
hindwings

clubbed
hindwing tails

markings vary
from yellow to
orange



Time of Flight ☼

Habitat 🌳 🌿

Wingspan 9–13cm (3½–5in)

Family PAPILIONIDAE

Species *Pachliopta aristolochiae*

Author Fabricius

COMMON ROSE SWALLOWTAIL

The markings of this butterfly vary and may even be absent. The forewings can be raved with white markings. The wings are rounded in the female form. The female *Papilio polytes* (see p 47), mimics this species.

• **EARLY STAGES** The caterpillar varies from pinkish grey to black. It feeds on Pipevines (*Aristolochia*), extracting poisons from them which make it distasteful to birds.

• **DISTRIBUTION** From India and Sri Lanka through southern China and Malaysia, to the Lesser Sunda Islands



INDO-AUSTRALIAN

robust, club-shaped tails

warning red colour on head indicates it is poisonous

vivid red patch on tip of abdomen

♂

Time of flight ☼

Habitat 🌿

Wingspan 8-11cm (3¼-4½")

Family PAPILIONIDAE

Species *Guraphaena carpaton*

Author Linnaeus

BLUE TRIANGLE

This distinctive species has elongate, triangular forewings and striking bands of turquoise blue, interspersed with veining, extending over both pairs of wings. The butterfly is also called the common bluebottle.

• **EARLY STAGES** The caterpillar is green with yellow stripes along its sides and a few short spines at the front and back of the body. It feeds on a variety of plants, including camphor laurel (*Cinnamomum*).

• **DISTRIBUTION** Common from India and Sri Lanka to China, Japan, Malaysia, Papua New Guinea and Australia.



INDO-AUSTRALIAN

unusual horizontal shape

distinctive patch of pale scent scales distinguishes the male

♂

Time of flight ☼

Habitat 🌿

Wingspan 8-9cm (3¼-3½")

Family PAPILIONIDAE

Species *Pieris philenor*

Author Linnaeus

PIPEVINE SWALLOWTAIL

The male butterfly has a metallic blue sheen on the hindwings. This swallowtail is mimicked by several other butterfly species. It is also called the blue swallowtail.

• **EARLY STAGES** The caterpillar is reddish brown, with rows of black or red, fleshy tentacles on its back. It feeds on the foliage of pipevines (*Aristolochia*), and other plants.

• **DISTRIBUTION** From southern Canada to Mexico and Costa Rica.



pale, arrow-shaped markings on hindwings

NEARCTIC
NEOTROPICAL

Time of flight ☉

Habitat ● arb. sh.

Wingspan 7.5–11 in (3–4 1/2 in)

Family PAPILIONIDAE

Species *Pieris polydamas*


Author Linnaeus

POLYDAMAS SWALLOWTAIL

This golden yellow butterfly has no tails. It is dark and the hindwings usually have a green lustre. The underside is patterned with red. These swallowtails are distasteful to birds.

• **EARLY STAGES** The caterpillar is black, and feeds on pipevines (*Aristolochia*).

• **DISTRIBUTION** From northern Argentina to the West Indies, Central America, and southern parts of the USA



NEARCTIC
NEOTROPICAL

Time of flight ☉

Habitat ☿ arb. sh.

Wingspan 7–9 cm (2 1/2–3 1/2 in)

Family PAPILIONIDAE

Species *Iphiclides podalirius*

Author Scopoli

SCARCE SWALLOWTAIL


This pale yellow species has slender, transverse stripes and long tails. In some forms, the background colour is almost white and the black stripes are much heavier.

• **EARLY STAGES** The caterpillar is slug-like. Its body is green with yellow lines, often spotted with red. It feeds on blackthorn (*Prunus spinosa*).

• **DISTRIBUTION** Despite its common name, this species is widespread in Europe. Its range extends to North Africa and across temperate Asia to China.



PALAEARCTIC



Time of Flight ☀

Habitat 🌳 🌾

Wingspan 7–8cm (2½–3in)

Family PAPILIONIDAE

Species *Zerynthia rumina*

Author Linnaeus

SPANISH FESTOON


A very distinctive black and yellow butterfly with an intricate, lace-like and delicate pattern. The Spanish festoon belongs to a very easily recognized group of tailless swallowtails. It can be distinguished from other closely related festoons by the vivid and conspicuous red markings on the forewing. Spanish festoons can be seen on the wing from late winter to late spring. Females are usually larger than the males, and are a darker shade of yellow.

• **EARLY STAGES** The caterpillar is pale brown with rows of blunt, red spines along its body. It feeds on birthwort (*Aristolochia*).

• **DISTRIBUTION** This butterfly species can be found among the rough, stony hillsides of south-eastern France, Spain, and Portugal. It is particularly common around coastal regions within its habitat.



PALAEARCTIC



Time of Flight ☀

Habitat 🌳 🌾

Wingspan 4.5–5cm (1½–2in)

Family PAPILIONIDAE

Species *Lamproptera meges*

Author Zeller

GREEN DRAGONTAIL

This butterfly is easily recognized by its translucent forewings and drooping tail. The only other species in this genus (*Lamproptera curius*) can be distinguished by the presence of a transverse white band on the wings. Green dragontails resemble dragonflies in flight, and have a very rapid wingbeat. Even when resting, they vibrate their wings and, unlike the majority of butterflies, they hover over flowers while feeding.


• **EARLY STAGES** Although the caterpillar does not appear to be known, the related *Lamproptera curius* has a dark apple-green caterpillar that feeds on *Liliger cordata* foliage.

• **DISTRIBUTION** Usually found in sunlit forest clearings from India to southern China, Malaysia, the Philippines, and Sulawesi.



INDO-AUSTRALIAN

long, feather-like tails



Time of Flight ☀

Habitat 🌿

Wingspan 4-7cm (1.5-2in)

Family PAPILIONIDAE

Species *Parnassius apollo*

Author Linnaeus

APOLLO

Although the pattern of this butterfly is distinctive, it is also very variable.

It can be distinguished from similar species by the absence of red markings on the forewing. Males are smaller than females.


• **EARLY STAGES** The caterpillar is a velvety black colour with a line of orange-red spots along its sides. It is known to feed on stonecrop (*Sedum*) and houseleek (*Sempervivum*).

• **DISTRIBUTION** In mountain districts in Europe, extending into central Asia.



PALAEARCTIC

hindwing markings vary in colour from red to orange-yellow



Time of Flight ☀

Habitat 🌿

Wingspan 5-10cm (2-4in)

Family PAPILIONIDAE

Species *Cressida cressida*


Author Fabricius

BIG GREASY BUTTERFLY

The male butterfly has transparent forewings with two large, black spots on each. Freshly emerged females are dark grey with a distinctive pattern, but most of the wing scales are soon shed and the wings take on a paler, greasy appearance.

• **EARLY STAGES** The caterpillar is dark brown, often mottled with creamy white, but is variable in colour and pattern. It feeds on pipevines (*Aristolochia*)


• **DISTRIBUTION** There are two subspecies of this butterfly found in Australia. A third subspecies occurs in Papua New Guinea.



CATERPILLAR OF
CRESSIDA CRESSIDA

the male has
narrower forewings
than the female

red spots on
hindwings



dull appearance
due to loss of scales

black and red body
indicates that this is a
poisonous species



INDO-AUSTRALIAN

Time of Flight



Habitat



Wingspan 7-7.5cm (2½-3in)

Family PAPILIONIDAE

Species *Ornithoptera alexandrae*

Author Rothschild

QUEEN ALEXANDRA'S BIRDWING

This is the largest known butterfly in the world.

The males are considerably smaller than the females and are distinguishable from related species by their striking wing pattern and colours. The underside of the male hindwing is golden-yellow with black veining, and is shaded with green.

• **EARLY STAGES** The caterpillar is reddish black with bright red, fleshy, pointed tentacles and a cream-

coloured saddle marking in the middle of its body. It feeds on *Aristolochia schlecteri*.


• **DISTRIBUTION**

Confined to south-east Papua New Guinea, east of the Owen Stanley Ranges. This species is rare and is now protected.

caterpillar has brightly
coloured tentacles




CATERPILLAR OF
ORNITHOPTERA ALEXANDRAE



metallic blue,
black, and greenish
yellow colouring
on wings

bright colour of
body indicates that
it is poisonous



small, white spot
on hindwings
distinguish this
from other species

strong,
black
veining on
hindwings

pale body colour



NEOAUSTRALIAN

Time of Flight ☉

Habitat ☿

Wingspan : 7-28cm (6 1/4-11in)


Family	PAPILIONIDAE	Species	<i>Ornithoptera priamus</i>	Author	Linnaeus
--------	--------------	---------	-----------------------------	--------	----------

CAIRNS BIRDWING

This common name applies to just one of a large number of subspecies of this magnificent birdwing butterfly. Males are distinctively patterned with black and green on the upperside. The underside of the forewing is black with a turquoise centre, overlaid with black veins. The females are much larger than the males, and their wings are black with white markings. These birdwings have a strong, gliding flight.


• **EARLY STAGES** The caterpillar varies in colour from blackish brown to grey, with long, fleshy spines. It feeds on pipevine (*Aristolochia*).

• **DISTRIBUTION** From the Moluccas to Papua New Guinea, the Solomon Islands, and northern Australia.



white band
across middle
of caterpillar

CATERPILLAR OF
ORNITHOPTERA PRIAMUS




pointed tip to
forewings

large, powerful
forewings

scalloped edge
to hindwings

distinctive gold
spots are smaller
than those on the
underside

characteristic black
and yellow body



INDO-AUSTRALIAN

Time of Flight		Habitat		Wingspan	10.8–13cm (4¼–5in)
----------------	--	---------	--	----------	--------------------

Family PAPILIONIDAE

Species *Troides brookiana*

Author Wallace


RAJAH BROOKE'S BIRDWING

Although there are several named subspecies, all males are similar in appearance, with a distinctive green pattern on a black background. Females vary in colour from olive-green with white or green markings to black with coppery green markings. The hindwings of the females are often flushed with metallic-blue at the base. These birdwings have a powerful, soaring flight. Males can often be found drinking from wet mud, both sexes are attracted to flowers.

• **EARLY STAGES** The caterpillar is dark brown to grey with a lighter saddle marking in the middle of the body. It has long, tentacle-like projections which are a pale yellowish brown. The shorter "tentacles" are the same colour as the body. The head is large, black, and shiny. The caterpillar eats pipevines (*Aristolochia*).

• **DISTRIBUTION** Occurs from Malaysia to Sumatra and Borneo.

PUPA OF
TROIDES BROOKIANA



• the pupa resembles a dead leaf

typical elongated forewing shape of birdwing butterflies

striking contrast of green on solid black base



• red collar

• characteristic wing pattern is also present in some females

• jet-black body



INDO-AUSTRALIAN

Time of Flight ☉

Habitat 🌿

Wingspan 12-17 cm (4½-7 in)

PIERIDAE

THIS IS A LARGE family of more than 1,000 species of butterfly. Most of the species are predominantly white, yellow, or orange in colour and are often referred to collectively as whites, yellows, or sulphurs. Pigments that are derived from the body's waste products explain the distinct colouring, which is a feature peculiar to this family of butterflies. It is believed that

the name "butterfly" originates from a member of the Pieridae—the bright yellow brimstone (*Gonepteryx rhamni*) that was known to the early British naturalists as the butter coloured fly.

This family includes the cabbage white butterflies (*Pieris brassicae* and *Pieris rapae*), which are commonly seen in gardens, and are notorious pests.

Family PIERIDAE

Species *Appias nero*

Author Fabricius

ORANGE ALBATROSS


This most striking butterfly is probably the only species in the world that is entirely orange in colour. Females look similar to males but have a black border around the wings and a black band on the hindwing. Males are often seen drinking from the moist sand of river banks. Females are much more retiring and tend to keep high in the tree canopy. They are known to feed from the flowers of a variety of trees.

• **EARLY STAGES** Little seems to be known about the early stages of this species except that the caterpillar feeds on plants of the family Capparidaceae.

• **DISTRIBUTION** Widely distributed from northern India to Burma, Malaysia, the Philippines, and Sulawesi.



INDO-AUSTRALIAN



Time of Flight ☼

Habitat 🌿

Wingspan 7–7.5cm (2½–3in)

Family *PIERIDAE*Species *Mylothris chloris*

Author Fabricius

COMMON DOTTED BORDER

This species of butterfly has two distinct geographical forms (the race shown here is from western Africa). The upperside of the female's forewing is similar to the underside but the hindwing upperside is a pale salmon-pink. Males of the east and the South African races differ. They have the base of the forewings flushed with pink and the black markings on the hindwings reduced to black dots.

• EARLY STAGES The caterpillar

is black with transverse, reddish bands. It feeds on the foliage of various mistletoes (Loranthaceae).

• **DISTRIBUTION** Very common in woodland, savanna, parks, and gardens throughout Africa, south of the Sahara.

distinctive underside hindwing pattern on female



black markings around hindwing margins



AFRICA TROPICAL

Time of Flight ☉

Habitat 🌳 🌿

Wingspan 5.5-6cm (2¼-2½in)

Family *PIERIDAE*Species *Neopharia menapue*

Author Felder

PINE WHITE


The leading edge and apex of the forewing of this distinctive white butterfly are strongly marked with black. The hindwing is covered with a fine network of black veins; in the female these veins are more strongly marked towards the wing margins. On the underside of the hindwing, the veins are strongly outlined with black in both sexes. Pine whites are on the wing from midsummer to early autumn but are most commonly seen in late summer.

• EARLY STAGES

The caterpillar is dark green with white stripes along the back and sides, giving it effective camouflage when it feeds on pine needles.

• **DISTRIBUTION** Found in coniferous woodland from southern Canada to southern California in the USA, and Mexico.

forewings less intricately patterned than hindwings



long, slender abdomen

outer margin edged with orange or reddish pink



NEARCTIC

Time of Flight ☉

Habitat 🌲 🌿

Wingspan 4-5cm (1½-2in)

Family PIERIDAE

Species *Anaphalis java*

Author Sparrman

CAPER WHITE


In the male form the distinctive black bands on the forewings and hindwings of this butterfly are patterned with a row of white streaks and spots. There are two female forms: one similar to the male but more strongly marked; the other with black bands, and almost devoid of white markings.

• **EARLY STAGES** The caterpillar is olive-green to brown. It feeds on capers (*Capparis*) and related plants.

• **DISTRIBUTION** About ten different subspecies are recognized ranging from Java to Papua New Guinea, Fiji, Samoa, and Australia.



INDO-AUSTRALIAN



Time of Flight ☀

Habitat 🌿 🌳 🌴

Wingspan 4.5–5.5cm (1½–2¼in)

Family PIERIDAE

Species *Anaphalis aurea*


Author Fabricius

BROWN-VEINED WHITE

This pure white butterfly is strongly marked on the upperside margins of the forewings with black or blackish brown bands, patterned with large, white, elongate spots. Females of the species tend to be more heavily marked than males.

• **EARLY STAGES** The caterpillar is yellowish green with black stripes along its side. It feeds on various species of *Capparis*, *Boscia*, and *Maerua*.

• **DISTRIBUTION** This species ranges from Africa to the Middle East, and India.

AFROTROPICAL
INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌿 🌳 🌴

Wingspan 5–5.5cm (2–2¼in)

Family PIERIDAE

Species *Delias mysis*


Author Fabricius

UNION JACK

The Union Jack has distinctive black tips on the forewings, marked with four white spots. The hindwing is marked with black along the margins.

• **EARLY STAGES** The caterpillar is yellowish green with long, white hairs. Its head is black. The caterpillar feeds on mistletoe (*Viscum*).

• **DISTRIBUTION** Found in rainforests of northern Australia, Papua New Guinea, and adjacent islands.



yellow inner margins of the hindwing underside

subtle pink and grey markings to hindwing

striking slug-like pattern of red, black, and white



INDONESIA AUSTRALIA

♂ Δ

Time of Flight ♂

Habitat ♂

Wingspan 5.5–6cm (2¼–2½in)

Family PIERIDAE

Species *Delias aglata*


Author Linnaeus

RED-BASED JEZEBEL

This attractive black, white, and yellow butterfly is similar to the Malayan jeebel (*Delias nimus*), but lacks red markings on the hindwings. The striking red base to the underside of the hindwing gives this species its common name.

• **EARLY STAGES** The caterpillar is brown with yellow hairs, transverse yellow bands, and a line of black dots along the sides. It feeds on the leaves of *Nerium*.

• **DISTRIBUTION** Common in forested areas from India to Malaysia, Indonesia, and Taiwan.



rather pointed, narrow forewings

white, feather-like markings along wing margin

bright wings indicate that this species is distasteful to birds



INDONESIA AUSTRALIA

Time of Flight ♂

Habitat ♂

Wingspan 7–9cm (2¾–3½in)

Family PIERIDAE

Species *Iporia crataegi*

Author LAMPROUS


BLACK-VEINED WHITE

Apdly named, this butterfly is unlikely to be confused with any other species. Females tend to be larger and more transparent than males.


The underside of both sexes is lightly suffused with black scaling.

• **EARLY STAGES** The caterpillar is grey and hairy with a black back, covered with broad, reddish brown lines. It feeds on Hawthorn (*Crataegus monogyna*) and blackthorn (*Prunus spinosa*).

• **DISTRIBUTION** Occurs throughout mainland Europe. Range extends to North Africa, and across temperate Asia to Japan.



PALAEARCTIC



Time of Flight (1)

Habitat (1) (2) (3)

Wingspan 4-5 cm (1 1/2 - 2 in)

Family PIERIDAE

Species *Pereute leucodorsum*

Author Kollar

RED-BANDED PEREUTE


This unusual black Pierid butterfly belongs to a small genus of about ten species, all confined to South America. It can be distinguished by its relatively large size, the red band on the forewing, and the bluish grey patch on the hindwing, although all of these markings are variable in extent. The underside of the hindwing lacks the bluish patch but has a small red spot at the base. The sexes look similar.

• **EARLY STAGES** The caterpillar and foodplants of this species appear to be unknown, but related species feed on plants of the family Loranthaceae.

• **DISTRIBUTION** Widespread in South America, from Brazil to Colombia.



NEOTROPICAL



Time of Flight (1)

Habitat (1) (2) (3)

Wingspan 6-7 cm (2 1/4 - 2 3/4 in)

Family PIERIDAE

Species *Pieris brassicae*


Author Linnaeus

LARGE WHITE


Letting us can be recognized by the presence of two black spots and a black streak on the forewing. The undersides of the hindwings of both sexes are bright yellow with slight black scaling.

• **EARLY STAGES** The caterpillar is pale green, heavily spotted with black, with yellow lines along the back and sides. It feeds on cabbage (*Brassica oleracea*), completely stripping the leaves. This is a notorious agricultural pest, commonly known as the cabbage white.

• **DISTRIBUTION** Common in Europe, the Mediterranean, and North Africa.



PALEARCTIC



Time of Flight ☀

Habitat 🌿 🌳 🏡

Wingspan 5.5–7 cm (2 1/4–2 3/4 in)

Family PIERIDAE

Species *Pieris rapae*

Author Linnaeus

SMALL WHITE

This is an uninspiring but well-known and widely distributed species, distinguished by its small size and simple black wing markings. Females have a yellow hue, and two black spots on the forewing. Small whites are on the wing from spring to autumn.

• **EARLY STAGES** The caterpillar is yellowish green. It feeds on cultivated and wild cabbage (*Brassica oleracea*) and other related plants.

• **DISTRIBUTION** Widespread throughout Europe, and across temperate Asia to Japan. It also occurs in Australia and North America.



WORLDWIDE



yellow forewing tip
and leading edge

underside of
hindwing finely
dusted with
black scales

bright yellow
hindwing
underside

♂ Δ

Time of Flight ☀

Habitat 🌿 🌳 🏡

Wingspan 4.5–5.5 cm (1 3/4–2 1/4 in)

Family **PIERIDAE**Species *Leptoclelea*

Author Fabricius

PSYCHE BUTTERFLY

This small, white butterfly has black markings on the wing tips. The underside of the hindwing is fairly marked with green. The sexes are similar. They seldom fly more than 1m (3ft) above the ground.


• **EARLY STAGES** The caterpillar is pale green and feeds on *Capparis heyneana* and *Crataeva religiosa*.

• **DISTRIBUTION**

Found in bamboo thickets from India to Malaysia, into southern China, as far as Indonesia.



INDO-AUSTRALIAN



Time of Flight

Habitat

Wingspan 4-5cm (1½-2in)

Family **PIERIDAE**Species *Zerene eurydice*

Author Boisduval

CALIFORNIA DOG-FACE


A distinctive butterfly, the California dog-face gets its unusual common name from the yellow "face" on the black forewings of the male, which are sometimes shot with a beautiful reddish purple lustre. The butterfly is also known as the flying pansy. The hindwings are a rich golden-yellow, sometimes with black margins. Females are a much paler yellow. These butterflies are on the wing from spring to autumn.

• **EARLY STAGES** The caterpillar is dull green with an orange-edged, white stripe along its sides. It feeds on clover (*Trifolium*).

• **DISTRIBUTION** Widespread in the USA in California, and sometimes as far afield as western Arizona.



NEARCTIC



Time of Flight

Habitat

Wingspan 4-5cm (1½-2in)

Family: Pieridae

Species: *Catopsilia florella*


Author: Fabricius

AFRICAN MIGRANT

The African migrant is a fairly common butterfly. The males are white with a greenish yellow tint and have a small, black spot in the middle of the forewing. The female forms can also occur, some of which are almost white.

• **EARLY STAGES** The caterpillar is greenish yellow with small, black spots. It feeds on sennas (*Cassia*).

• **DISTRIBUTION** Occurs throughout Africa, and the Canary Islands. Also extends eastwards across India to Sumatra and Malaysia.

AFROTROPICAL
INDO-AUSTRALIAN

Time of Flight: ☉

Habitat: 🌳 🌿

Wingspan: 5-7cm (2-2½ in)

Family: Pieridae

Species: *Gonepteryx cleopatra*

Author: Linnaeus

CLEOPATRA

This is the most spectacular species in this small genus of distinctive yellow butterflies. The deep orange centre on the forewing of the male is characteristic, as are the slight hindwing tails.


The females are larger and much paler, with only a trace of colour. Cleopatras can be distinguished from other species by the presence of a faint orange streak on the underside of the forewing. They are on the wing from late winter to autumn, particularly in Mediterranean coastal areas.

• **EARLY STAGES** The caterpillar is bluish green, with a white stripe along the sides. It feeds on buckthorn (*Rhamnus*).

• **DISTRIBUTION** Occurs in lightly wooded areas in Spain, southern France, and Italy, to Greece, North Africa, and the Canary Islands where there is a distinct race known as the Canary Island brimstone.



PALEARCTIC



Time of Flight: ☉

Habitat: 🌳 🌿

Wingspan: 4-7cm (2-2½ in)

Family *Pieridae*Species *Proetia phobea*


Author Jones et al.

ORANGE-BARRED GIANT SULPHUR

Males of this species have a broad, orange bar on the forewing, giving rise to the common name. Females are yellow or white with brown or black markings on both the fore- and hindwing borders. The underside is variably coloured with salmon-pink and purplish hues. The butterfly is also commonly known as the yellow apricot.

• **EARLY STAGES** The caterpillar is yellowish green with transverse wrinkles and a brownish black band along the sides. It feeds on sennas (*Cassia*).

• **DISTRIBUTION** Widespread from southern Brazil to Central America and southern Florida, in the USA, where it often occurs in parks and gardens. It also strays as far north as New York.



NEOTROPICAL

traces of dark markings
on forewing tips
of male

V-shaped
marking
to forewing

dark shading
to hindwing
margin

central
spot on
forewing
of female

slight
scalloping to
hindwings

smoky-red
hindwing
borders

Time of Flight

at all

Wingspan 7-8cm (2 1/4-3 1/4 in)

Family PIERIDAE

Species *Eurema brigitta*


Author Cramer

BROAD-BORDERED GRASS YELLOW

A very distinctive little butterfly varying in colour from yellow to deep orange. The black margins of the forewing and narrower margins of the hindwing are characteristic of males of this species. Females are usually paler with more diffuse, dark markings.

• **EARLY STAGES** The caterpillar is green with a stripe on its back and a yellow stripe on its sides. It feeds on sennas (*Cassia*).

• **DISTRIBUTION** From Africa to India, China, Papua New Guinea, and Australia.

AFROTROPICAL,
INDO-AUSTRALIAN

♂

Time of Flight ☀

Habitat 🌿 🌳

Wingspan 4–5cm (1½–2in)

Family PIERIDAE

Species *Anteos clorinde*

Author Godart

YELLOW-SPOTTED GONATRYX

This large and distinctive species belongs to a small genus of mainly South American butterflies known as the mammoth sulphurs. They are rather similar in appearance to the Palearctic genus, *Gonepteryx*, but are not closely related. This butterfly can be recognized by the large, bright golden-yellow patch on the forewing of the male, and by the small, yellow-ringed black spots in the centre of each wing. Females lack the yellow forewing marking, or merely show slight traces of it.

Another common name for the butterfly is the white-angled sulphur.

• **EARLY STAGES**

Although the caterpillar appears to be undescribed, it is known to feed on senna (*Senna spectabilis*), and *Psittacanthum*.

• **DISTRIBUTION** Found from Brazil northwards to Central America, the West Indies, and the USA in southern Texas, Arizona, and Colorado.



NEOTROPICAL

thin, faint
hindwing
margin

♂

curved
wing-tips
bright golden
patch on forewing
of male

small, pointed tails

Time of Flight ☀

Habitat 🌿 🌳

Wingspan 7–9cm (2¾–3½in)

Family PIERIDAE

Species *Colias erytheme*


Author Boisduval

ORANGE SULPHUR

Females are larger than males and are more extensively marked with black on the forewing margins. Spring examples are sometimes yellow, flushed with orange in the centre of the wings.

• **EARLY STAGES** The caterpillar is dark green with a black-edged, white stripe along the sides and a pink stripe lower down. It feeds on alfalfa (*Medicago sativa*), white clover (*Trifolium repens*), and related plants.

• **DISTRIBUTION** Common in many parts of the USA, becoming scarcer in Canada and towards southern Florida.



Time of Flight ☀

Habitat 🌱 🌿 🍃

Wingspan 4-6cm (1½-2½in)

Family PIERIDAE

Species *Pontia daplidice*

Author Linnaeus

BATH WHITE

The distinctive black markings on the forewings of the bath white, particularly the large, squarish, central spot, separate this species from related European species. The pale, olive-green underside markings effectively camouflage it when at rest. Females are larger than males and have more extensive dark markings, particularly on the hindwings. Bath whites are on the wing from late winter to early autumn.

• **EARLY STAGES** The caterpillar is bluish grey with raised, black dots and yellow stripes along the back and sides. It feeds on mignonette (*Reseda lutea*), mustard (*Sinapis*), and related plants.

• **DISTRIBUTION** From central and southern Europe across temperate Asia to Japan.



Time of Flight ☀

Habitat 🌱 🌿 🍃

Wingspan 4-5cm (1½-2in)

Family **PIERIDAE**

Species *Anthocharis cardamines*

Author Linnaeus

ORANGE TIP

This butterfly is easily distinguished from related European species, which all have a yellow or yellowish white ground colour. Female orange tips have black or dark grey wing tips. The underside's delicate pattern produces a dappled effect, which camouflages the butterfly when among vegetation. Adults fly in spring and early summer.

• **EARLY STAGES** The caterpillar is pale bluish green or greyish green. It resembles seedpods of garlic mustard (*Aliaria petiolata*), Lady's smock (*Cardamine pratensis*), and other plants on which it feeds.

• **DISTRIBUTION** Meadows throughout Europe and across temperate Asia to Japan.



PALAEARCTIC

chequered hindwing margins



♂



delicate patterning produced by dark underside markings showing through

Time of flight ☀

Habitat 🌱 🌿 🍄

Wingspan 4–5cm (1½–2in)

Family **PIERIDAE**

Species *Colotis danai*

Author Fabricius

CRIMSON TIP

Females are easily distinguished by their extensive dark patterning. On the underside of both sexes the forewing tip is pale red and the hindwing is yellow with a central band of black spots. This is a variable species with both seasonal and regional forms.

• **EARLY STAGES** The caterpillar is green above, bluish white beneath, with a narrow, yellow stripe along the back. It feeds on *Conopsis*, *Cadaba*, and *Mucos*.

• **DISTRIBUTION** Widely distributed in woodland and scrub country from Africa to Iran, India, and Sri Lanka.



AFROTROPICAL
INDO-AUSTRALIAN

dark shading at inner fore- and hindwing bases



crimson tip to wing reduced in female

hindwing spots can be joined to form a black band

♂



Time of flight ☀

Habitat 🌱 🌿 🍄

Wingspan 4–5cm (1½–2in)

Family PIERIDAE

Species *Dismorphia amphione*

Author Cramer

TIGER PIERID

This unusual Pierid butterfly belongs to a large genus of about 40 species of South American butterfly that are remarkable mimics of various distasteful butterflies. The striking black, orange, and yellow patterning of both sexes, which has earned them their common name, is very variable and there are many named forms and subspecies. They are mostly seen flying along forest edges from sea level to about 1,000m (3,300ft).

• EARLY STAGES

The caterpillar is a dark, translucent green. It feeds on *Inga sapindoides*, *Inga densiflora*, and related species.

• DISTRIBUTION

Widespread and common in South and Central America, and also in the West Indies, and Mexico.

unusual wing shape for this family

large translucent white patch on male hindwing

bands of yellow spots on each forewing

long, slender body



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 4-4.5cm (1½-1¾in)

Family PIERIDAE

Species *Leptidea sinapis*

Author Linnaeus

WOOD WHITE

A delicate white butterfly, the wood white belongs to a small group of European species with long, slender abdomens. It is distinguished by its relatively small size and pure white wings with grey markings. Males have a distinctive grey spot at the tip of the forewing, whereas females simply have a few pale grey streaks. The underside is tinted with yellow, and the hindwings are patterned with grey along the veins. The butterflies have a weak, fluttering flight close to the ground.

• **EARLY STAGES** The caterpillar is yellowish green with a dark line along the back, and yellow lines along the sides. It feeds on the foliage of various wild plants of the pea family, particularly *Lathyrus*.

• **DISTRIBUTION** Occurs locally in wooded country in many areas of Europe, including the British Isles.

♂

♂ ♀

pale yellow tints to underside of forewings

slender body is typical of this group



PALEARCTIC

Time of Flight ☀

Habitat 🌿

Wingspan 4-5cm (1½-2in)

Family **PIRIRIDAE**Species *Hebemonia glaucippe*Author **Linnaeus**

GREAT ORANGE TIP

This handsome species is the largest Pierid butterfly in Asia. Females are much darker than males and have an extensive pattern of dark spots on the hindwings. The undersides of both sexes are similar, but strikingly different from the uppersides. The entire hindwing and the outer half of the forewing are delicately patterned with shades of brown and buff, creating the appearance of a dead leaf when the butterfly rests on the ground with its wings closed. Great orange tips have a fast and powerful flight. Males are often seen congregating on moist ground by streams, but females seldom leave the shelter of the forest.


• EARLY STAGES

The caterpillar is green with a pale stripe along each side. It feeds on *Crataeva religiosa* and *Capparis moonii*.

• **DISTRIBUTION** Occurs from India to Malaysia, China, and Japan.



IN SOUTH-ASIAN
PALEO-ARCTIC



Time of Flight



Habitat



Wingspan 7-10cm (2½-4in)

LYCAENIDAE

THIS is a large family of more than 5,000 small, brightly coloured butterflies that occur throughout the world, but mostly in tropical and subtropical regions. The sexes often differ in coloration, and the undersides usually differ from the upper surfaces. There are several distinct groups of Lycaenidae. One large group, the hairstreaks, have tails and bright

eyespot markings on their hindwings, which create a false "head" at the rear, thus diverting attackers from this area.


The caterpillars are often described as "slug-like". Many draw their head back into the body when threatened or resting, and some of them secrete a sweetish substance, which is very attractive to various species of ant.


Family	LYCAENIDAE	Species	<i>Euphyas brassolis</i>	Author	Westwood
--------	------------	---------	--------------------------	--------	----------

MOTH BUTTERFLY

This very large orange and black butterfly has an almost moth-like appearance and behaviour, hence its common name. The males are much more extensively marked with black than the females.

- **EARLY STAGES** The caterpillar is smooth, elliptical in shape, and very flattened. It lives in the nests of tree ants, and feeds on the larvae. When the butterfly emerges from the pupa, the wings and body are covered with highly adhesive scales, which will stick to any ant that may attack it
- **DISTRIBUTION** From India, across South-east Asia to northern Australia.



Time of Flight	 	Habitat		Wingspan	6-9cm (2 1/2-3 1/2 in)
----------------	---	---------	---	----------	------------------------

Family LACERTIDAE

Species *Liptena simplica*

Author Möschler

MÖSCHLER'S LIPTENA


This species belongs to a genus of more than 50 species living in the tropics of Africa. It has satin-white wings with broad, black borders to the front of the forewings. The underside is similarly marked, but there is an additional black band on the hindwings. The sexes look similar.

• **EARLY STAGES** The hairy caterpillar feeds on various lichens and fungi.

• **DISTRIBUTION** Widespread in Africa, south of the Sahara.



AFRICA TROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 2.5–3cm (1 1/4 in)

Family LACERTIDAE

Species *Spalgis epetis*

Author Westwood

APFELY


Male apfelys have pointed, triangular forewings with one white marking, while those of the females are broader and more rounded. The hindwings of females are a paler brown.

• **EARLY STAGES** The caterpillar is undescribed, but it is known to feed on scale insects and mealy bugs.

• **DISTRIBUTION** From India and Sri Lanka, through Malaysia to Sulawesi.



INDO-AUSTRALIAN



Time of Flight ☀

Habitat 🌿

Wingspan 2–5cm (3/4–1 1/2 in)

Family LACERTIDAE

Species *Lachnocnema limulus*


Author Fabricius

WOOLLY LEGS

The upperside of the male butterfly is entirely blackish brown while the female has large patches of white or bluish white. The underside of both sexes is patterned with brown, with metallic scales on the hindwings. The legs are very hairy, hence the common name.

• **EARLY STAGES** The hairy, buff coloured caterpillar feeds on aphids and scale insects.

• **DISTRIBUTION** Tropical Africa, south of the Sahara.



AFRICA TROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 2–3cm (3/4–1 1/4 in)

Family LYCAENIDAE

Species *Megalaopis zynna*

Author Westwood

SMALL HARVESTER

Easily recognizable by its strong, black forewing markings, this butterfly also has unusually shaped hindwings. The underside of this species lacks the strong, dark forewing markings that are evident on the upperside, but these show through as greyish shading. The sexes of this species are similar.

• **EARLY STAGES** The caterpillar is predacious and feeds on the nymphs and adults of various plant bugs.

• **DISTRIBUTION** Western tropical Africa, south of the Sahara



AFROTROPICAL



• tear-shaped hindwings

• broken hindwing margins

Time of Flight ☀

Habitat 🌿

Wingspan 3–4cm (1¼–1½in)

Family LYCAENIDAE

Species *Stelenus boisduvali*

Author Moore

BOISDUVAL'S MILETUS


This rather drab-coloured butterfly resembles the apelfly (*Spalgis epus*, see p.77) in that the sexes are distinguished by differing wing shape and the extent of white markings. The Boisduval's miletus does have longer antennae and a more slender body.

• **EARLY STAGES** The caterpillar is undescribed, but is known to feed on aphids.

• **DISTRIBUTION** Widely distributed, mainly in lowland rainforests, from Java to Borneo, and Papua New Guinea.



INDO-AUSTRALIAN



pointed forewings
• of male

Time of Flight ☀

Habitat 🌿

Wingspan 3–4cm (1¼–1½in)

Family LYCAENIDAE

Species *Ferrisia tarquinius*

Author Fabricius

HARVESTER

This distinctive butterfly varies in colour from orange-brown to pale orange-yellow with blackish brown forewing borders, with other markings. The sexes look similar.

• **EARLY STAGES** The greenish brown caterpillar is known to feed on woolly aphids. It covers itself with loosely spun webbing, to which the empty shells of its prey are attached.

• **DISTRIBUTION** Occurs in alder swamps and wet woodland in North America from Canada to Florida and Texas.



NEARCTIC

distinctive black
• markings on forewings



Time of Flight ☀

Habitat 🌿

Wingspan 2.5–3cm (1–1½in)

Family LYCAENIDAE

Species *Loxura atymus*

Author Scott

YAMFLY


A very distinctive butterfly, the yamfly is orange-red with strong black margins to the forewings. The hindwings taper strongly to a fairly robust tail. The sexes are similar, but females are slightly darker on the hindwings. The underside is orange-yellow with faint, dark markings.

These butterflies fly high above the ground.



• **EARLY STAGES** The caterpillar is green with ridges along the back. It feeds on the young shoots of yam (*Dioscorea*) and *Smilax*. The caterpillars are often attended by red ants.

• **DISTRIBUTION**

Occurs in lowland forest and waste and from India and Sri Lanka to Malaysia and the Philippines.



INDO-AUSTRALIAN



• dark brown border to hindwings

• distinctive lobe at base of hindwings

Time of flight ☀

Habitat 🌳 🦋

Wingspan 3–4cm (1¼–1½ in)

Family LYCAENIDAE

Species *Chloroda jent*

Author Fabricius

COMMON IMPERIAL


Both sexes of this distinctive hairstreak are dark blackish brown above with white tails. The wings of males are often shot with purple, while females have more white on the hindwings. The underside is white with the forewings shaded an orange-brown colour; the hindwings are lined and spotted with black.

• **EARLY STAGES**

The caterpillar varies from pink to green. It has brown markings, and six protrusions on its back.

• **DISTRIBUTION**

Common in forested areas at various altitudes from India and Sri Lanka, to Malaysia and Borneo.



• two eyespots either side of hindwing tails



• double hindwing tails, one much smaller than the other



INDO-AUSTRALIAN

Time of flight ☀

Habitat 🌳 🦋

Wingspan 4–4.5cm (1½–1⅞ in)


Family	LYCAENIDAE	Species	<i>Talmenus eucorotus</i>	Author	Dunovan
--------	------------	---------	---------------------------	--------	---------

COMMON IMPERIAL BLUE

All nine species of this genus come from Australia. This is a particularly beautiful species, with metallic-blue scaling on the upperside, and a distinctive underside pattern of black and orange brown lines on a buff background. In one subspecies, the blue upperside patches are replaced by greenish white.

• **EARLY STAGES** The caterpillar is apparently undescribed, but is known to feed on acacia and the waxy secretions of scale insects. It is gregarious, and is attended by colonies of black ants. The pupae are formed in webs spun by the fully grown caterpillars.

• **DISTRIBUTION** Occurs throughout eastern and south-eastern Australia.



Time of flight	☉	Habitat	☐	Wingspan	3-4cm (1¼-1½in)
----------------	---	---------	---	----------	-----------------


Family	LYCAENIDAE	Species	<i>Graphula isocrates</i>	Author	Fabricius
--------	------------	---------	---------------------------	--------	-----------

COMMON GUAVA BLUE

Males of this species are dark purplish blue, while females are a pale brown with a small, orange spot in the centre of each forewing, and a black and orange eyespot at the base of the hindwing tails. The underside is pale buff with darker brown scalloped bands and white vertical lines.

• **EARLY STAGES** The caterpillar is apparently undescribed, but is known to feed inside the fruit of pomegranate (*Punica granatum*) and guava (*Psidium*). The pupae are later formed inside the shell-like remains of the eaten fruit.

• **DISTRIBUTION** Widespread and common from India to Sri Lanka and Burma. It frequents the plains, and also occurs up to an altitude of 2,000m (6,560ft) in the Himalayas.



Time of flight	☉	Habitat	☐	Wingspan	3-5cm (1¼-2in)
----------------	---	---------	---	----------	----------------

Family LYCAENIDAE

Species *Dendoris antalas*

Author Hopffer

BROWN PLAYBOY

The upperside of this butterfly is a delicate, pinkish brown, with an iridescent, purplish sheen which can be seen in certain lights. Some specimens are almost white. The underside is pale brown with dark brown and white lines.

• **EARLY STAGES** The caterpillar of this species is apparently undescribed, but is known to feed on the fruits of *Crotalaria* and acacia.

• **DISTRIBUTION** Common in Africa's scrubland and savanna.



AFROTROPICAL



• lobe bears large, round, black spot

Time of Flight ☀

Habitat 🌳 🌾 🌿

Wingspan 2.5–3cm (1–1¼in)

Family LYCAENIDAE

Species *Strymonda eulimn*

Author Knab

WHITE-LETTER HAIRSTREAK

Both the common and scientific names refer to the white "W" on the underside of the hindwing.

The uppersides of both sexes are blackish brown.

• **EARLY STAGES** The caterpillar is coloured yellowish green with dark green lines and diagonal markings, which are sometimes tinged with a pinkish colour. It feeds on elm (*Ulmus*).

• **DISTRIBUTION**

This butterfly is distributed throughout Europe, and across temperate Asia to Japan.



PALEARCTIC



uniform colour of forewings

• trace of orange eyespot

Time of Flight ☀

Habitat 🌳 🌾 🌿

Wingspan 3–4cm (1¼–1½in)

Family LYCAENIDAE

Species *Spindasis natalensis*

Author Westwood

NATAL BARRED BLUE

The upperside of this pretty species is suffused with blue, and barred with blackish brown. By contrast, the underside is creamy white with spectacular bars of metallic-silver, edged with reddish brown or black. Females are larger than males, and have slightly duller colouring.


• **EARLY STAGES** The caterpillar is apparently undescribed, but it feeds on *Mundulea* and *Vigna*.

• **DISTRIBUTION**

Scrubland from South Africa to Mozambique and Zimbabwe.



AFROTROPICAL



broken orange triangle at forewing tip

unusual double lotus

Time of Flight ☀

Habitat 🌳 🌾 🌿


Wingspan 2.5–4cm (1–1½in)

Family	LYCAENIDAE	Species	<i>Ogyris genoveva</i>	Author	Hewitson
--------	------------	---------	------------------------	--------	----------

GENOVEVA AZURE

Males vary from dull violet-brown to deep purplish blue, while the much larger females are blackish brown with metallic blue patches.

- **EARLY STAGES** The caterpillar is yellowish brown with darker markings and has a flattened appearance. It feeds on mistletoe (*Amymma*).
- **DISTRIBUTION** Widespread in eastern and south-eastern regions of Australia



INDO-AUSTRALIAN


Time of flight		Habitat		Wingspan	4.5–5.7cm (1 1/4–2 1/4in)
----------------	--	---------	--	----------	---------------------------

Family	LYCAENIDAE	Species	<i>Ogyris abrola</i>	Author	Westwood
--------	------------	---------	----------------------	--------	----------

DARK PURPLE AZURE

The common name for this butterfly refers to the attractive colour of the male of the species, which is deep purplish blue with black borders. By contrast, the larger female is blackish brown with large, rounded, yellow patches on the forewings.

- **EARLY STAGES** The caterpillar is reddish or pinkish brown with a dark brown line down the back, which is marked with pink or brown. It feeds on mistletoe (*Loranthus*), which grows on eucalyptus.
- **DISTRIBUTION** This species is widespread in south-eastern Australia.



INDO-AUSTRALIAN

Time of flight		Habitat		Wingspan	4–4.5cm (1 1/4–1 1/2in)
----------------	--	---------	--	----------	-------------------------

family LYCAENIDAE

Species *Hypochrysops ignita*

Author Leach

FIERY JEWEL

The upper surfaces of all wings have broad borders. The centres of the forewings are azure and those of the hindwings are indigo. The fiery red and blue underside gives rise to its name.

- **EARLY STAGES** The caterpillar feeds on acacia, eucalyptus, and various other plants.


• **DISTRIBUTION**

Widespread throughout Australia and Papua New Guinea.

black and white fringes



silvery white underside of body



INDO-AUSTRALIAN

Period of Flight ☀

Habitat 🌿

Wingspan 2.5–3cm (1–1½in)

family LYCAENIDAE

Species *Scaptis alpharus*

Author Cramer

ORANGE-BANDED PROTEA

The upperside is marked with red bands on all the wings. On the underside the red colour is restricted to a triangle on the forewings. Both the fore- and hindwings are slightly scalloped.

- **EARLY STAGES** The caterpillar is a pale grey colour with bluish spots. It can be found feeding inside the lower heads of sugarcushes (*Protea*).

• **DISTRIBUTION**

Widespread throughout dry and mountainous country in South Africa.



AFROTROPICAL



chequered wing fringes

characteristic small tails

Period of Flight ☀

Habitat 🌿

Wingspan 3–4cm (1¼–1½in)

family LYCAENIDAE

Species *Lajuria cippus*


Author Fabricius

PEACOCK ROYAL


The colour of the male gives this species its name. Females are paler and have more rounded wings. The underside is grey with black lines, with an orange and black eyespot on the hindwings.

- **EARLY STAGES** The caterpillar is brown with pinkish markings. It feeds on mistletoes (*Dendrophthoe*, *Loranthus*).

- **DISTRIBUTION** This species of butterfly is found in India, Sri Lanka, across to southern China, Malaysia, as far as the island of Borneo.



INDO-AUSTRALIAN



long, narrow hindwings of male

slender tails on both sexes

Period of Flight ☀

Habitat 🌿

Wingspan 3–4.5cm (1¼–1½in)

Family LYCAENIDAE

Species *Chrysonephyrus syla*

Author Kollar

SILVER HAIRSTREAK

Males are metallic golden-green with narrow, brown borders. Females have purplish blue forewings with broad, black margins. The hindwings are dark brown with greenish blue rays towards the margins. The common name derives from the silvery underside of both sexes, which has brown markings and orange and black eyespots at the tail bases.

• **EARLY STAGES** The caterpillar is apparently undescribed, but is known to feed on oak (*Quercus*)

• **DISTRIBUTION** Between 1,800 and 3,500m (5,900–11,480ft) in the Himalayas.



PALEARCTIC
INDO-AUSTRALIAN

• broad black
margin in
hindwings



♂



• characteristic
small, slender tails

• white,
transverse
bar on
forewings
of female

Time of Flight ☉

Habitat ▲ ▼

Wingspan 4–4.5cm (1½–1½in)

Family LYCAENIDAE

Species *Bindakara proides*

Author Fabricius

PLANE BUTTERFLY

Males of this species are blackish brown with white tails. Females are a paler or reddish brown with a large, black spot at the base of the tails. The underside of this butterfly is pale brown with darker bands and spots.

• **EARLY STAGES** The hairy caterpillar is dark brown and marked with yellowish white. It feeds inside fronds of creepers or vines (*Salacia*)

• **DISTRIBUTION** From India and Sri Lanka, through Malaysia to Papua New Guinea and northern Australia.



INDO-AUSTRALIAN



♀

• characteristic
lobes at base
of hindwing



♂

• narrow patch of
metallic-blue on
margin of hindwings

• delicate,
silvery white
hindwing tails

Time of Flight ☉

Habitat 🌿

Wingspan 4–4.5cm (1½–1½in)

Family LYCAENIDAE

Species *Porcellio thysbe*

Author Linnaeus

COMMON OPAL


The opalescent blue that gives this butterfly its common name is more extensive in the male than the female. Females are mainly orange with black markings.

• **EARLY STAGES** The caterpillar is green with dark lines along the back. It feeds on *Zygophyllum* and numerous other plants of sand grass and.

• **DISTRIBUTION** Occurs in dry, sandy areas; common in dunes in South Africa.



AFROTROPICAL



Time of Flight ☉

Habitat ☐

Wingspan 2.5-3cm (1-1 1/8 in)

Family LYCAENIDAE

Species *Hemistaneus exilis*

Author Hefter

AZURE HAIRSTREAK

Males have bright violet-blue wings with blackish brown borders. Females are less vivid and have broader, paler wing margins. In contrast, the underside of both sexes is greyish white, with lines of brownish red. The hindwings have two tails, each with a turquoise and black eyespot at its base.


• **EARLY STAGES**

Unrecorded, but it feeds on mistletoe (Loranthaceae).

• **DISTRIBUTION** Occurs in scrubland savanna and forests in tropical and southern Africa.



AFROTROPICAL



Time of Flight ☉

Habitat ☐

Wingspan 3-4cm (1 1/4-1 1/2 in)

Family LYCAENIDAE

Species *Rapala taenias*

Author Fabricius

COMMON RED FLASH

The male has coppery red wings. Females are pale brown. The underside is pale buff with white lines and a black and orange eyespot at the base of the hindwing tails.


• **EARLY STAGES** The caterpillar is red or brownish yellow in colour with black markings and two stripes on the back.

• **DISTRIBUTION**

Widespread in forests from India and Sri Lanka, to Malaysia, and the Lesser Sunda Islands.



INDO-AUSTRALIAN



Time of Flight ☉


Habitat ☐

Wingspan 2-4cm (3/4-1 1/2 in)

Family LYSAEINIDAE	Species <i>Mimacraea marshalli</i>	Author Turchin
MARSHALL'S FALSE MONARCH <p>This species is a mimic of <i>Danais chrysippus</i> (see p. 187). The uppersides of both the fore- and hindwings are orange with black margins. The underside is similar to some <i>Acrata</i> species. The sexes are similar.</p> <ul style="list-style-type: none"> • EARLY STAGES The hairy caterpillar feeds at night on lichens growing on tree trunks. • DISTRIBUTION Forests of eastern and central Africa, from Mozambique to Kenya and Zaire 		
Time of Flight ☉	Habitat 🌳	Wingspan 4.5–5.5cm (1 3/4–2 1/4in)



AFROTROPICAL



Family LYCAENIDAE	Species <i>Quercusia quercus</i>	Author Linnaeus
PURPLE HAIRSTREAK <p>The upperside of the male is deep purple with black borders. Females are blackish brown with vivid patches of purple. The underside of both sexes is pale greyish brown with white lines.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is reddish brown with dark brown markings. It feeds on the flower buds and foliage of oak (<i>Quercus</i>). • DISTRIBUTION Occurs from Europe to North Africa and temperate Asia. 		
Time of Flight ☉	Habitat 🌳	Wingspan 2.5–3cm (1–1 1/4in)



PALAARCTIC



• splash of bright purple on female forewings

small tail present on hindwings

Family LYCAENIDAE	Species <i>Palaecotryphane astrophote</i>	Author Linnaeus
PURPLE-EDGED COPPER <p>The deep coppery red males have black borders and are shot with iridescent purple on the hindwings. The females are less vivid and lack the purple sheen. The hindwings of the female are coloured brown with an orange spotted border. The underside of both sexes is grey with an orange band on the hindwings and an orange centre to the forewings.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is green, and feeds on docks (<i>Rumex</i>) and knorgrass (<i>Polygonum</i>). • DISTRIBUTION Occurs in boggy areas across much of Europe and temperate Asia, to Siberia. 		
Time of Flight ☉	Habitat 🌳	Wingspan 3–4cm (1 1/4–1 1/2in)



PALAARCTIC



black spots and dark veining on forewings

traces of orange band

Family LYCAENIDAE

Species *Amblypodia catta*

Author Hewison

LEAF BLUE

Males are a dull purplish blue with a black border. Females are either blackish brown over the entire upperside or have large patches of brilliant metallic blue on the forewings and smaller patches on the hindwings.


The underside is patterned with brown and resembles a dead leaf when the butterfly is at rest.

• **EARLY STAGES** The caterpillar is undescribed, but is known to feed on young shoots of a climbing shrub (*Olea scandens*).


• **DISTRIBUTION** Occurs from India and Sri Lanka, to Malaysia and Java.



INDO-AUSTRALIAN



♀



♂

• rounded hindwings are characteristic of this group

• short, pointed tails and inner lobes

Time of Flight



Habitat



Wingspan 4.5–5 cm (1 7/8–2 in)

Family LYCAENIDAE

Species *Myriana selenus*

Author Fabricius

FIGTREE BLUE


This beautiful, long-tailed butterfly is distinctively patterned with brown and metallic blue. Females are similar to males, but are larger and have broader, orange-brown bands to the forewings, with less blue on the hindwings. The underside of both sexes is orange-brown with a single transverse line on the hindwings.

• **EARLY STAGES**


The caterpillar is green with white spots. It feeds on the foliage of fig trees (*Ficus*).

• **DISTRIBUTION**

Widespread in tropical and subtropical Africa



AFROTROPICAL



♀

• distinctive, long tails



♂

• male has larger patches of blue on wings than female

• triangular shaped forewings

• slightly scalloped hindwings

Time of Flight



Habitat




Wingspan 3–4 cm (1 1/4–1 1/2 in)

Family	LYCAENIDAE	Species	<i>Thecla cororua</i>	Author	Hewson
--------	------------	---------	-----------------------	--------	--------

HEWITSON'S BLUE HAIRSTREAK

Females differ from the males by the broader, black borders to the wings and a large, brick-red patch at the base of the hindwing tails. The underside is dark green with a black line extending over fore- and hindwings. This species is one of many South American Lycaenid butterflies incorrectly placed in the genus *Thecla*, that still need to be more accurately classified.

- **EARLY STAGES** Nothing is known of the caterpillar or its foodplants.
- **DISTRIBUTION** Occurs from tropical South America to Mexico.




Time of Flight	☀	Habitat	🌿	Wingspan	4.5–6cm (1½–2½in)
----------------	---	---------	---	----------	-------------------

Family	LYCAENIDAE	Species	<i>Thecla betulae</i>	Author	Linnaeus
--------	------------	---------	-----------------------	--------	----------

BROWN HAIRSTREAK

Males lack the strong, orange markings on the forewing, although traces of orange may still remain.

- **EARLY STAGES** The caterpillar is green with yellowish lines.
- **DISTRIBUTION** Europe to temperate Asia.



Time of Flight	☀	Habitat	🌿	Wingspan	3–4cm (1¼–1½in)
----------------	---	---------	---	----------	-----------------

Family LYCAENIDAE

Species *Atlides halesus*

Author Cramer

GREAT PURPLE HAIRSTREAK


This species is unique in North America. Females are larger than males, duller blue with broader borders. The underside is purplish grey with red spots at the base of the wings. The abdomen is bright red underneath. Butterflies are on the wing from late winter to mid autumn.

• **EARLY STAGES** The caterpillar is green with a dark stripe on the back and a yellowish stripe along the sides. It feeds on mistletoe (*Phoradendron*).

• **DISTRIBUTION** North and South America



NEARCTIC



• unusual shaped forewings of male



• distinctive patch of metallic scales on the hindwings of both sexes

• this butterfly has one or two hindwing tails present

Time of Flight ☞

Habitat 🌳

Wingspan 2.5-4cm (1-1.5in)

Family LYCAENIDAE

Species *Funaria atala*

Author Poey

THE ATALA

This exotic blue butterfly lacks hindwing tails. The forewings of the male are suffused with metallic-greenish blue scaling, except for the borders and wing veins. The underside is black with three rows of metallic spots and a red hindwing spot.

• **EARLY STAGES** The caterpillar is red with yellow spots along its length.

• **DISTRIBUTION**



From southern Florida to the Greater Antilles.

• characteristic rounded forewing margins



• distinctive red abdomen

• row of metallic blue dots around outer hindwing margins





NEOTROPICAL

Time of Flight ☞

Habitat 🌳

Wingspan 4-4.5cm (1.5-1.75in)


Family LYCAENIDAE	Species <i>Stymon melinus</i>	Author Hübner
<p>GREY HAIRSTREAK</p> <p>Males are slate-grey with a distinctive orange spot marked with black on the hindwing. Females are similar, but browner in colour.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is green with diagonal, white or mauve markings on the sides. It feeds on many plants, including maize (<i>Zea mays</i>) and cotton (<i>Gossypium</i>). • DISTRIBUTION Occurs from southern Canada to Central America and north-western South America. 		
Time of Flight ☀	Habitat 🌿 🌳 🏞️	Wingspan 2.5–3cm (1–1.2 in)

NEARCTIC
NEOTROPICALblack and orange markings
at bases of hindwing tails

Family LYCAENIDAE	Species <i>Callotrochus erlo</i>	Author Linnaeus
<p>GREEN HAIRSTREAK</p> <p>The upperside of this common hairstreak is a dull brown. Males can be distinguished by the small, oval patch of scent scales on the forewing. Both sexes have a beautiful, green underside.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is green with a dark line down the back and oblique yellow and green markings on either side. It feeds on gorse (<i>Ulex</i>), broom (<i>Cytisus scoparius</i>), and other herbs and shrubs. • DISTRIBUTION Widespread in Europe, ranging to North Africa and temperate Asia. 		
Time of Flight ☀	Habitat 🌿 🌳 🏞️	Wingspan 2.5–3cm (1–1.2 in)



PALAEARCTIC

scalloped edge
to hindwing is less
distinct than in female

Family LYCAENIDAE	Species <i>Lycaena phlaeas</i>	Author Linnaeus
<p>SMALL COPPER</p> <p>This little butterfly is one of the commonest species in the northern hemisphere. The forewings are bright orange-red with black spots and dark grey borders. The hindwings are predominantly dark grey.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is green and variably marked with purplish pink. It feeds on dock (<i>Rumex</i>). • DISTRIBUTION Europe to Africa and across temperate Asia to Japan. Also in North America. 		
Time of Flight ☀	Habitat 🌿 🌳 🏞️	Wingspan 2.5–3cm (1–1.2 in)



HOLARCTIC

black
forewing
markings,
variable
in extentbroken,
orange-red line

Family LYCAENIDAE

Species *Lycaena dispar*

Author Haworth

LARGE COPPER


Males of this magnificent species are a brilliant orange-red with narrow, black borders and a single black spot in the centre of the forewing. Females are duller in colour and have broader, black borders and a row of black spots on the forewing. The hindwing underside of both sexes is a beautiful, pale bluish grey with black spots and an orange band.

• **EARLY STAGES** The caterpillar of this species is bright green and covered with small, white, raised spots. It feeds on water dock (*Rumex hydrolypethum*) and related species.


• **DISTRIBUTION** Large coppers occur from Europe, into temperate Asia.



PALEARCTIC



♀



♂

• black spots along hindwing margin

• characteristic arrangement of pale-ringed, black spots

• female hindwings much duller than those of male

Time of Flight ☀

Habitat 🌿

Wingspan 3.4cm (1¼–1½in)

Family LYCAENIDAE

Species *Arhopala amantes*

Author Hewson

LARGE OAK BLUE


The males of this striking species are coloured a deep metallic-blue with narrow, black borders, while the females are an intense metallic-blue with much broader, black borders. In contrast, the undersides of both sexes are greyish brown with brown lines and irregular spots, producing a confusing camouflage pattern when the butterfly is at rest. These butterflies often gather together in large numbers on nutmeg (*Myristica*) trees and cinnamon (*Cinnamomum*) trees.

• **EARLY STAGES** The caterpillar appears to be undescribed, but both the caterpillar and the pupa are attended by green tree ants.

• **DISTRIBUTION** From northern India to Sri Lanka, Malaysia, and Timor. Common in the Himalayas at altitudes of up to 1,500m (4,920ft).



INDO-AUSTRALIAN



♂

• broad, black inner margin to hindwing

• small tail on hindwing

Time of Flight ☀

Habitat 🌿

Wingspan 4.5–5.5cm (1½–2¼in)

Family LYCAENIDAE

Species *Parthenocissus m-album*



Author Boisduval & Le conte

WHITE "M" HAIRSTREAK

Males of this species are a brilliant, iridescent blue with black borders on the upperside. Females are similar but larger and less brightly coloured. On the underside of both sexes is a thin, white line that runs across both fore- and hindwings and forms an "M" shape near the tails. The hindwings have a black and orange eyespot on the underside. These fast flying butterflies are on the wing from late winter to mid autumn.

• **EARLY STAGES** The caterpillar of this species is light yellow with a darker stripe along its back and diagonal bars along its sides. It feeds on oak (*Quercus*). There are normally one or two broods a year.

• **DISTRIBUTION** Occurs from Iowa and Connecticut in the USA, south to Mexico and the mountainous regions of Guatemala.



black and orange eyespot on hindwings



NEARCTIC
NEOTROPICAL

Time of Flight ☀

Habitat 🌳 🌿

Wingspan 2.5–3cm (1–1½in)

Family LYCAENIDAE

Species *Lamides alata*

Author F. de cler

METALLIC CAERULEAN

This butterfly is one of several similar species from South-east Asia with distinctive, metallic, pale blue wings, finely lined with white. This species can be recognized by the characteristic spots on the margin of the hindwings. Females are generally darker than males and have much broader, dark bands on the forewings. The underside is brown with white wavy lines and a black and orange eyespot near the hindwing tails.

• **EARLY STAGES** The caterpillar is known to feed on the flowers and young fruit of cardamom (*Elettaria cardamomum*), and is sometimes a minor pest. It is apparently undescribed, but the caterpillar of the closely related common caerulean (*Lamides celona*) is a dull reddish green, covered with small, white, raised spots. It is attended by ants.

• **DISTRIBUTION** Widespread in wooded, hilly localities from India and Sri Lanka, to Burma, and Malaysia.



single hindwing tails

distinctive black spot at base of hindwing tails



INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌳 🌿

Wingspan 3–4.5cm (1¼–1½in)

Family LYCAENIDAE

Species *Aibuhia orbitulus*

Author De Prunner

ALPINE ARGUS

Males are a deep blue with narrow black borders. Females are dark brown. The underside is pale brown with black spots on the forewings and white patches on the hindwings.

• **EARLY STAGES** The green caterpillar feeds on milk vetches (*Astragalus alpinus* and *A. frigidus*).

• **DISTRIBUTION**

Occurs in alpine meadows of Norway and Sweden. Also in mountainous areas of temperate Asia.




♀

narrow, black borders to wings of male



♂

white wing patches



PALAEARCTIC

Time of Flight ☀

Habitat ▲

Wingspan 2.5–3cm (1–1¼ in)

Family LYCAENIDAE

Species *Everes corymbus*

Author Godart

EASTERN TAILED BLUE

Males are purplish blue with narrow black borders, while females are slate grey, sometimes shot with blue. The underside is greyish white with a curved row of dark grey spots and hindwing eyespots.

• **EARLY STAGES** The caterpillar is usually dark green with brown stripes and pale green stripes on the sides. It feeds on clover (*Trifolium*).

• **DISTRIBUTION** Eastern regions from southern Canada to Central America.

NEARCTIC
NEOTROPIC AM

♀

grey and white wing fringes

two orange and black spots on each hindwing

Time of Flight ☀

Habitat 🌱 🌿

Wingspan 2–2.5cm (¾–1 in)

Family LYCAENIDAE

Species *Glaucopsyche alexis*

Author Poda

GREEN-UNDERSIDE BLUE

Unlike the male, the female is dark brown, sometimes with a bluish suffusion near the wing bases. The distinctive feature is the greenish blue base of the wings' undersides.

• **EARLY STAGES** The caterpillar is green or brown in colour, with a dark line along the back and black stripes along the sides. It is known to feed on *Astragalus* and *Cytisus*.

• **DISTRIBUTION** This butterfly occurs in southern and central Europe, and temperate Asia.



PALAEARCTIC



♂

narrow brown wing borders of male

Time of Flight ☀

Habitat 🌱 🌿

Wingspan 2.5–4cm (1–1½ in)

Family LYCAENIDAE

Species *Iolana iolas*

Author Ochsenheimer

IOLAS BLUE

The beautiful, purplish blue males of this species have an iridescent sheen. Females are larger, darker and have broad, greyish brown borders and black dots around the margin of the hindwing. The underside is pale buff with white-ringed, black spots. The bases of the wings are sometimes suffused with blue.

• **EARLY STAGES** The caterpillar is purplish pink and feeds inside the pods of bladder senna (*Colutea arborescens*).

• **DISTRIBUTION** Rocky areas or open woodland, up to an altitude of 2,000m (6,560ft) in southern and eastern Europe, Turkey, Iran, and North Africa.



PALEARCTIC

narrow, dark
wing borders
of males



♂



marginal spots
show through
faintly on the
underside



♀

Time of Flight ☼

Habitat ▲ ● ●

Wingspan 3-4cm (1 1/2-1 5/8")

Family LYCAENIDAE

Species *Agrodiaetus dorus*

Author Hübner

FURRY BLUE

The silvery blue males of this species have large patches of brown scent scales on the forewings which create the distinctive furry appearance alluded to in the common name. The wing veins and narrow margins are blackish brown. The upperside of the female is entirely dark brown. The underside of the male is pale buff with black spots and there is sometimes a white streak on the hindwing.

• **EARLY STAGES** The caterpillar is apparently undescribed, but is known to feed on sainfoin (*Onobrychis*) and alfalfa (*Medicago sativa*).

• **DISTRIBUTION** Grassland and hillsides in northern Spain, southern France, and central Italy.



PALEARCTIC


in some males the
ground colour is
almost white



♂



characteristic
spotting of
hindwing



♂ Δ

Time of Flight ☼

Habitat ▲ ● ●

Wingspan 2.5-4cm (1-1 1/2")

Family LYCAENIDAE

Species *Danis danis*

Author Cramer

LARGE GREEN-BANDED BLUE

This spectacular tropical blue belongs to a genus confined largely to Australasia. Males have narrower, black margins, while females are generally larger and darker and often have a flash of metallic-turquoise on the forewing. The hindwing border bears a series of large, black spots on the underside.

• **EARLY STAGES** The caterpillar feeds on red ash (*Alphitonia excelsa*). It is apparently undescribed but caterpillars of *Danis hymetus*, which feed on the same host plant, are flattened and pale green.

• **DISTRIBUTION** Occurs from north-eastern Australia to Papua New Guinea and the Moluccas.




INDO-AUSTRALIAN

narrow, black wing margins on males

white centre to forewing more developed in some species

distinctive white abdomen reflects hindwing pattern



Time of Flight ☀

Habitat 🌿

Wingspan 4-4.5cm (1 1/2-1 7/8")

Family LYCAENIDAE

Species *Lampides boeticus*


Author Linnaeus

LONG-TAILED BLUE

Males of this species are violet-blue with narrow, blackish brown borders. Females have dark forewing margins, while the hindwings are dark brown, variably suffused with blue towards the base. The underside of both sexes is pale brown with a series of wavy, white lines and two black and orange eyespots on the hindwing tails.

• **EARLY STAGES** The caterpillar is pale to yellowish green, with a dark stripe along the back. It feeds on beans (*Vicia*), pea (*Pisum*), and other legumes. It is often an agricultural pest.

• **DISTRIBUTION** From Europe to Africa, Asia, Australia, and the Pacific Islands




PALEARCTIC
AFROTROPICAL
INDO-AUSTRALIAN

two large, black spots at base of hindwings of both sexes

the tails are short, despite the common name

extent of dark colouring in the female is variable



Time of Flight ☀

Habitat 🌿

Wingspan 2.5-4cm (1-1 1/4")

Family LYCAENIDAE

Species *Candalides sarthophilos*

Author Hübner

YELLOW-SPOT BLUE

The males of this species are black with a slight purplish blue suffusion in the centre of each wing. Females are similar except they lack the purplish blue suffusion. The undersides of the wings of both sexes are bluish white with pure white centres and small black dots along the outer margins.

• **EARLY STAGES** The caterpillar is green to bluish green with oblique, dark green markings and a yellow line along its sides. It feeds at night on the foliage of *Pimenta*.

• **DISTRIBUTION** Found in wooded country in Australia.



INDO-AUSTRALIAN

orange-
yellow patch
on forewings
gives this
species its
common name



♂



♂ Δ

large faint
white marking
on forewing

characteristic central
hindwing spots

Time of Flight ☀

Habitat 🌳

Wingspan 2.5–3cm (1–1½in)

Family LYCAENIDAE

Species *Colostynus argutus*

Author Linnaeus

HOLLY BLUE

Males of this distinctively coloured species are pale lilac-blue with narrow black borders while females have broad, blackish brown borders. The underside of both sexes is bluish white with a line of elongated, black spots on the forewings and a pattern of small, black dots on the hindwings.

• **EARLY STAGES** The caterpillar is green with a yellowish green or white line along the sides, and white and purplish pink markings on the back.

• **DISTRIBUTION** Widespread throughout Europe, extending right across to North Africa and across much of temperate Asia as far as Japan.



PALEARCTIC



♂



black and
white wing
fringes



♀

series of diffuse
marginal spots
on female
hindwings

Time of Flight ☀

Habitat 🌳

Wingspan 2–3cm (¾–1½in)

Family LYCAENIDAE

Species *Castilius rostron*

Author Fabricius

COMMON PIERROT


This attractive little butterfly is strongly patterned with large black spots on a white background. Females are larger than males and have broader wing borders.

• **EARLY STAGES** The caterpillar is green with two yellow lines along the back and small, yellow spots along the sides. It is known to feed on jujube or Chinese date (*Ziziphus jujuba*).

• **DISTRIBUTION** India and Sri Lanka, to Malaysia and the Lesser Sundas.



INDO-AUSTRALIAN



small hindwing tail

base of wings shot with metallic-blue scales

Time of Flight ☀

Habitat 🌿 🌳 🌴

Wingspan 2.5–3cm (1–1¼in)

Family LYCAENIDAE

Species *Philoetes sonorensis*

Author Felder

SONORAN BLUE


This striking metallic-blue and orange butterfly is unlike any other North American blue. The females are more strongly marked with orange than males. The underside is brown grey with black spots and orange forewing markings.

• **EARLY STAGES** The caterpillar is pale green and red. It feeds on stonecrops (*Sedum*).

• **DISTRIBUTION** California to northern areas of Mexico.



NEARCTIC



distinctive, chequered wing fringes

Time of Flight ☀

Habitat 🌿 🌳 🌴

Wingspan 1.5–2cm (½–¾in)

Family LYCAENIDAE

Species *Heppichia exilis*

Author Boisval

WESTERN PYGMY BLUE



This is a very tiny butterfly. Females are larger than males but are not as blue. The underside of both sexes is pale brown with grey markings. There are black, metallic blue-centred spots on the hindwing margins.

• **EARLY STAGES** The pale green caterpillar feeds on pickleweed (*Salicornia ambigua*) and saltbush (*Atriplex*).

• **DISTRIBUTION** Occurs from the western USA, through to South America.



black and white fringes to forewings

NEARCTIC
NEOTROPICAL

Time of Flight ☀


Habitat 🌿 🌳 🌴

Wingspan 1–2cm (¾–¾in)

Family LYCAENIDAE	Species <i>Syntarucus pithous</i>	Author Linnaeus
LANG'S SHORT-TAILED BLUE Males are violet-blue, while females are brown with a blue sheen to the centre of the forewings and base of the hindwings. The underside of both sexes is pale greyish brown with white, wavy lines. • EARLY STAGES The green caterpillar feeds on the buds of plumbago (<i>P. europaea</i>), alfalfa (<i>Medicago sativa</i>), and other plants of the pea family (Leguminosae). • DISTRIBUTION This species occurs in southern Europe and Africa extending into Asia.		
Time of Flight ☀	Habitat 🌿 🌳 🏞	Wingspan 2.5–3cm (1–1¼in)




PALAEARCTIC




Family LYCAENIDAE	Species <i>Freyeria trochylus</i>	Author Freyer
GRASS JEWEL This is one of the smallest species in the world. The sexes are similar although the males have paler brown wings. There are two to four orange lunules with black centres on each of the hindwings. The underside is coloured a silvery grey with brown and black spots. • EARLY STAGES The caterpillar is undescribed. It feeds on heliotrope (<i>Heliotropium</i>). • DISTRIBUTION Confined to Greece in Europe but widespread in Africa and parts of Asia.		
Time of Flight ☀	Habitat 🌿 🌳 🏞	Wingspan 1–1.5cm (½–⅝in)




AFROTROPICAL



Family LYCAENIDAE	Species <i>Aricia agestis</i>	Author Denis & Schiffermüller
BROWN ARGUS Both sexes are brown with marginal, orange-red lunules. Females are larger than males and have bigger spots. The underside is greyish brown with black and orange spots. • EARLY STAGES The caterpillar is coloured green with purple stripes and oblique, dark green lines. It feeds on rock rose (<i>Helianthemum</i>) and cranesbill (<i>Geranium</i>). • DISTRIBUTION Occurs in heathland throughout Europe, extending across temperate Asia.		
Time of Flight ☀	Habitat 🌿 🌳 🏞	Wingspan 2–3cm (¾–1¼in)



PALAEARCTIC



Family LYCAENIDAE

Species *Leptotes cassius*


Author Cramer

CASSIUS BLUE


Males of this little American butterfly are pale lilac-blue, while females are mainly white. The underside is white with brown markings and two black and orange hindwing eyespots.

• **EARLY STAGES** The caterpillar is green tinged with reddish brown. It feeds on flowers of Lima bean (*Phaseolus limensis*) and other plants of the pea family.

• **DISTRIBUTION** Occurs in warm, southern parts of North America, to Central and South America.



NEARTIC
NEOTROPICAL



Time of Flight ☀

Habitat 🌿 🌳 🏞

Wingspan 1.5–2cm (½–¾in)

Family LYCAENIDAE

Species *Polyommatus icarus*

Author Rottemburg

COMMON BLUE


This is one of the commonest European butterflies. Males are bright violet-blue, while females are brown with marginal, orange spots. The underside is pale greyish brown with black spots and marginal, orange spots.

• **EARLY STAGES** The green caterpillar feeds on various trefoils (*Lotus*) and related plants.

• **DISTRIBUTION** Grassy areas of Europe, North Africa, and temperate Asia.



PALAEARCTIC



Time of Flight ☀

Habitat 🌿 🌳 🏞

Wingspan 2.5–4cm (1–1½in)

Family LYCAENIDAE

Species *Plebejus argus*

Author Linnaeus

SILVER-STUDDED BLUE


Males are a deep purplish blue with white wing margins while females are brown with marginal, orange spots. The underside is greyish brown with black spots and marginal, orange markings.

• **EARLY STAGES** The caterpillar is green with a dark brown stripe down the back, and a white stripe along each side. It feeds on gorse (*Ulex*) and various heathland plants.

• **DISTRIBUTION** Heaths and grassland throughout Europe, extending across temperate Asia to Japan.




PALAEARCTIC




Time of Flight ☀

Habitat 🌿 🌳 🏞

Wingspan 2–3cm (¾–1in)


Family LUCANIDAE	Species <i>Isonarta bellus</i> gr.	Author Reimberg
ADONIS BLUE Males are a brilliant, clear blue, while females are dark brown, dusted with blue scales, with orange, black, and blue marginal spots on the hindwings. The underside of both sexes is coloured pale brown with black spots and orange markings. • EARLY STAGES The green and yellow caterpillar feeds on horseshoe vetch (<i>Hippocrepis comosa</i>). • DISTRIBUTION Widespread in Europe, to Turkey and Iran.		
Time of Flight ♀	Habitat 	Wingspan 2-4 cm (1/4-1 1/2 in)



PALAEARCTIC




black and white fringes to wings


Family LUCANIDAE	Species <i>Zerina atris</i>	Author Fabricius
COMMON GRASS BLUE Males are iridescent blue, while females are dull brown with a slight suffusion of blue towards the wing bases. The underside of both sexes is a pale grey colour with brown markings. • EARLY STAGES The caterpillar is green with dark green markings and a white line along each side. It is covered with minute, white hairs. It feeds on alfalfa (<i>Medicago sativa</i>) and other legumes. • DISTRIBUTION Ranges from Africa, throughout India to Japan and Australia.		
Time of Flight ♀	Habitat 	Wingspan 3-4 cm (1 1/4-1 1/2 in)

AFROTROPICAL
INDO-AUSTRALIAN

silvery leading edges to forewings

dark brown hindwing margins

Family LUCANIDAE	Species <i>Zizania knysna</i>	Author Turner
AFRICAN GRASS BLUE Males of this widespread butterfly are violet-blue while the females are dull brown. The underside of both sexes is greyish brown with black spots. It is also known as the dark grass blue, and the sooty blue. • EARLY STAGES The caterpillar is green and covered with short hairs. It feeds on devil's thorn (<i>Tribulus terrestris</i>) and other plants. • DISTRIBUTION Range extends from Mediterranean Europe to Africa, India, and Australia. Some consider the Australian subspecies to be a distinct species.		
Time of Flight ♀	Habitat 	Wingspan 2-2.5 cm (3/8-1 in)

PALAEARCTIC
AFROTROPICAL
INDO-AUSTRALIAN

triangular shaped forewing

thin, brown hindwing margins

Family LYCAENIDAE

Species *Hemiargus isola*


Author Reakirt

REAKIRT'S BLUE

Males are lilac blue with greyish brown margins. Females are similarly marked, but are dusky brown with a bluish suffusion of the wing bases. The underside of both sexes is pale brown with white markings and white-ringed, black spots on the forewings.

• **EARLY STAGES** This caterpillar is undescribed but is known to feed on mesquite (*Prosopis*) and related plants.

• **DISTRIBUTION** From southern USA to Costa Rica.

NEOTROPICAL
NEARCTIC

♂

characteristic arrangement
of black spots on each hindwing

Time of Flight ☀

Habitat 🌿 🌳 🏞

Wingspan 2–3cm (¾–1½in)

Family LYCAENIDAE

Species *Agrades franklinii*

Author Curtis

HIGH MOUNTAIN BLUE

Males are bluish grey; females are reddish brown. The underside of both sexes is greyish brown with white markings and black spots on the forewings.

• **EARLY STAGES** The caterpillar is undescribed, but feeds on various alpine plants, including *Androsace*, *Dodecatheon*, and *Diapensia*.

• **DISTRIBUTION** Found from Labrador and Alaska to the high mountains of Arizona and New Mexico, in the USA.




♀

variable extent
of blue colouring on
wings of males



♂

black
spots in
centre of
forewings



NEARCTIC

Time of Flight ☀

Habitat 🌿 🌳 🏞

Wingspan 2–2.5cm (¾–1in)

Family LYCAENIDAE

Species *Macalinea arion*

Author Linnaeus

LARGE BLUE


Both sexes of this species are bright blue with black markings on the forewings. Females are larger than the males and have broader margins. The underside is greyish brown with black spots.

• **EARLY STAGES** The yellowish white caterpillar feeds at first on thyme (*Thymus*), then on ant eggs and grubs.

• **DISTRIBUTION** Europe, but extinct in the British Isles, extends to Siberia and China.



PALAEARCTIC



♀

pear-shaped
forewing spots

Time of Flight ☀

Habitat 🌿 🌳 🏞

Wingspan 3–4cm (1¼–1½in)

Family LYCAENIDAE

Species *Mesene phareus*

Author Cramer

CRAMER'S MESENE

Males are deep red with black borders. Females are paler and larger. The forewing undersides are suffused with reddish black. The hindwing undersides are similar to those of the uppersides.

• **EARLY STAGES** The caterpillar is apparently undescribed but is known to feed on the highly poisonous foliage of *Pullinia prunata*.

• **DISTRIBUTION** This butterfly is fairly common in tropical regions of Central and South America



NEOTROPICAL

bright colour of wings indicates that this butterfly is poisonous to predators

sharply pointed forewings



♂



Time of Flight ☉

Habitat 🌿

Wingspan 2–2.5cm (¾–1in)

Family LYCAENIDAE

Species *Theopoe endorcia*

Author Westwood


ORANGE THEOPE BUTTERFLY

Both sexes of this striking butterfly have black borders to the forewings. The underside is pale lemon yellow and the abdomen is bright orange. They have a darting flight and settle on the undersides of leaves. Males are larger than females.

• **EARLY STAGES** The hairy, green caterpillar feeds on the foliage of cocoa

(*Theobroma cacao*).

• **DISTRIBUTION** Tropical Central and South America, including Trinidad.



NEOTROPICAL

patch of purple at wing-tips of male butterfly



♂



Time of Flight ☉

Habitat 🌿

Wingspan 2.5–4cm (1–1½in)

Family LYCAENIDAE

Species *Humana lucina*

Author Linnaeus

DUKE OF BURGUNDY FRITILLARY

This species is not in fact a fritillary; it belongs to the same family as the blues. The sexes are similar except that the forewings of the female are more rounded than those of the male.

• **EARLY STAGES** The caterpillar is pale brown with a darker stripe on its back. It feeds on cowslip and primrose (*Primula*).

• **DISTRIBUTION** Widespread in Europe



PALEARCTIC



♀



distinctive marginal band of black-dotted orange spots

Time of Flight ☉

Habitat 🌿

Wingspan 3–4cm (1¼–1½in)

Family LYCAENIDAE

Species *Symmatia dorsalis*

Author Cramer

WHITE-SPOTTED TADPOLE BUTTERFLY

This is one of a genus of about five species confined to tropical Central and South America.


They are slow flying but their rapid wingbeat is like that of wasps. Females have broader forewings with orange spots.

• EARLY STAGES


Undescribed

• DISTRIBUTION

Brazil and Venezuela



NEOTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 1.5–2 cm (3/4–7/8 in)

Family LYCAENIDAE

Species *Alexander menander*

Author Stoll


BLUE THAROPS

One of about ten species in this South and Central American genus of brightly coloured, iridescent metalmark butterflies.

Males are greenish blue with black streaks, while females are darker metallic blue. The underside of both sexes is yellowish white with reddish brown spots forming broken lines across the fore- and hindwings. Blue tharops are fast-flying and feed at flowers of agnimony (*Eupatorium*).

• **EARLY STAGES** Nothing appears to be known of the appearance of the caterpillar or its foodplants.

• **DISTRIBUTION** Occurs from Panama to the tropical regions of northern South America, and also in Trinidad




black wing margins

red blue on leading edge

blue coloration ceases at wing tips

wings have fringed appearance

broken black lines running across wings of female



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 3–4 cm (1 1/4–1 1/2 in)

Family LYCAENIDAE

Species *Apodemia nais*

Author Edwards

NAIS METALMARK

The upperside of this species is mainly brownish orange with a distinctive pattern of brown spots and bars that form zigzag lines and bands across both wings. Females are larger and paler than males and have slightly rounded forewings. The underside of both sexes is greyish white, strongly suffused with orange over most of the forewings, and with an orange band along the hindwing margins. The wings are patterned with black spots.

Adults are on the wing in summer; they visit flowers and settle on damp ground.

• **EARLY STAGES** The caterpillar is pale green with small tufts of bristles over the upper surface. It feeds on buckbrush (*Leunothus junceus*).

• **DISTRIBUTION** Found in the USA from Colorado, extending south to New Mexico, and Mexico.


chequered
wing fringes



♀



white patch
on front edge
of forewings



♂ Δ



NEARCTIC

Time of Flight ☀

Habitat 🌿 🌳

Wingspan 3-4 cm (1 1/4-1 1/2 in)

Family LYCAENIDAE

Species *Helicopsis rupido*

Author L. M. M. J. S.


GOLD-DROP HELICOPSIS

The forewings of the males are yellowish white, edged with brown, while the bases are orange-yellow. The hindwings are dark brown with an orange-yellow base. The females are lighter, and are marked with brown around the hindwing margins. The undersides are similar to the uppersides except for several metallic spots on the inner hindwing, and margins.

• **EARLY STAGES** The caterpillar appears to be undescribed, but is known to feed on wild tania (*Montrichardia*).

• **DISTRIBUTION** Found in tropical South America, from Venezuela to Trinidad and Brazil.

striking pattern of
"metalmarks" on
hindwing underside is
present in both sexes




♀

distinctive
dark forewing
borders



♂ Δ



NEOTROPICAL

Time of Flight ☀

Habitat 🌿 🌳

Wingspan 3-4 cm (1 1/4-1 1/2 in)

Family LYCAENIDAE

Species *Catoplius mutica*


Author McApine

SWAMP METALMARK

This species is reddish brown with black lines and spots, and rows of silvery blue or bluish green metallic markings. The underside varies from yellow to orange-brown, but has a similar pattern of black and metallic-blue markings. The sexes are similar.


• **EARLY STAGES** The hairy pale green caterpillar feeds on swamp thistle (*Cirsium muticum*)

• **DISTRIBUTION** Swamps from western Pennsylvania to southern Minnesota.




♂ Δ

body matches
colour of
wings



♂

• metallic
markings
on upper-
and
undersides



NEARCTIC

Time of Flight ☀

Habitat 🌿

Wingspan 2–2.5cm (1/4–1in)

Family LYCAENIDAE

Species *Uranis acubis*


Author Hewitson

HEWITSON'S URANEIS

This distinctive butterfly belongs to a genus of three South American species that are all believed to be mimics of day-flying *Hypsa* moths. Males are smaller than females and have straighter outer margins to the wings. The underside is similar to the upper side. There are various forms of this butterfly.


• **EARLY STAGES** The caterpillar is undescribed and its foodplants are unknown.

• **DISTRIBUTION** Occurs throughout the tropical forests of Colombia.



♂

• white wing
markings are
smaller in males



♀

• females
have more
rounded
wings



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 3–4cm (1/4–1 1/2in)

Nymphalidae

A HUGE FAMILY comprised of over 5,000 species, the Nymphalidae contains some of the world's most beautiful and spectacular butterflies, incorporating emperors, monarchs, fritillaries, admirals, and many others.

The most important characteristic that separates this large group from other species of butterfly is the front pair of

legs, which are usually undeveloped so they no longer have a walking function. In males they are often covered with dense tufts of scales, giving rise to the term "brush-footed butterflies" that is commonly applied to this family. The Nymphalidae is divided into numerous subfamilies, most of which, at one time, were regarded as distinct in their own right.

Family NYMPHALIDAE

Species *Gethosia biblus*



Author Drury

RED LACEWING

There are two female forms of this butterfly, one resembles the male, the other has a dull green ground colour. The undersides of both sexes are orange red with lacy patterns of white lines outlined with black. Several species in the genus are similar. These butterflies are on the wing throughout the year.

• **EARLY STAGES** The caterpillar is reputed to have poisonous, branched spines. It lives gregariously on passion flowers (*Passiflora*).

• **DISTRIBUTION** Widespread from northern India to China, Malaysia, Indonesia, and the Philippines.



INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌿

Wingspan 8-9cm (3¼-3½ in)

Family NYMPHALIDAE

Species *Anartia jatrophae*

Author Johansson

WHITE PEACOCK

The sexes of this butterfly are quite similar, although females tend to be larger and have slightly less angular wings. The wings are shaded and overlaid with a brown pattern.

• **EARLY STAGES** The spiny caterpillar is black, spotted with silver. It feeds on water hyssop (*Bacopa monnieri*).

• **DISTRIBUTION** South and Central America, the West Indies, into southern Texas and Florida, USA.



NEOTROPICAL



Time of Flight ☼

Habitat ☼, ☼

Wingspan 5.5-5.5cm (2.2-2.2in)

Family NYMPHALIDAE

Species *Pantoporia borbonica*

Author Stoll

BURMESE LASCAR


This is one of a group of very distinctive species. The underside is pale straw-yellow with brown lines and narrow marginal bands.

• **EARLY STAGES** The caterpillar is greenish grey with bands along the sides. There are four pairs of points on the back. It feeds on acacia.

• **DISTRIBUTION** Found throughout India and Sri Lanka, and right through to Malaysia.



INDO-AUSTRALIAN



Time of Flight ☼

Habitat ☼

Wingspan 4.5-5.7cm (1.8-2.3in)

Family NYMPHALIDAE

Species *Gyrtona thyodamas*


Author Brändén

COMMON MAP

The intricate and distinctive pattern of map-like markings on the white wings of this butterfly gives rise to its common name. The butterfly has a jerky flight.

• **EARLY STAGES** The caterpillar is very unusual because it is smooth, but has two long, fleshy projections on the back. It feeds on fig (*Ficus*).

• **DISTRIBUTION** North India and Pakistan to Japan.


INDO-AUSTRALIAN
PALAEARCTIC


Time of Flight ☼

Habitat ☼

Wingspan 6-7cm (2.4-2.8in)

Family NYMPHALIDAE

Species *Araschnia levana*

Author Innacus


EUROPEAN MAP BUTTERFLY

This butterfly is remarkable for having quite distinct spring and summer seasonal forms. Spring forms are orange with dark brown markings, while summer forms are dark chocolate-brown with white bands. There is a characteristic, map-like pattern of yellowish white lines on the dark underside that gives rise to the common name.

• **EARLY STAGES** The black, spiny caterpillar feeds on stinging nettle (*Urtica dioica*).

• **DISTRIBUTION**

Widespread in Europe. Range extends across temperate Asia.



PALEARCTIC



SPRING BROOD

distinctively
scalloped
forewing



SUMMER BROOD

characteristic
black and white
wing fringes

Time of flight ☉

Habitat ☿

Wingspan 3-4cm (1¼-1½ in.)

Family NYMPHALIDAE

Species *Polyura delphus*

Author Doubleday

JEWELLED NAWAB


The characteristic hindwing tails of this butterfly are similar to those of the closely related *Charaxes* butterflies. The upperside is pale, greenish yellow to white, with a black, triangular tip to the forewing. The underside is pale blue with brown, green, and darker blue markings. This species varies in pattern.

• **EARLY STAGES** The caterpillar is undescribed; other caterpillars of this group have distinctive horned heads. The foodplant is unknown.

• **DISTRIBUTION** Extends from north India and Pakistan to Burma.



INDO-AUSTRALIAN



triangular, dark
tip to forewing

marginal markings on
hindwing are variable

robust body

♂

Time of Flight ☉

Habitat ☿

Wingspan 9.5-10cm (3¾-4 in.)

Family NYMPHALIDAE

Species *Polyura pyrrhus*

Author Linnaeus

TAILED EMPEROR

The extent of black on the upperside of this butterfly is very variable and some specimens are predominantly creamy yellow with narrow, black margins. There is always a marginal band of blue on the hindwing that runs into the distinctive paired tails. The underside is brown with a creamy white centre, banded with black. The outer margin of the hindwing is orange with a black border on the other side, and inside this is a series of striking, maroon-red spots. The sexes are similar. These butterflies have a powerful flight. They rest high up in tree tops, descending to feed on rotting fruit. Some subspecies, including *Sempronius fabriceus* from Australia, are now regarded as distinct species.

• **EARLY STAGES** The caterpillar is green and finely speckled with white spots. There is a yellow line along the sides and two or more striking yellow transverse bands on the back. It feeds on acacia.

• **DISTRIBUTION** Occurs from the Moluccas to Papua New Guinea and Australia.

the caterpillar is well camouflaged on its foodplant



CATERPILLAR OF
POLYURA PYRRHUS

double spot at centre of forewing

plain black leading edge to forewing

variable spotting on hindwing margin



band of blue on hindwing runs into double tails



INDO-AUSTRALIAN

Time of Flight ☉

-arital ♂

Wingspan 7-9cm (2 7/8-3 1/2 in)

Family	Nymphalidae	Species	<i>Aglais urticae</i>	Author	Linnaeus
--------	-------------	---------	-----------------------	--------	----------

SMALL, TORTOISESHELL

One of the most common European butterflies, this species is relatively small and bright. A distinctive marginal row of blue spots extends across the fore- and hindwing. The sexes are very similar. Butterflies are on the wing from spring to autumn. Those that emerge in late summer hibernate.

• **EARLY STAGES** The spiny caterpillar is black with broken, yellow bands. It feeds on stinging nettle (*Urtica dioica*).

• **DISTRIBUTION** Widespread across Europe, extending through temperate Asia to Japan.

forewing has squarish, black patches, with areas of orange-yellow

black base to hindwing

extended point on hindwing edge



PALAEARCTIC

Time of Flight		Habitat		Wingspan	4.5-5.5cm (1 7/8-2 in)
----------------	--	---------	--	----------	------------------------

Family	Nymphalidae	Species	<i>Apatura iris</i>	Author	Linnaeus
--------	-------------	---------	---------------------	--------	----------

PURPLE EMPEROR

Males of this beautiful species are suffused with iridescent purple. The underlying pattern is blackish brown with white markings. These butterflies fly around the tree tops.

• **EARLY STAGES** The plump, green caterpillar tapers at each end. It feeds on willow (*Salix*).


• **DISTRIBUTION** Widespread in woodlands in Europe, and across temperate Asia to Japan.

large orange, black, and purple eyespot on each hindwing

the undersides of both sexes are shaded brown, and marked with white



PALAEARCTIC



Time of Flight		Habitat		Wingspan	6-7.5cm (2 1/2-3 in)
----------------	--	---------	--	----------	----------------------

Family NYMPHALIDAE

Species *Asterocampa celtis*

Authors Boisduval & Leconte

HACKBERRY BUTTERFLY

This brown butterfly is intricately and variably patterned with dark brown spots and bands. The tip of the forewing is characteristically spotted with white. Females are larger and paler than males, and their hindwings are more rounded. Butterflies are on the wing from spring to autumn, depending on the locality.

• **EARLY STAGES** The caterpillar is bright green with yellow stripes. The head has small branched horns. It feeds on hackberry (*Celtis*).

• **DISTRIBUTION** Widespread in North America, from northern Ontario to Florida and Texas.



NEARCTIC

black and white
eyespots on
hindwing
underside

slight
scalloping
to wings

distinctive
angular
hindwings

Time of Flight ☼

Habitat 🌳

Wingspan 4–5.5cm (1½–2¼in)

Family NYMPHALIDAE

Species *Argynnis lathonia*

Author Linnaeus

QUEEN OF SPAIN FRITILLARY

One of the most distinctive European fritillaries, this species has pointed forewings and angular hindwings. The uppersides of both sexes are orange-red, with black. The undersides are marked with silver. Butterflies are on the wing from spring to autumn.

• **EARLY STAGES** The brown-spined caterpillar is black, spotted with white, with a double white line down the back. It feeds on violets (*Viola*).

• **DISTRIBUTION** Widespread in southern Europe and North Africa, migrating northwards. Range extends across temperate Asia to western China.



PALAEARCTIC

double black
line around
wing margin

large, silver
patches on
hindwing
underside

Time of Flight ☼

Habitat 🌳

Wingspan 4–4.5cm (1½–1¾in)

Family NYMPHALIDAE

Species *Enthalia aconthea*

Author Cramer

BARON


Males have dark brown wings with blackish brown markings, and a diffuse, whitish grey band on the forewing. Females are larger and paler, and are usually marked with varying degrees of white on both fore- and hindwings. The undersides of both sexes are pale brown with a band of blackish spots along the wing margins, and blackish rings at the wing bases.

• **EARLY STAGES** The caterpillar is green with a yellow stripe along the back. It feeds on mango (*Mangifera indica*) and cashew (*Anacardium*).


• **DISTRIBUTION** Found from India and Sri Lanka, to China, and through Malaysia to Indonesia.



INDO-AUSTRALIAN



♀



♂

• marginal band of U-shaped markings on forewings

• more rounded hindwings on female

Time of Flight ☼

Habitat 🌳 🌿

Wingspan 5-6cm (2-2 1/2 in)

Family NYMPHALIDAE

Species *Eurytelus* sp.

Author Cramer

GOLDEN PIPER

This very distinctive, dark brown butterfly has a broad, orange band extending across both fore- and hindwings. The underside is pale brown banded with dark chocolate-brown, with a broad, brownish white outer margin. The sexes are similar. Golden pipers can be seen hovering over trees and bushes. They feed on sap exuding from trees, and sometimes visit flowers.

• **EARLY STAGES** This spiny caterpillar is greyish green. It feeds on castor oil plant (*Ricinus communis*), *Tragia henthiana* and *Crotalaria*.

• **DISTRIBUTION** This species is very common and widespread in tropical and southern Africa. It also occurs in Madagascar and the Middle East.



AFROTROPICAL



♂ Δ



♂

• dark brown outer margin to upperside hindwing

• distinctive scalloped outline to wings

Time of Flight ☼

Habitat 🌳 🌿

Wingspan 5-6cm (2-2 1/2 in)

Family NYMPHALIDAE

Species *Phycodes tharos*

Author Drury

PEARL CRESCENT

This is a common North American butterfly. The upperside is orange with blackish brown borders and black markings at the wing bases. The forewing underside is pale orange with two black patches on the hind margin. It also has crescent-shaped markings on the hindwing. Another name for the butterfly is the pearly crescent-spot.


• **EARLY STAGES** The caterpillar is apparently undescribed, and its food-plants are unknown.

• **DISTRIBUTION**

Widespread from Newfoundland to Mexico.



NEARCTIC



series of spots on hindwing

white crescent on hindwing margin

Time of Flight ☀

Habitat 🌿 🍄 🌳 🌲

Wingspan 2.5-4cm (1-1½ in)

Family NYMPHALIDAE

Species *Charaxes jasius*

Author Linnaeus

TWO-TAILED PASHA

Of this group of butterflies, the two-tailed pasha is the only member to occur in Europe. The upperside is dark brown with orange borders. There are blue spots at the base of the paired tails. The underside is banded with reddish brown, pale yellow, and white, and there are broken bands of purplish grey. Females are larger than males. Another common name for the butterfly is the foxy charaxes.


• **EARLY STAGES** The caterpillar is green, speckled with white. It feeds on strawberry tree (*Arbutus unedo*).

• **DISTRIBUTION** This species occurs from the Mediterranean coast of Europe to tropical and southern Africa.



AFROTROPICAL

hindwing outlined with black



dark blackish brown upperside

smoky yellow hindwing margins

pale inner margins to hindwings

Time of Flight ☀

Habitat 🌿 🍄 🌳 🌲

Wingspan 7.5-8cm (3-3½ in)

Family NYMPHALIDAE

Species *Doseschallia besaltide*



Author Cramer

LEAFWING BUTTERFLY

This butterfly is chestnut brown with blackish brown margins to the forewings. It is the leaf-like underside that gives this species its common name.

• **EARLY STAGES** The caterpillar is coloured black with two rows of spots along the back. It feeds on jack fruit (*Artocarpus heterophyllus*)

• **DISTRIBUTION** This species ranges from India and Sri Lanka, to Thailand, Japan, the Philippines, Indonesia, the Solomon Islands and the Vanuata



the hindwings have two small, black, marginal spots

weakly developed eyespots resemble blemishes on a dead leaf



INDIA-AUSTRALIAN

Time of Flight ☀

Habitat 🌿

Wingspan 6–7cm (2½–2¾in)

Family NYMPHALIDAE

Species *Calabura darte*

Author Linnaeus

ZEBRA BUTTERFLY

The upperside of this species is dark brown with a broad, pale yellow, diagonal band across the forewing. The common name is derived from the spectacular zebra-striped underside which also has a broad, white, diagonal band on the forewing. These butterflies occur throughout the year.

• EARLY STAGES

The caterpillar is velvety black with white spines on its back. It feeds on the foliage of *Cecropia peltata*.

• DISTRIBUTION

Occurs from Mexico to Central and South America, including the West Indies



line of black-ringed, blue eyespots

♂



characteristic angular hindwings

distinctive eyespot markings



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 5.5–7.5cm (2¼–3in)

Family NYMPHALIDAE

Species *Rhaopatra polytes*

Author Cramer

THE WIZARD

The upperside of this rather strangely shaped butterfly is a rich orange-brown with blackish brown margins and hindwing spots. The underside is intricately patterned with brown and reddish brown bands and lines, interspersed with fine lines of silvery blue. There is a line of black and white eyespots.


• **EARLY STAGES** The caterpillar is apparently undescribed, but is known to feed on *Poikilospermum suaveolens*.

• **DISTRIBUTION** Well wooded areas of India and Malaysia to Indonesia.



INDO-AUSTRALIAN

characteristic short hindwing tails



Time of Flight ☼

Habitat 🌿

Wingspan 7-10 cm (2 1/2-3 1/2 in)

Family NYMPHALIDAE

Species *Paratrypa acis*

Author Cramer

COLOUR SERGEANT


This butterfly is coloured a very distinctive orange and brown. The underside of the male is orange-brown with white markings, similar to the upperside, and has a striking band of black spots on the hindwing, which also has a band of larger, pinkish orange markings. Female butterflies are often attracted to the flowers of *Lantanas*.

• **EARLY STAGES** The spiny caterpillar is mainly brown, with a large, dark red patch in the middle of the back. It feeds on *Glochidion* and *Mussaenda*.

• **DISTRIBUTION**

Common on the plains and in dense rainforest in India, Pakistan, Burma, and Malaysia.

females are similar to the males but they are paler and suffused with yellow



orange marginal line present in both sexes



INDO-AUSTRALIAN

Time of Flight ☼

Habitat 🌿

Wingspan 5-7 cm, ♀-2 1/2 in

Family NYMPHALIDAE

Species *Charaxes bernardus*


Author Fabricius

TAWNY RAJAH

This beautiful Asian *Charaxes* butterfly is orange with a broad, white, central band and a blackish brown border to the forewing. The underside is greyish brown with an irregular pattern of darker lines. Females are similarly patterned to males, but are larger and have more developed hindwing tails. Butterflies fly rapidly around the tree tops.

• **EARLY STAGES** The caterpillar is dark green with red spots on the body, and four red horns on the head. It feeds on various tropical trees and shrubs, including red sandalwood (*Adenanthera pavonia*) and albizias.

• **DISTRIBUTION** Occurs in the jungles of India, Pakistan, Sri Lanka, Burma, and Malaysia.



INDO-AUSTRALIAN

Time of Flight ☉

Habitat 🌿

Wingspan ♀ 12cm (3¼–4¼in)

Family NYMPHALIDAE

Species *Brenthis mo*

Author Rotteburg


LESSER MARBLED FRITILLARY

This little butterfly has typical fritillary markings of black spots on an orange ground. The undersides of the hindwings are yellow. Several geographical forms are known, but the species can usually be recognized by its small size and the solid black margins to the wings. The sexes are similar. These butterflies have a weak flight.

• **EARLY STAGES** The caterpillar is black with a double white stripe and orange-brown spines along its back. It feeds on great burnet (*Sanguisorba officinalis*), meadowsweet (*Valeriana ulmaria*), and raspberry (*Rubus idaeus*).

• **DISTRIBUTION**

The lesser marbled fritillary is widespread across marshy areas of Europe, but not the British Isles. The range extends from temperate Asia to Japan.



Time of Flight ☀

Habitat 🌿

Wingspan 3–4cm (1¼–1½in)

Family NYMPHALIDAE

Species *Charaxes holoteni*

Author Felder

LARGE BLUE CHARAXES


The blue on the upperside of this beautiful *Charaxes* butterfly is slightly iridescent, and is broadly bordered with black. Females are larger than males and have characteristic white, diagonal, forewing bands and longer hindwing tails. The underside of both sexes is dull purplish grey.

• **EARLY STAGES** The green caterpillar feeds on mahogany bean (*Azadirachta indica*) and related plants.

• **DISTRIBUTION** Occurs in open wood and areas of scrub, throughout tropical Africa from Kenya to Malawi, Zambia, and Angola.



AFROTROPICAL



Time of Flight ☀

Habitat 🌿


Wingspan 7.5–10.8cm (3–4¼in)

Family	NYMPHALIDAE	Species	<i>Hypolimnas bolina</i>	Author	Linnaeus
--------	-------------	---------	--------------------------	--------	----------

GREAT EGG-FLY

The males of this geographically variable butterfly are generally velvety black with purple-edged, white patches in the middle of each wing. The larger females are blackish brown with a much more complex pattern of white markings, they have an orange-red patch on the forewing. In some forms of this species, females lack the orange markings, and the white markings are greatly reduced. The undersides of both sexes are rather similar – they are brown, with bands of white spots and patches. The forewing is suffused towards the base with reddish brown. These butterflies are attracted to *Lantanas*.

- **EARLY STAGES** The caterpillar is dark brown or black with orange-yellow, branched spines and a yellow line along the side. It feeds on various tropical plants.
- **DISTRIBUTION** A very widespread species occurring from India to Taiwan, Malaysia, Indonesia, and Australia. There are many described subspecies.



CATERPILLAR OF
HYPOLIMNAS BOLINA



• *Dark, black and white fringes are characteristic of both sexes*



• *the forewing is suffused with reddish brown towards the base*

• *concave margin to forewing*



INDO-AUSTRALIAN

Time of flight	Habitat	Wingspan
☐	☐	7-11cm (2¾- 4½in)

Family NYMPHALIDAE

Species *Hypolimnast salmantis*

Author Dmry

BLUE DIADEM

Males of this appropriately named butterfly are rich blue with black wing margins and bases, and white dots. Females are often suffused with yellow. The underside is chocolate-brown with white bands and elongate, purple spots.

• **EARLY STAGES** The blue diadem caterpillar is dark brown with red spines. It feeds on *Urena* *hypselodendron* and *Flacryn*.

• **DISTRIBUTION** Lowland forests from tropical west to east Africa.



AFROTROPICAL

wavy, black and white wing fringes



♂

Time of Flight ☼☼

Habitat 🌿

Wingspan 9–9.5cm (3½–3¾in)

Family NYMPHALIDAE

Species *Prepona meander*

Author Cramer

BANDED KING SHOEMAKER

This beautiful butterfly belongs to a group of similar species. The pattern of metallic, greenish blue on black is very striking and quite variable, and many forms have been named. The underside by contrast is greyish brown, with a dark brown central band. The sexes are similar. When in flight these butterflies make a crackling sound.

• **EARLY STAGES** The caterpillar's head has two spiny horns. It feeds on plants of the family Annonaceae.


• **DISTRIBUTION** Widespread in Central and South America, including the West Indies.



NEOTROPICAL

blue band broken at top, leaving two floating spots of colour

slight scalloping to hindwing edge



♀

Time of Flight ☼

Habitat 🌿

Wingspan 8–10.8cm (3¼–4⅞in)

Family NYMPHALIDAE

Species *Junonia coenia*

Author Hübner

BUCKEYE

The striking eyespots of this butterfly make it easy to recognize, although the markings can be quite variable. The sexes are similar.


• **EARLY STAGES** The caterpillar is green to blackish grey, marked with orange and yellow. It feeds on plantains (*Plantago*)

• **DISTRIBUTION**

Can be found throughout North America from Ontario to Florida, and down to Mexico, in fields and along shorelines.



NEARCTIC



Time of Flight ☀

Habitat 🌱 🌿

Wingspan 5–6cm (2–2½in)

Family NYMPHALIDAE

Species *Junonia callida*

Author Fabricius

MEADOW ARGUS

This species has a pair of black and violet eyespots on each wing, with three distinctive cream markings at the wing-tip. The underside is coloured a greyish brown with darker markings, but there are no eyespots on the hindwings. Females are similar to males but have more rounded wings.

• **EARLY STAGES**


The caterpillar feeds on plantains (*Plantago*).

• **DISTRIBUTION**

Papua New Guinea to Australia, and the islands of the South-east Pacific.



INDO-AUSTRALIAN



Time of Flight ☀

Habitat 🌱 🌿

Wingspan 4–5.5cm (1½–2¼in)

Family NYMPHALIDAE

Species *Chandrys nictis*

Author Doubleday

SILVERY CRESCENTSPOT

The hindwing row of small, black spots on this black and orange butterfly is very distinctive. The undersides of the forewings are similar to the uppersides, but the hindwing undersides are coloured yellowish white with orange and black markings and silvery spots.

• **EARLY STAGES**


The caterpillar is black and it is a so spiny

• **DISTRIBUTION**

Meadows from Canada, south to Arizona, Texas, and Georgia, in the USA.



NEARCTIC



Time of Flight ☀

Habitat 🌱 🌿

Wingspan 3–5cm (1¼–2in)

Family NYMPHALIDAE

Species *Salanis parhasus*

Author Drury

MOTHER-OF-PEARL BUTTERFLY

In nature this beautiful butterfly is a translucent pale green, suffused with iridescent purple. Both the fore- and hindwings have dark eyespots, but those near the hindwing tails are brightly coloured and prominent. The underside is similar to the upperside but lacks dark wing margins and has smaller, red eyespots. The sexes are alike.

• **EARLY STAGES** The spiny caterpillar is dark brown with a band of orange-red markings along its back.


• **DISTRIBUTION** Common in dense woodland, particularly along forest rivers, in tropical Africa, extending into South Africa.



AFROTROPICAL

short, dagger-like
hindwing tails •

brightly coloured
eyespot divert predators •



strongly hooked
wing-tips •

moon High ☾

Habitat 🌳

Wingspan 7.5–10 cm (3–4 in.)

Family NYMPHALIDAE

Species *Lunania orithya*

Author Linnaeus

BLUE PANSY

Males have predominantly black forewings with white, transverse bands and orange-ringed eyespots. It is the beautiful hindwings that give rise to its other common name, the blue argus. Females are larger than males. Their colours tend to be duller and their hindwings have only a slight suffusion of blue. The underside of both sexes is greyish brown, marked with white.

• **EARLY STAGES** The short-spined caterpillar is black with orange and yellow markings. It feeds on a wide and varied range of plants.

• **DISTRIBUTION** Extends from Africa to India, Malaysia, and Australia.



black and white
hindwing margins
present in both sexes

female
has larger
hindwing
eyespot



female
has more
rounded
wings

AFROTROPICAL
INDOMALAYAN

Time of flight ☼

Habitat 🌳

Wingspan 4–6 cm (1½–2 in.)

Family NYMPHALIDAE

Species *Polodryas imula*

Author Edwards

DOFTED CHECKERSPOT

With its pretty, chequered pattern of black and orange, this is a typical fritillary. The underside is mainly pale orange with a series of large, white, marginal markings on both wings, and distinctive black spots. Females are considerably larger than males.

• **EARLY STAGES** The caterpillar is orange with orange and black spines. It feeds on beardtongue (*Penstemon*). There are several broods a year.

• **DISTRIBUTION** Found in limestone and chalk districts where the foodplant flourishes, in the USA, in New Mexico and Texas, and in Mexico.



clubbed antennae

tooth-like pattern on forewing edge

chequered wing fringes

characteristic triple band of black spots on underside of hindwing



NEARCTIC

Time of Flight ☉

Habitat 🌳 🌾

Wingspan 3-4 cm (1 1/4-1 1/2 in)

Family NYMPHALIDAE

Species *Neopharis antiopa*

Author Linnaeus

CAMBERWELL BEAUTY

This unmistakable species has a dark maroon upperside with blue, marginal spots and broad, pale yellow borders to the wings. The underside is dark grey, lined with black, and the margins are yellowish white, speckled with black. The sexes are similar. The butterfly is known in the USA as the mourning cloak.

• **EARLY STAGES** The spiny caterpillar is velvety black, finely spotted with white, with a row of reddish brown patches along the back. It feeds on various deciduous trees.

• **DISTRIBUTION** Found in Europe and temperate Asia. Also occurs from North America to northern South America.

unusual outline to forewings

speckled effect to yellow borders

distinctive row of black-ringed, blue spots



HOLARCTIC

Time of Flight ☉

Habitat 🌳 🌾

Wingspan 6-8 cm (2 1/2-3 1/4 in)

Family NYMPHALIDAE

Species *Nymphalis polychloros*

Author Linnaeus


LARGE TORTOISESHELL

This butterfly can be distinguished from the small tortoise shell (*Aglais urticae*, see p.110) by its larger size, its hairy appearance, and the lack of white markings on the leading edge of its forewing. The underside is patterned with various shades of brown, and has a distinctive marginal band of slate grey.

- **EARLY STAGES** The caterpillar is black, speckled finely with white, and has orange-brown spines. Orange lines extend along the back and sides. It feeds on the foliage of various broadleaves.
- **DISTRIBUTION** Widespread in Europe, extending to North Africa and the Himalayas.



PALEARCTIC



Time of Flight ☀

Habitat 🌳 🌿

Wingspan 6-8cm (2-2.5in)

Family NYMPHALIDAE

Species *Marpesia petraea*

Author Cramer


RUDDY DAGGER WING

The distinctive shape of both fore- and hindwings make this butterfly easy to recognize. The upperside is orange with brown cross-lines and brown tails. The underside is pale pinkish brown with brown markings. The sexes are similar. Adults are attracted to flowers and over-ripe fruit, particularly figs.

- **EARLY STAGES** The caterpillar is reddish brown and yellow, spotted and lined with black. The head has distinctive spiny horns. It feeds on the leaves of fig (*Ficus*), cashew (*Anacardium*), and mulberry (*Morus*).
- **DISTRIBUTION** South and Central America, extending into the USA, in Florida and Texas.



NEOTROPICAL



Time of Flight ☀

Habitat 🌳 🌿

Wingspan 7-7.5cm (2.5-3in)

Family NYMHALIDAE

Species *Basiaarchia archippus*

Author Cramer

THE VICEROY

Also known as the mimic because of its remarkable resemblance to the monarch butterfly (*Danaus plexippus*, see p 184), the viceroy can be distinguished by the black line that crosses the wing veins. These butterflies are on the wing from spring to autumn. They are attracted to honeydew secreted by aphids.

• **EARLY STAGES** The humped caterpillar is mottled olive-green and brown, and has a pair of bristly tufts behind the head. It feeds on the foliage of willow

(*Salix*), and related deciduous trees.

• **DISTRIBUTION**

Range extends from Canada, right through the USA, down to Mexico.



NEARCTIC
NEOTROPICAL



• black cross-line on hindwing

Time of Flight ☀

Habitat 🌳

Wingspan 7-7.5 cm (2 1/2-3 in)

Family NYMHALIDAE

Species *Procris arcas*

Author Cramer

THE GAUDY COMMODORE

This beautiful butterfly occurs in two distinct seasonal forms. The dry season form (shown right) is dark brown,


variably suffused with blue. The wet season form is orange-red with dark brown spotting and borders. There is geographic variation in this species.

• **EARLY STAGES** The spiny caterpillar is dark brown with a reddish brown head. It feeds on *Coleus*, and Labiatae.

• **DISTRIBUTION** Wooded localities in tropics, and southern Africa.



AFROTROPICAL



marginal band of red ringed, black spots

distinctive scalloped outline to hindwing

Time of Flight ☀

Habitat 🌳

Wingspan 5-6 cm (2-2 1/2 in)

Family NYMPHALIDAE

Species *Polygonia c-album*

Author Linnaeus


COMMA

This is a variable butterfly: the first generation is lighter and more brightly coloured than the second. Both the common and scientific names refer to the white "c" or comma that is present on the hindwing underside.

• **EARLY STAGES** The spiny caterpillar is black with orange-brown lines and a large, white patch on the back. It feeds on stinging nettle (*Urtica dioica*) and hop (*Humulus lupulus*).

• DISTRIBUTION

Occurs from Europe, to North Africa, across temperate Asia to Japan.



• scalloped outline of forewing



underside patterning resembles a dead leaf



PALEARCTIC

Time of Flight ()

Habitat ● JULY

Wingspan 4.5-6cm (1 3/4-2 1/4 in)

Family NYMPHALIDAE

Species *Pandora pandora*

Author Denis & Schiffermüller

CARDINAL

The upper surface of this fritillary resembles several other species, but the underside is unmistakable with its beautiful, rosy-red patch on the forewing.

• **EARLY STAGES** The caterpillar is black with orange stripes and spines. It feeds at night on violets (*Viola*).

• **DISTRIBUTION** Southern and eastern Europe, to north Africa, Iran, and Pakistan



solid, undermark band on wing margins



♂ Δ

• small, white spots on underside of hindwing



AFROTROPICAL

Time of Flight ☼

Habitat ●

Wingspan 6-8cm (2 1/4-3 1/4 in)

Family NYMPHALIDAE

Species *Palla nssherr*


Author Burder

PALLA BUTTERFLY

Males are very distinctive with white-barred, black forewings. The hindwings are dark brown with broad, central bands of deep orange. Females are larger and have brown wings with pale orange central bands. Palla butterflies are fast and powerful fliers.

• **EARLY STAGES** The caterpillar is patterned with green and brown. It resembles a dying leaf, and feeds on *Porana densifolia*, *Bonania poranoides*, and *Toddalia*.

• **DISTRIBUTION** Occurs in tropical forest in western, eastern, and central Africa.



Time of Flight ☀

Habitat 🌿

Wingspan 7–8cm (2½–3¼in)

Family NYMPHALIDAE

Species *Inachis io*


Author Linnaeus

PEACOCK

The patterning on this exquisite butterfly is unique. In contrast to the striking upperside, the underside is dark brown with purplish black lines, which provides good camouflage. The females are slightly larger than the males.

• **EARLY STAGES** The caterpillar is black and spiny. It feeds on nettle (*Urtica dioica*) and hop (*Humulus lupulus*).

• **DISTRIBUTION** Widespread in gardens in Europe, temperate areas of Asia, and Japan.



PALAEARCTIC



Time of Flight ☀

Habitat 🌿

Wingspan 5.5–6cm (2¼–2½in)

Family NYMPHALIDAE

Species *Kallima mackens*



Author Boisduval

INDIAN LEAF BUTTERFLY

The uppersides of both the male and the female butterfly are brightly and attractively coloured with orange and purplish blue. However, the brown patterning of the underside, coupled with the unusual wing shape, makes this one of the most remarkable leaf mimics of all. This facility for camouflage has given the Indian leaf butterfly its very apt common name.

• **EARLY STAGES** The caterpillar is velvety black with red spines and long yellow hairs. It feeds on *Girardinia* and *Sirostaphis*, as well as other plants.

• **DISTRIBUTION** This species is widespread from India and Pakistan, to southern China and Taiwan.



INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌿

Wingspan 9–12cm (3½–4½in)

Family NYMPHALIDAE

Species *Vanilla erota*


Author Fabricius

CRUISER BUTTERFLY


Males are orange-brown with a paler, central band. The underside is similar but with reddish brown lines. Females are greyish brown with orange on the hindwing and a central, white band. The underside has red lines and pale patches.

• **EARLY STAGES** The caterpillar is pale yellow with brown markings and feeds on *Adiantum* and passion flower (*Passiflora*)

• **DISTRIBUTION** Occurs in forest, from India and Pakistan, to Malaysia and Indonesia.



♂



♀

• distinctive, pale spot at the wing tip

• eyespots present on the hindwings of both sexes

• small hindwing tails



INDO-AUSTRALIAN

Time of flight



Habitat



Wingspan

7-9 cm (2 1/2-3 1/2 in)

Family NYMPHALIDAE

Species *Nepus sappho*

Author PALLAS

COMMON GLIDER

This distinctive European species belongs to a genus of butterflies occurring throughout Africa and South-east Asia. Its wing pattern of black and white bands distinguishes it from other European butterflies. The underside of the common glider is a rusty, reddish brown.

• **EARLY STAGES** The caterpillar is smooth with four pairs of spiny projections on the back. It feeds on spring pea (*Lathyrus*)

• **DISTRIBUTION** Found in woodland and on scrub-covered hillsides in central and eastern Europe.



PALEARCTIC



♂

• central forewing streak

• characteristic double, white hindwing band

Time of flight



Habitat



Wingspan

4.5 cm (1 1/2 in)

family NYMPHALIDAE

Species *Sasakia charonda*

Author: E. J. WILSON

JAPANESE EMPEROR

This beautiful species is the national butterfly of Japan. Male Japanese emperors have distinctive, dark brown wings with a bronze-green sheen, richly suffused with iridescent purple. The females are brown, but without the purple iridescence. In both sexes the underside of the forewing is blackish brown with white spots and pale greyish green tips. The underside of the hindwing is pale, greyish green with paler spots and a pink spot on the base of the hindwing. This is quite a variable butterfly with several named subspecies. Japanese emperors are powerful fliers and can be seen on the wing in the summer months.


• **EARLY STAGES** The caterpillar is coloured green and has several pairs of pointed, fleshy protuberances along its back. The green head has a pair of long horns. The caterpillar feeds on *Celtis*.

• **DISTRIBUTION** Occurs in China and Japan.



CATERPILLAR OF
SASAKIA CHARONDA

caterpillar blends
with leaf on
which it feeds



white spotting along
margins of both wings

long slender
antennae

slightly indented
forewing

robust body, typical
of a strong flier

shallow
scalloping to
wing margin

pink
hindwing patch



PALAEARCTIC

Time of Flight ☀

Habitat 🌿

Wingspan 9.5–12cm (3¾–4¾in)

Family NYMPHALIDAE

Species *Kallima atene rumia*


Author Westwood

AFRICAN LEAF BUTTERFLY

The males of the species are dark brown with purple and red markings on the forewings. The females are larger than the males and are marked with pale blue on the forewings and cream on the hindwings. The underside of this species has the typical leaf-like, brown pattern of this particular group. It is this distinctive underside that gives the African leaf butterfly its common name.

• **EARLY STAGES** The caterpillar is reddish grey with black lines. Its food plant is apparently unknown.

• **DISTRIBUTION** This species is found in tropical eastern and western Africa.



Time of Flight



Habitat



Wingspan

7-8cm (2 3/4-3 1/4 in)

Family NYMPHALIDAE

Species *Eurodryas aurima*

Author Rottemburg

MARSH FRITILLARY


The upperside of both sexes is orange, cream, and brown. The underside is paler with fewer black markings. Females are larger than males.

• **EARLY STAGES** The spiny caterpillar is black with white spots. It normally feeds on the leaves of devil's bit scabious (*Succisa pratensis*).

• **DISTRIBUTION** Widespread in Europe, and extending to temperate Asia.



PALEARCTIC



Time of Flight ☉

Habitat 🌿 🌳 🏞️

Wingspan 3.4-5cm (1.4-1 1/4 in)

Family NYMPHALIDAE

Species *Speyeria cybele*

Author Fabricius

GREAT SPANGLED FRITILLARY

Females of this large American fritillary can be identified by the strong, black suffusion of the basal half of both the fore- and hindwings. In males this suffusion is much less distinct.


The underside of this fritillary can be distinguished by its pale orange colour, with black markings on the forewings and silvery patches on the hindwings.

• **EARLY STAGES** The caterpillar is black with orange-based spines. It feeds on the leaves of violet (*Viola rotundifolia*).

• **DISTRIBUTION** Occurs from southern Canada to New Mexico, and Georgia, in the USA.



NEARCTIC



Time of Flight ☉

Habitat 🌿 🌳 🏞️

Wingspan 5.5-7.5cm (2 1/4-3 in)

Family NYMPHALIDAE

Species *Hamadryas arthusa*

Author Cramer

QUEEN CRACKER

This species belongs to a group called the cracker butterflies, so-named because they produce a clicking noise when flying. It has distinctive, metallic-blue spotting on both the fore- and hindwings. Females are larger than males, and have a diagonal white band on the forewing and metallic-blue markings on the hindwing.


• **EARLY STAGES** Little is known about the early stages of this particular butterfly, but caterpillars of related species are spiny and have curved, knobbed horns on the head.

• **DISTRIBUTION** Extends from Mexico to Bolivia



NEOTROPICAL

strongly
rounded
hindwing



Time of Flight ☀

Habitat 🌿

Wingspan 6-10 cm (2 1/2 - 3 1/2 in)

Family NYMPHALIDAE

Species *Euthardina neoblaena*

Author Hübner

GOLD-BANDED FORESTER

The common name of this butterfly, which belongs to a group of some 125 species of African forest butterfly, derives from the broad, diagonal forewing band on a blackish brown background. The base of the forewing, and the greater part of the hindwing, is usually purplish blue, although in some forms they are green. The underside is pale orange-brown with lighter bands.


• **EARLY STAGES** The caterpillar is green with two large, pinkish red patches on the back, and longer, feathered spines along the sides. It feeds on *Dombolha*.

• **DISTRIBUTION** Found in tropical, eastern Africa.



AFROTROPICAL

scalloped
hindwings



Time of Flight ☀

Habitat 🌿

Wingspan 6-7.5 cm (2 1/2 - 3 in)

Family NYMPHALIDAE

Species *Agriax claudia*

Author Schulze


SCHULZE'S AGRIAS

One of the more striking members of a large group of very brightly coloured South American butterflies, Schulze's agrias has striking vermillion patches of colour on its forewings. Intricate patterning on the hind-wing underside is a trait of many similar species of this genus. The females have orange markings on the forewings, and lack a coloured hindwing patch.

- **EARLY STAGES** Little is known of the early stages of this butterfly.
- **DISTRIBUTION** Widespread in tropical South America.



NEOTROPICAL



Kind of Flight C

Habitat T

Wingspan 7-9 cm (2 1/2 - 3 in)

Family NYMPHALIDAE

Species *Diethria chymena*

Author Cramer

88 BUTTERFLY

This butterfly is one of several species with similar wing markings (see *Callisto mormona* p 135). The common name refers to the distinctive, black and white "88" pattern displayed on the underside of the hindwing. The underside of the forewing is strikingly patterned with red, black, and white. In contrast, the upperside is more sombre in colour, although the black wings can sometimes be marked with bands of metallic-blue.


The sexes are similar.

• **EARLY STAGES**

The caterpillar of this species is green with yellow markings, and has two short spines at the tail. The head has two long, spined horns. It feeds on *Trema micrantha*.

• **DISTRIBUTION**

Widespread in South America, and common in Brazil.



NEOTROPICAL

Kind of Flight C

Habitat T

Wingspan 4-4.5 cm (1 1/2 - 1 3/4 in)

SMALL PEARL-BORDERED FRITILLARY

This fritillary has a distinctive upperside pattern of black spots on orange. Its colourful underside markings distinguish it from similar species. A common name for the butterfly in North America is the silver-bordered fritillary.

• **EARLY STAGES** The caterpillar is brown, speckled with white, and with yellowish brown spines. It feeds on violets (*Viola*).

• **DISTRIBUTION**

Widespread in Europe, extending into temperate Asia. Also occurs in North America.




♂

forewing underside
paler than upperside



♂ Δ

black spot
near the
hindwing
base



HOLARCTIC

Time of Flight



habitat



Wingspan 3.5cm (1 1/4 in)

Family NYMPHALIDAE

Species *Parus caeruleus*

Author Fabricius

GUINEAFOWL BUTTERFLY


This unusual-looking butterfly varies in colour from leaden grey to greyish brown.

It has a pattern of black and white spots over both fore- and hindwings, which is reminiscent of guineafowl plumage. The underside of both sexes is coloured orange-brown with a similar pattern of spots and is generally much brighter in appearance. The male and female of this species are similar. Guineafowl butterflies fly close to the ground and settle with their wings outspread.

• **EARLY STAGES** The caterpillar is covered with long, feathery spines and feeds on *Gambetum*.


• **DISTRIBUTION** This species is common in semi-desert and open scrubland throughout Africa.

"toothed" edge to fore-
and hindwings



♂

distinctive,
black markings
at base of
hindwing



♂ Δ

white spotted
wing fringes



AFROTROPICAL

Time of Flight



habitat



Wingspan 5.6cm (2 1/4 in)

Family NYMPHALIDAE

Species *Callicore maiwana*

Author Hewitt, 19

EIGHTY-EIGHT BUTTERFLY

This butterfly is one of forty species from Central and South America, which are distinguished by the striking "88" pattern on the underside of the hindwing. The upperside surface is black with diagonal, orange markings at the wing-tips and a large, basal patch of red on the forewing. The hindwing often has an iridescent purplish sheen in males.


• **EARLY STAGES** Little is known of the early stages of this butterfly, but other *Callicore* butterflies have long, slender caterpillars.

• **DISTRIBUTION**

Throughout tropical South America, from Brazil to Colombia, and up to the West Indies




NEOTROPICAL



♂ Δ

• small white markings on hindwing margin

• "88" marking is bordered by a black and blue band



♂

Time of Flight ☉

Habitat 🌿

Wingspan 5-5.5cm (2-2 1/4 in)

Family NYMPHALIDAE

Species *Argynnis paphia*

Author L. Dudgeon, 19


SILVER-WASHED FRITILLARY

Males of this butterfly have distinctive, black forewing stripes, which carry scent scales. Females are usually orange with black spotting. The hindwing underside, although mainly green, is "silver-washed", hence the common name.


• **EARLY STAGES** The caterpillar is dark brown with two orange-yellow stripes on the back, and reddish brown spines. It feeds on violets (*Viola*).

• **DISTRIBUTION**

Widespread in Europe, extending to north Africa, and across temperate Asia to Japan.



PALEARCTIC



♂

• male butterfly has rather angular forewings

Time of Flight ☉

Habitat 🌿

Wingspan 5-7cm (2 1/4-2 3/4 in)

Family NYMPHALIDAE

Species *Calisto chontia*

Author Guenée

PIRATE BUTTERFLY

This reddish brown butterfly has distinctive rows of black-ringed, blue spots on both the fore- and hindwings. The leading edge of the forewing is speckled with black, and all wings have dark bases and outer margins. Males have a distinct, iridescent, purple sheen but this is absent from the larger females.

The underside is variable in colour. Adults drink from damp mud, and are attracted to flowers.


• **EARLY STAGES** The caterpillar is greyish yellow with black spines. The head is brown with two bulbous horns. It feeds on *Gomphocarpus* and *Jussiaea*.

• DISTRIBUTION

Common in grasslands and swampy areas in Africa.



AFROTROPICAL



Time of Flight ☀

Habitat 🌿 🌾 🌳

Wingspan 5.5–7cm (2¼–2½in)

Family NYMPHALIDAE

Species *Siproeta epaphus*

Author Latreille

BROWN SIPROETA

This striking, blackish brown butterfly with its bright orange-brown wing-tips and white bands is easily recognizable. Females are similar to males but larger. The underside pattern is paler and duller than the upperside, and the white hindwing band is margined with orange-brown. Adults tend to fly close to the ground, where they feed from forest flowers.


• **EARLY STAGES** The caterpillar is very distinctive, and has a maroon-coloured body with long, branched, bright yellow spines. Its head is shiny black. It feeds on *Ruellia*.

• DISTRIBUTION

Occurs in tropical rainforest in Central and South America, where it flies at high altitudes.



NEOTROPICAL



Time of Flight ☀

Habitat 🌿 🌳

Wingspan 7–7.5cm (2¾–3in)

Family NYMPHALIDAE

Species *Melitara didyma*

Author Esper


SPOTTED FRITILLARY

Males are bright orange-red and have strong, black margins. Females are generally larger and paler than males. The forewing underside is pale orange with black spots, while the hindwing underside is predominantly cream with orange and black.

- **EARLY STAGES** The spiny caterpillar is white with black lines and red orange spots on the back. It feeds on plantains (*Plantago*).
- **DISTRIBUTION** Found in Europe, North Africa, and temperate Asia.



PALAEARCTIC



Time of Flight



Habitat



Wingspan

3-4.5cm (1¼-1½in)

Family NYMPHALIDAE


Species *Ladona camilla*

Author Linnaeus


WHITE ADMIRAL

The upperside of this attractive butterfly is entirely black and white, while the underside is patterned with reddish brown and white. The inner margin of the hindwing is flushed with pale blue. Females are larger and slightly paler in colour than males. Butterflies are on the wing in early and mid-summer, and are attracted to flowers of bramble (*Rubus*).

- **EARLY STAGES** The caterpillar is green above and brown beneath, with two rows of brown spines on the back, and a brown, spiny head. It feeds on honeysuckle (*Lonicera*).
- **DISTRIBUTION** Widespread in Europe, extending across temperate Asia to Japan



PALAEARCTIC



Time of Flight



Habitat




Wingspan 5-6cm (2-2½in)

Family	NYMPHALIDAE	Species	<i>Vanessa atalanta</i>	Author	Linnaeus
--------	-------------	---------	-------------------------	--------	----------


RED ADMIRAL

The distinctive, red-banded, black forewings with white spots make this an easy butterfly to recognize. The underside of the forewing is similar to, though paler than, the upperside, while the hindwing underside is patterned with brown and black. The sexes are similar. Red admirals are strong-flying butterflies and often migrate.

- **EARLY STAGES** The spiny caterpillar is variable in colour, ranging from greyish black to greyish green or pale yellowish brown. It feeds on stinging nettle (*Urtica*).
- **DISTRIBUTION** Extends from Europe to North Africa and northern India, and from Canada through the USA to Central America.



EUROPEAN
PALEARCTIC



♂

small, black spots in red hindwing band

intricate pattern of hindwing underside

♂ ♀


Time of Flight	☀	Habitat	☀ ☀ ☀	Wingspan	5.5-6cm (2 1/4-2 1/2 in)
----------------	---	---------	-------	----------	--------------------------

Family	NYMPHALIDAE	Species	<i>Vanessa indica</i>	Author	Hübner
--------	-------------	---------	-----------------------	--------	--------


INDIAN RED ADMIRAL

This butterfly is similar to the red admiral (*Vanessa atalanta*, see above) but has a broad, red forewing band, and black spots on the hindwing band.

- **EARLY STAGES** The spiny caterpillar is either black, speckled with yellow, or yellow, speckled with black. It feeds on plants of the nettle family (*Urtica*).
- **DISTRIBUTION** From India and Pakistan, through to Japan, and the Philippines.



INDO-AUSTRALIAN
PALEARCTIC



distinctive, black forewing spots

large, black spots on wing margin

small, blue spots on hindwing

♂

Time of Flight	☀	Habitat	☀ ☀ ☀	Wingspan	5.5-6cm (2 1/4-2 1/2 in)
----------------	---	---------	-------	----------	--------------------------

Family NYMPHALIDAE

Species *Vanessa atalanta*

Author Johannsen

BLUE ADMIRAL

This bluish black butterfly has pale, marginal bands. These bands vary in width, and the large forewing spot is either white or blue, according to the subspecies.


• **EARLY STAGES** The caterpillar is coloured orange yellow with black spots. It feeds on the foliage of *Saururus*.

• **DISTRIBUTION** Ranges from India and Sri Lanka to Malaysia, the Philippines, and Japan.



INDO-AUSTRALIAN

ragged edge to wings, typical of this species



pale blue marginal band

Time of Flight ☀

Habitat 🌿

Wingspan 6–7.5 cm (2½–3 in)

Family NYMPHALIDAE

Species *Catonephele numitor*

Author Cramer

GRECIAN SHOEMAKER

Males of this striking species are velvety black with brilliant orange spots and purplish markings on the hindwings. By contrast, females have yellowish white markings on the forewings and the hindwings are largely brownish orange with black spots and bands. The underside is brown with a patch on the forewing: orange for the male, and yellow for the female. It is believed that the males may mimic one of the distasteful *Heliconia* butterflies.

• **EARLY STAGES** The caterpillar is green with white spots and short spines that are orange and black, or green and black. Its head is reddish orange with spined horns. It feeds on *Alchornea* and *Cathartocyanus*.

• **DISTRIBUTION** Occurs in Central and South America including the West Indies.




NEOTROPICAL

rounded hindwings on male



indented outer margin of female



Time of Flight ☀

Habitat 🌿

Wingspan 7–7.5 cm (2½–3 in)

Family NYMPHALIDAE

Species *Pseudacraea boissduvali*

Author Doubleday


BOISDUVAL'S FALSE ACRAEA

The bright orange, red, and black colours of this butterfly are typical of a distasteful species, and closely mimic the pattern of the poisonous *Acraea* butterflies. The front part of the forewing is grey with striking, black wing veins. The hindwing is rich orange-red with black markings. The underside is paler than the upperside. Females are larger and paler, and have more rounded hindwings than males.


• **EARLY STAGES** The caterpillar is very unusual in appearance. It has a spiny head and large, fleshy, spiny projections along its dark brown body. It is quite difficult to distinguish the head from the tail. It feeds on *Chrysophyllum* and *Mimusops*.

• **DISTRIBUTION**

Found in tropical rainforest, particularly in clearings and near streams, in tropical Africa south to Natal.



CATERPILLAR OF
PSEUDACRAEA BOISDUVALI



AFROTROPICAL

Time of Flight ☼	Habitat 🌿	Wings Jan 7–8cm (2¼–3¼in)
------------------	-----------	---------------------------

Family NYMPHALIDAE

Species *Cynthia cardui*

Author Linnaeus

PAINTED LADY

With its characteristic pattern of orange and black, with white spots this butterfly is easy to recognize.

• **EARLY STAGES** The caterpillar is black, finely speckled with white. It has black or yellow spines. It is known to feed on thistles (*Carduus*), nettles (*Urtica*), and various other plants.

• **DISTRIBUTION** Worldwide, with the exception of Australia and New Zealand



Time of Flight ☀

Habitat 🌿

Wingspan 5-6cm (2-2½ in)

Family NYMPHALIDAE

Species *Symbrenthia hypoleis*


Author Godart

HIMALAYAN JESTER

This is one of several orange and black, striped species. The underside is strikingly patterned with chocolate-brown squares on a white background. Females are larger and paler than males.

• **EARLY STAGES** Little is known of the early stages of this particular butterfly, but the caterpillar of the related *Symbrenthia flava* is dark brown with diagonal, dark stripes along both of the sides. It also has branched, blackish spines. It is known to feed communally on *Gerardinia heterophylla* and *Dibreyesia*, and various other plants.

• **DISTRIBUTION** Found from India and Pakistan to Malaysia and Java.



Time of Flight ☀

Habitat 🌿



Wingspan 4-5cm (1½-2in)

Family	NYMPHALIDAE	Species	<i>Terminus terpander</i>	Author	Hewitts 10
--------	-------------	---------	---------------------------	--------	------------

ROYAL ASSYRIAN


The regal name of this butterfly derives from the purple iridescence of the male's blackish wings. Females have less purplish suffusion

- **EARLY STAGES** The caterpillar is greenish with longitudinal lines, blackish spines, and a yellow coloured head. It feeds on *Antidesma*
- **DISTRIBUTION** Malaysia to Java and Borneo.



two distinct triangular spots on hindwing

row of dark brown, marginal, hindwing spots



INDO-AUSTRALIAN



Time of Flight	☀	Habitat	🌿	Wingspan	7-7.5cm (2 7/8-3in)
----------------	---	---------	---	----------	---------------------

Family	NYMPHALIDAE	Species	<i>Doxocopa cherubina</i>	Author	Felder
--------	-------------	---------	---------------------------	--------	--------

BLUE-GREEN REFLECTOR

This beautiful butterfly belongs to a group noted for their brilliant iridescent colours. The underside is pale brown with blackish markings.

- **EARLY STAGES** The caterpillar is apparently undescribed, but feeds on *Celtis*
- **DISTRIBUTION** Widespread in Central and South America.



three white spots on forewing tip

small hindwing tail of male

delicate, white and pale brown patterning



NEOTROPICAL

Time of Flight	☀	Habitat	🌿	Wingspan	6-7cm (2 1/2-2 7/8 in)
----------------	---	---------	---	----------	------------------------

Family NYMPHALIDAE

Species *Euxanthe wakefieldii*

Author WERC

FOREST QUEEN

This species belongs to a group of African butterflies noted for their distinctively rounded wings. The white markings on the black wings of the male have a bluish green iridescence. The underside is similar, but the black colouring is largely replaced by brown. The butterflies tend to fly in dappled shade, where their black and white pattern blends into the background. Females are larger and paler, and lack the bluish tint of the males.

• **EARLY STAGES** The caterpillar is green with two black-ringed, white spots on the back, each spot having two green markings within. The head is green and pale brown with four large, curved horns. It feeds on *Dombolua*.

• **DISTRIBUTION** Tropical East Africa to Mozambique and Natal in South Africa

dramatically horned head



CATERPILLAR OF
EUXANTHE WAKEFIELDII



♂

*marginal
row of
rounded,
white spots
on hindwing*

*body tipped with
brownish yellow
in both sexes*

*forewing
tip of female
is fuller
than in male*



♀ Δ

*slight
scalloping to
hindwings*



AFROTROPICAL

Time of flight ☀

Habitat 🌿

Wingspan 8-10cm (3 1/4 in)

Family NYMPHALIDAE

Species *Limenitis archippe*

Author Doubleday & Hewitson

BI-COLOUR COMMODORE

This dark brown butterfly has a striking, orange-yellow band on the forewing which continues on the hindwing as a white band, tapering towards the rear. A scalloped red line extends along the margins of both wings. The forewing bases are suffused with orange-brown. The sexes are alike.


• **EARLY STAGES** Nothing seems to be known about the early stages of this butterfly.

• **DISTRIBUTION** Common in forests up to altitudes of 2,500m (8,200ft) in India, Pakistan, and Burma.



INDO-AUSTRALIAN

white-flecked
wing fringes
at base •



♂

Time of flight ☀

Habitat 🌿 ⚡

Wingspan 8-9.5cm (3-4 3/8in)

Family NYMPHALIDAE

Species *Metamorpha stelenes*

Author Linnaeus

MALACHIITE

The upperside of this butterfly is a very pale green with distinctive, black markings. The underside is also pale with orange-brown lines. Malachites are on the wing all year in the tropics. They feed on fermenting fruit.


• **EARLY STAGES** The caterpillar is black with red spines. It feeds on *Blechnum* and *Ruellia*.

• **DISTRIBUTION** Widespread in South and Central America, migrating northwards to the USA, as far as Texas and southern Florida.



♂ ♀

strongly scalloped
hindwing margin
• with short tail



♂



NEOTROPICAL

Time of flight ☀

Habitat 🌿

Wingspan 6-8cm (2 1/4-3 1/8in)

Family NEMPHALIDAE

Species *Parthenos sylvia*


Author Cramer

CLIPPER


The clipper is an extremely variable butterfly with the background colour ranging from blue, to green or orange. However, the translucent, white forewing patches and dark markings are characteristic. The underside pattern is much paler. The sexes are similar. Clipper butterflies are attracted to *Lantana* blossom.

• **EARLY STAGES** The caterpillar is green to yellowish brown with dark purple spines. It feeds on *Adiantum palmata* and *Tinnspora cordifolia*.

• **DISTRIBUTION** From India and Sri Lanka through Malaysia to Papua New Guinea.



INDO-AUSTRALIAN



pattern of translucent white patches

distinctive black and orange striped body

♂

Time of Flight ☀

Habitat 🌿

Wingspan 10–10.5cm (4–4 1/8 in)

Family NYMPHALIDAE

Species *Labythia celtis*

Author Laichard

NETTLE-TREE BUTTERFLY


This is the only European representative of a group known as snout butterflies. The dark brown pattern and distinctive wing shape make it easy to recognize. The underside of the forewing is similar to the upperside but the hindwing is entirely greyish brown. These butterflies are on the wing from early summer to early autumn, and again in early and mid-spring, after hibernation.

• **EARLY STAGES** The caterpillar is brown or green. It feeds in small groups on nettle-tree (*Celtis australis*).

• **DISTRIBUTION** Central and southern Europe to North Africa, Japan, and Taiwan, with several described subspecies.



PALAARCTIC



distinctive "snout", characteristic of this group of butterflies




strongly "toothed" forewing




♂ ♀

Time of Flight ☀

Habitat 🌿

Wingspan 5.5–7cm (2 1/8–2 7/8 in)

Family	Nymphalidae	Species	<i>Libythea groffroyi</i>	Author	Godart
BEAK BUTTERFLY Males are black-brown with a purple sheen Females are dark brown with an irregular pattern of white patches. The undersides of the wings in both sexes are brown and white with a purple sheen. • EARLY STAGES Nothing is known. • DISTRIBUTION Burma, Thailand, Philippines, Papua New Guinea, and Australia.					
  <p>♂</p> <p>notched forewings</p> <p>♀</p> <p>scalloped hindwing margin present in both sexes</p>  <p>INDO-AUSTRALIAN</p>					
Time of Flight	☀	Habitat	🌳	Wingspan	5-5.5cm (2-2¼in)

Family	Nymphalidae	Species	<i>Libytheana carinenta</i>	Author	Cramer
SOUTHERN SNOOT BUTTERFLY The distinctive wing shape of this butterfly distinguishes it from any other North American butterfly, except for the snout butterfly (<i>Libytheana bachmanii</i>) which has brighter orange markings and occurs further north. The undersides of the forewings are paler than the uppersides, whereas the hindwings are speckled with greyish brown markings. The sexes are similar. Southern snout butterflies are on the wing throughout most of the year. • EARLY STAGES The caterpillar is dark green with yellow stripes. It is known to feed on <i>Celtis</i> . • DISTRIBUTION Occurs in light woodland and hilly scrubland areas, from Paraguay to Central America, migrating northwards as far as Kansas					
  <p>long snout</p> <p>♂ Δ</p> <p>characteristic triangle of white spots on wing-tips</p>  <p>NEOTROPICAL NEARCTIC</p>					
Time of Flight	☀	Habitat	🌳 🌿	Wingspan	4-5cm (1½-2in)

Family NYMPHALIDAE

Species *Morpho argus*

Author Hübner


BRAZILIAN MORPHO

Male Brazilian morpho butterflies are distinguished by their brilliant metallic-blue wings, which, in the past, were used to make butterfly jewellery. Females are very different to males, displaying a characteristic pattern of pale orange with blackish brown margins. They also have quite different forewing shapes, and altogether stronger patterning on the fore- and hindwings.

• **EARLY STAGES** The caterpillar is yellow, becoming white towards the tail. It is hairy, and has two red and black stripes on the back. This species is known to feed on bamboo (*Chusquea*).

• **DISTRIBUTION**

Common in Brazil.



NEOTROPICAL

Time of Flight ☼

Habitat 🌿

Wingspan ~9 cm (3 1/2 in)

Family NYMPHALIDAE

Species *Morpho menelaus*

Author Linnaeus

BLUE MORPHO

Both males and females of this beautiful species are deep metallic blue, but females have broad, black margins with white spots. The undersides of both sexes are brown with a row of brown ringed, orange eyespots outlined with pale metallic-bronze. Females also have a broken band of metallic-yellow bronze. Blue morphos fly rapidly through dense forest and feed on the juices of fallen fruit. Males are particularly active, chasing each other in bright sunlight. They will even chase

a blue cloth waved in the air; this device has been used by collectors to lure these fast-moving butterflies that are otherwise difficult to catch.


• **EARLY STAGES** The hairy caterpillar is reddish brown with brilliant, leaf-shaped patches of lime-green on the back. It feeds at night on *Persea caroliniana* and various other plants.

• **DISTRIBUTION** Widespread in the South American rainforest from Venezuela to Brazil.

wings of female have a more scalloped appearance than
• on male


dark leading edge
• to forewings

outer edges of
forewings are
black with two
white marks



characteristic
elongated
hindwings

"toothed" white
markings on
• wing margins



NEOTROPICAL

Time of Flight ☉

Habitat 🌿

Wingspan 13-14cm (5-5.5 in)

Family NYMPHALIDAE

Species *Morpho peleides*

Author Kollar


COMMON MORPHO

The male of this beautiful species of butterfly has more blue on the upperside than its female counterpart.

The undersides of the wings have a distinctive, striking pattern of black- and yellow-ringed eyespots on a brown background. Common morphos are attracted to fermenting fruit.

• **EARLY STAGES** The caterpillar at has fine brown, red, and black lines, and has two yellow patches on the back with red lines running through them. The body is covered with reddish brown and white hairs, which form tufts on the back. It feeds on the foliage of *Machaerium seemannii*, *Lonchocarpus*, and other plants of the pea family. If threatened, it is able to release a strong-smelling scent from a gland situated between the forelegs, which is intended to deter predators.

• **DISTRIBUTION** Common and widespread in Central and South America as well as the islands of the West Indies.



Range of Flight ☉

Habitat 🌿

Wingspan 9.5–12cm (3¾–4in)

Family NYMPHALIDAE

Species *Morpho ceteris*

Author Cramer

CRAMER'S BLUE MORPHO


Males are a spectacular metallic-blue colour. By contrast, the more robust females are orange brown and black with a pale orange yellow triangle on the forewing undersides. The undersides of both sexes are silvery greyish brown with dark spots near the wing bases.

• **EARLY STAGES** The pale, yellowish brown caterpillar has purplish brown markings and two pale, diamond-shaped patches on the back. It feeds on *Macarobium bijutum*.

• **DISTRIBUTION** Found in the jungles of Colombia, Venezuela, Ecuador, French Guiana, Surinam, and Guyana.



NEOTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 13–15cm (5–6 in)

Family NYMPHALIDAE

Species *Morpho laertes*


Author Drace

MOTHER-OF-PEARL MORPHO

This distinctive pale morpho has silvery white wings with a mother-of-pearl sheen. The upperside is marked with blackish brown on the forewing tips; the underside is more extensively marked with black, and there is a striking band of elongate golden eyespots on the hindwing. The sexes are similar. These morphos are attracted to fermenting fruit, particularly jackfruit (*Artocarpus*).

• **EARLY STAGES** The caterpillar is greyish brown to dark fawn, tinted with yellow, and has reddish brown spots on the back. The body is covered with hairs. It feeds on the foliage of *Inga*.

• **DISTRIBUTION** Confined to the forests of Brazil.



NEOTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 10-10.8cm (4-4 1/4 in)

Family NYMPHALIDAE

Species *Faunis canens*


Author Hubner

COMMON FAUN

This is an inconspicuous species. The uppersides of both sexes are a uniform brown, while the undersides are dark brown with blackish brown lines and white dots along the wing margins.

• **EARLY STAGES** The caterpillar is pale green and hairy. It feeds on wild banana (*Musa*).

• **DISTRIBUTION** Found in the jungles of India, Burma, and Malaysia.



INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌿

Wingspan 6-7.5cm (2 1/2-3 in)

Family NYMPHALIDAE

Species *Amathusia anythara*

Author Doubleday

KOH-I-NOOR BUTTERFLY


Males of this handsome and distinctive butterfly are backish brown with a broad, diagonal band of pale blue on the forewings. Females, on the other hand, have a band of dark yellow. The underside ranges in colour from brown to pinkish blue with black lines, and there are two eyespots on each hindwing. These butterflies are reluctant to fly unless disturbed, but seem to be most active towards dusk – even then, however, they do not fly very far. They tend to be attracted to fermenting fruit. Males are reputed to give off a sweet odour that persists, even after they are dead.

• **EARLY STAGES** Nothing seems to be known about the early stages of this butterfly.

• **DISTRIBUTION** This species occurs from India and Pakistan to Malaysia, Indonesia, and the Philippines. There are several described subspecies.



INDO-AUSTRALIAN



Time of flight



Habitat



Wingspan 1–17cm (4½–4 in)

Family NYMPHALIDAE

Species *Euplophiala camadeva*

Author Westwood

NORTHERN JUNGLE QUEEN

This species is very distinctive with its bluish white forewings spotted with black along the margin, and blackish brown hindwings with pale blue and white, marginal bands. The undersides are pale yellowish brown patterned with black and brown lines, white bands, and a row of black-ringed, orange eyespots. The sexes are alike.


These butterflies do not visit flowers, but are attracted to rotting fruit, fermenting sap, and cattle dung. They are powerful fliers, usually keeping close to the ground. Males are more active than females. There are generally two broods a year, with butterflies on the wing during the summer months.

• **EARLY STAGES** The caterpillar is apparently undescribed but it is most likely that it feeds on palms (*Palmae*) or bamboos (*Bambusa*).

• **DISTRIBUTION** Occurs in dense jungle from northern India and Pakistan to northern Burma.

diamond shaped
black markings
on forewings


single brown spot
on forewings



blackish brown
colour of hindwings
continues on to body

characteristic
white hindwing
margins

striking eyespots
on underside deter
attackers from
delicate body



NORTHERN JUNGLE QUEEN

Time of Flight ☀

Habitat 🌿

Wingspan 12-13cm (4 1/2-5in)

Family NYMPHALIDAE

Species *Thaonia alaris*

Author Westwood

TUFTED JUNGLE QUEEN

This large butterfly has square forewings, which are mainly black with a diagonal, white band. Males have a large patch of hair-like, specialized scales on their black and orange hindwings, but these are absent in the larger, but otherwise similar, females. The underside is strikingly patterned with orange, brown, and white.

Tufted jungle queens fly just before sunset.

They are attracted to fermenting fruit. They

belong to the subfamily

Amathusiinae, part of a

small group confined to South east Asia

• EARLY STAGES

Little is known of the

early stages of this

butterfly, but it has

been suggested that

the foodplant may be

bamboo (*Chusquea*).

• DISTRIBUTION

Widespread from Burma

to Thailand, Malaysia, and


Borneo. There are several

similar species in India.



INDO-AUSTRALIAN


white spot has a faded appearance



scale patches on hindwings

feather-like brown patterning on forewing

orange marking at hindwing base



large eyespots on hindwings to deter predators

Time of Flight



Habitat



Wingspan

11-13cm (4½-5 in)

Family NYMPHALIDAE

Species *Zeuxidia ornithystus*

Author Butler

SATURN BUTTERFLY

Males of this attractive species have sharply pointed forewings and a violet-blue patch on the hindwings. Females are larger than males. They are brown with yellowish brown markings and a diagonal, cream band on the forewing. The species is well camouflaged, as the undersides of both sexes are brown and patterned to resemble leaves.

- **EARLY STAGES** Little is known of the early stages, but caterpillars of other *Zeuxidia* species are known to be hairy with horns on both head and tail.
- **DISTRIBUTION** Found in forests in Thailand, Malaysia, and Sumatra.



INDO-AUSTRALIAN

scale patches on hindwings only present in males



Time of Flight ☉

Habitat ☿

Wingspan 7–10cm (2½–4 in)

Family NYMPHALIDAE

Species *Dynastor napoleon*

Author Westwood

BRAZILIAN DYNASTOR

This orange and brown butterfly is a rare species. The wings are dark brown and the undersides of the forewings are paler than the uppersides. The undersides of the hindwings have dark brown wing veins that give a leaf-like impression. Females are larger than males and their forewings are more rounded.

- **EARLY STAGES** Little is known of the early stages, but related species are green or brown with ring-like markings on the back. They feed on plants of the pineapple family Bromeliaceae.
- **DISTRIBUTION** Found in high-altitude rainforests in Brazil.




NEOTROPICAL

broad, orange band on hindwings

band of white patches on forewings

small, orange markings on wing-tips



Time of Flight ☉

Habitat ☿

Wingspan 12–16cm (4½–6½ in)

Family NYMPHALIDAE

SPECIES *Caligo idomeneus*

Author Linnaeus

OWL BUTTERFLY

This striking species belongs to a genus of large butterflies characterized by enormous owl-like eyespots on the undersides of the hindwings. In both sexes, the uppersides of the forewings are dark brown with a bluish suffusion and a white line running through. The hindwings are black with a dull blue base. The undersides of the wings have an intricate brown and white, feather-like pattern. Owl butterflies fly early in the morning and towards dusk.

• **EARLY STAGES** The large caterpillar is pale greyish brown, shaded with dark brown towards the head and the forked tail. It feeds on the foliage of Banana (*Musa*), and can often be a pest in plantations.

• **DISTRIBUTION** Widespread throughout South America, from Argentina up to Surinam



white, longitudinal line
• on forewing upperside

♂




prominent
center on
• forewings

brown
and white
underside
patterning

large owl-like
eyespot on the
hindwing
• undersides

♂ Δ



NEOTROPICAL

Time of Flight ☀️ 🌙

Habitat 🌿 🍌

Wingspan 12-15cm (4.7-6in)

Family NYMPHALIDAE

Species *Caligo atreus*

Author Linnaeus

COCOA MORT BLEU

The male of the cocoa mort bleu butterfly is blackish brown with a yellowish band and pale base to the forewing, while the base of the hindwing is shot with iridescent violet-blue. The female is larger than the male and has a darker forewing base. The undersides of both sexes are more ornate than the uppersides. They are intricately patterned with brown and have large, owl-like eyespots on the hindwings. These butterflies avoid bright sunlight and are on the wing in the afternoon and at dusk. They are attracted to fermenting fruit.

• **EARLY STAGES** The large caterpillar is pale brown with approximately five slender, dark bristles along the back and a pale, central oval, ringed with black. The tail is forked, and the head has a number of curved spines. It feeds on the foliage of various species of banana (*Musa*).

• **DISTRIBUTION** Occurs from Costa Rica to Guiana, Surinam, Guyana, and Ecuador.



veins are quite prominent on forewings

yellow-coloured band on forewings of male



narrow, yellow wing margins on upperside

characteristic owl-like eyespots on hindwings

hindwings more scalloped than forewings



NEOTROPICAL

Time of Flight ☉ ☿

Habitat 🌿

Wingspan 9.5-11 cm (3.5-4 in)

Family NYMPHALIDAE

Species *Erythraeus porycerus*


Author Meerburg

PURPLE MORT BLEU

This beautiful butterfly has iridescent, deep purple wings with black borders. Females are larger and lack the brilliant purple colour of the male, although they often have a purplish blue sheen. The undersides of both sexes, by contrast, are various shades of brown, with large eyespots on the hindwings. These butterflies have a rapid, dipping flight and frequent forest clearings in the late afternoon and at dusk.


• **EARLY STAGES** The caterpillar is pale brown with a series of five black bristles along the back. The long, forked tail is covered with hair, and the head has six short, curved spines. It feeds on bamboo (*Chusquea*).

• **DISTRIBUTION** Widely distributed in Central and South America, including the West Indies.



♂

• patch of yellowish scent scales on inner hindwing margins of male



♂ ♀

brown, leaf like pattern on undersides of wings



NEOTROPICAL

Time of Flight ☀️ ①

Habitat 🌿

Wingspan 8.25–10cm (3¼–4in)

Family NYMPHALIDAE

Species *Enides isabella*

Author Cramer

HELICONIUS MIMIC


This species of butterfly is boldly coloured with orange, yellow, and black. The underside is duller than the upperside, with orange markings suffused with brown.

• **EARLY STAGES** The caterpillar is black with distinctive white bands on the back. It feeds on passion flowers (*Passiflora*).

• **DISTRIBUTION** Occurs in Central and South America



NEOTROPICAL



♂

pale spots around hindwing margins

Time of Flight ☀

Habitat 🌿

Wingspan 57–75cm (24–3in)

Family NYMPHALIDAE

Species *Dryas iulia*

Author Fabricius

JULIA


This species is distinguished by its long, narrow forewings, and bright orange brown colour. Females are duller and lack a distinctive black marking on the leading edge of the forewing. The underside is patterned with various shades of orange-buff, and has two small, red spots close to the hindwing base. It visits garden flowers and wet ground.

• **EARLY STAGES** The spiny caterpillar is light brown in colour. It feeds on passion flowers (*Passiflora*).

• **DISTRIBUTION** Found in South and Central America, extending north to southern Texas and Florida, in the USA.

bright wing colouring indicates that this is a poisonous species

black forewing spot is characteristic of males




♂

hindwing fringe with white area



NEOTROPICAL



♂ Δ

two reddish brown markings on inner hindwings

Time of Flight ☀

Habitat 🌿

Wingspan 75–95cm (3–4in)

Family NYMPHALIDAE

Species *Agraulis vanillae*

Author Latreilles

GULF FRITILLARY


The long-winged butterfly is bright orange-red with black spots and wing veins. It is the striking, silver spotted underside that distinguishes this species and gives rise to its other common name, the silver spotted flambeau.

• **EARLY STAGES** The spiny, black caterpillar has two brownish red stripes along each side. It feeds on passion flower (*Passiflora*). Butterflies are strongly attracted to such flowers as a source of nectar.

• **DISTRIBUTION** This species is widespread and common from South America to the southern USA, migrating further north as far as the Rockies and the Great Lakes.

dark spotting
on inner
forewings •

striking, dark
wing veins •



black-ringed
orange spots •

slightly
indented
forewings •

comma-shaped
marking •

thin, silver
frenge to
hindwings •



♂ Δ



NEOTROPICAL
NEARCTIC

Time of Flight ☉

Habitat 🌿 urban

Wingspan 6.75 in (2/3 in)

Family NYMPHALIDAE

Species *Heliconius charithonia*

Author Latreilles

ZERRA

The striking black and yellowish bands on the upperside of this butterfly give rise to the common name. The underside is similar, but there are red spots at the wing bases.

• **EARLY STAGES** The caterpillar is white with black spines and black spots. It feeds on passion flowers (*Passiflora*).


• **DISTRIBUTION** Central and South America to southern parts of the USA.

elongated shape
of forewing •



♂

• long, slender abdomen,
typical of *Heliconius* species



NEOTROPICAL
NEARCTIC

Time of Flight ☉

Habitat 🌿

Wingspan 7.5-8 in (3-3 1/2 in)

Family NYMPHALIDAE

Species *E. andes heliconius*


Author Godart

SMALL FLAMBEAU


This orange and black butterfly is a miniature replica of southern forms of the Julia (*Dryas julia*, see p.159), and is part of a mimetic group.

• **EARLY STAGES** The caterpillar is black with long spines, and has a broad, white or yellow band along the sides. It feeds on passion flowers (*Passiflora*).

• **DISTRIBUTION** Southern Mexico to tropical South America, and includes Trinidad



NEOTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 4.5-5cm (1 7/8-2in)

Family NYMPHALIDAE

Species *Dione juno*

Author Cramer


SCARCE SILVER-SPOTTED FLAMBEAU

Often occurring in the same places as the very similar Gulf fritillary, this butterfly may be distinguished by its longer forewings and extensive dark brown markings on the underside.

The scarce silver-spotted flambeau is attracted to red and blue flowers.

• **EARLY STAGES** The caterpillar is mottled with light brown and covered with short hairs. The head is dark brown with short horns. The caterpillar feeds gregariously on passion flowers (*Passiflora*).

• **DISTRIBUTION** It is widely distributed in Central and tropical South America.



elongate forewing

"notched" appearance to hindwings

wing pattern continues on body

solid black hindwing fringe



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 6-7 cm (2 1/4-3in)

Family NYMPHALIDAE

Species *Heliconius doris*


Author Linnaeus

DORIS BUTTERFLY

This beautiful butterfly has three major colour forms. In all three the forewings are similar in their patterning of black and pale yellow, but the hindwing markings may be orange, blue or green. The underside of the forewing is similar to the upperside, the hindwing is black with white rays. The sexes are alike.

• **EARLY STAGES** The greenish yellow caterpillar has black bands and black spines. It feeds gregariously on old leaves of passion flowers (*Passiflora*).

• **DISTRIBUTION** Forest margins and clearings from Central to South America.




marginal row of small, white spots on hindwing

slight scalloping to hindwings

distinctive, comma-shaped markings

two white markings on forewing



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 8-9cm (3 1/4-3 3/4 in)

Family NYMPHALIDAE

Species *Heliconius melpomene*

Author Linnaeus

THE POSTMAN


Many species of this genus have forms that match so closely that they are very difficult to distinguish. The underside of the form illustrated is similar to the upperside, but is paler and has red spots at the base of the hindwing. These butterflies fly with the small postman (*Heliconius erato* see p.163), but tend to avoid direct sunlight.

• **EARLY STAGES** The caterpillar feeds on passion flower (*Passiflora*)

• **DISTRIBUTION** From Central America to southern Brazil.



NEOTROPICAL



this colour variety is just one of the many forms in this species

Time of Flight ☀

Habitat 🌿

Wingspan 6-8cm (2 1/4-3 1/4 in)

Family NYMPHALIDAE

Species *Heliconius erato*

Author Linnaeus

SMALL HELICONIUS

This butterfly has black forewings marked with cream, and orange hindwings with broad black borders. The underside is similar but duller, lacking the orange hindwing markings.

• **EARLY STAGES** Little is known of the early stages, although it is known to feed on passion flower (*Passiflora*).

• **DISTRIBUTION**

Central and South America to the Amazon Basin.



NEOTROPICAL



short, robust antennae •

• large orange patch on the hindwing

Time of Flight ☀

Habitat 🌿

Wingspan 5.5–7cm (2 1/4–2 3/4 in)

Family NYMPHALIDAE

Species *Heliconius erato*

Author Linnaeus

SMALL POSTMAN

This is an amazingly variable butterfly. Almost all variations are matched by parallel forms in the postman (*Heliconius melpomene* see p 162), and the two species occur in the same habitats. Similar forms occur in both sexes. Butterflies fly close to the ground along forest margins and open ground. They roost communally at night.

• **EARLY STAGES** The caterpillar of the species is white with black spots and spines, and a buff coloured head. It feeds on various passion flowers (*Passiflora*).

• **DISTRIBUTION** A common species from Central America to southern Brazil.

the distinctive spiny caterpillar of the
• small postman



CATERPILLAR OF
HELCONIUS ERATO

white spot on forewing tip •

characteristic long antennae •

characteristic elongated forewings •

orange hindwing rays are characteristic of this form •

pale hindwing bands are also present on the black underside •



long, slender abdomen •



NEOTROPICAL

Time of Flight ☀

Habitat 🌿 all vlt

Wingspan 5.5–8cm (2 1/4–3 1/4 in)

Family NYMPHALIDAE

Species *Philothris dido*

Author Linnaeus

SCARCE BAMBOO PAGE

Belonging to a complex of almost identical species, this butterfly is characterized by its beautiful, bluish green colour, and blackish brown markings. The underside is paler and has reddish brown and greyish brown markings. The sexes are similar. These butterflies feed on the nectar of *Lantana* and other flowers, preferring white, blue, and yellow varieties. They generally fly high in the tree canopy, but at times descend to drink and take in salts from damp ground.

• **EARLY STAGES** The caterpillar is pale green with blackish red markings and black tipped, red spines. It feeds on passion flowers (*Passiflora*).

• EARLY STAGES

The caterpillar is pale green with blackish red markings and black tipped, red spines. It feeds on passion flowers (*Passiflora*).

• **DISTRIBUTION** This complex of species occurs from Mexico to Argentina.

species has exceptionally long forewings • for its group



NEOTROPICAL

smaller blue spots on forewing leading edge •



scalloped hindwing margins

long, slender abdomen

two small white spots at base of forewing margin

Time of Flight ☼

Habitat 🌿

Wingspan 8-9.5cm (3 1/4-3 7/8 in)

Family NYMPHALIDAE

Species *Acraea andromacha*

Author Fabricius


GLASSWING

Appropriately named, this butterfly has transparent forewings, and white hindwings with black borders. The underside is similar, but the hindwing has larger white spots in the black marginal band. The sexes are similar, but females are larger.

• **EARLY STAGES** The caterpillar of this species is a glossy, yellowish brown, with long, black, branched spines arising from raised, bluish black spots. It feeds on passion flowers (*Passiflora*).


• DISTRIBUTION

Found from Indonesia to Papua New Guinea, Fiji, and Australia. The glasswing has a number of described subspecies.



INDO-AUSTRALIAN

spotting from underside shows through on pale forewings •



band of marginal white spots less developed than on underside

Time of Flight ☼

Habitat 🌿

Wingspan 5-6cm (2-2 1/4 in)

Family NYMPHALIDAE

Species *Acraea acerata*

Author Hewison

SWEET POTATO ACRAEA

This common little African butterfly varies from pale yellow to orange brown. The underside is paler and has distinctive, elongate, orange spots in the dark marginal band.

• **EARLY STAGES** The caterpillar is pale green with yellow and black spines. It feeds on sweet potatoes (*Ipomoea*) and can be a pest.

• **DISTRIBUTION** Tropical Africa from Ghana to eastern Africa.



AFRICO-TROPICAL

short robust antennae typical of the butterfly group •



♂

• warning colours indicate butterfly is distasteful

Time of Flight ☉

Habitat 🌳 🌿

Wingspan 3-4cm (1¼-1½in)

Family NYMPHALIDAE

Species *Acraea crata*

Author Hewison


YELLOW COSTER

This orange and dark brown butterfly is quite variable, and some specimens are almost entirely black. The underside is similar to the upperside but is paler and lacks the dark marginal bands.

Females are generally larger and more heavily marked.

• **EARLY STAGES** The spiny, black caterpillars have red heads. They live gregariously, which maximizes their unpleasant warning smell. They feed on *Boehmeria*, *Delonixia*, and *Buddleia*. Butterflies are most often found near the caterpillar's foodplant.

• **DISTRIBUTION** Open scrub country from northern India to Pakistan, Burma, and southern China.



♂

forewings much darker than hindwings

• black, U-shaped markings surrounding pale, marginal spots

reddish brown tinge to hindwing margin •



♀



INDIA-AUSTRALIAN

Time of Flight ☉

Habitat 🌳 🌿

Wingspan 4.5-8cm (1½-3¼in)

Family NYMPHALIDAE

Species *Acraea teles*

Author Linnaeus

LARGE SPOTTED ACRAEA

This orange and brown butterfly is very variable and several subspecies have been described, some of which are virtually completely suffused with black. The females are larger than the males. They have a greasy appearance and a paler underside.

• **EARLY STAGES** The caterpillar is ochreous yellow with black bands and spines. The head lacks spines. It feeds on passion flowers (*Passiflora*), *Adenia*, and other plants.

• **DISTRIBUTION** Widespread and common in Africa, south of the Sahara.

elongate forewings
• typical of species

orange spots along hindwing border



females much less vividly patterned than males

distinctive white shading

violet red tip to abdomen

white patch on forewing

dark spotting on inner hindwing margin



AFRICA

Time of Flight ☀

Habitat 🌳 🌾 🍄

Wingspan 6–7 5/8 in (2 1/2–3 in)

Family NYMPHALIDAE

Species *Aphantopus hyperantus*

Author Linnaeus

THE RINGLET


Males are blackish on the upperside, with a variable number of distinct eyespots, while females are larger and paler. The distinctive, yellow-ringed, underside eyespots give rise to the very appropriate common name.

• **EARLY STAGES**


The caterpillar is a pale yellowish brown with light and dark stripes. It feeds on various grasses. There is one generation each year.

• **DISTRIBUTION** It is widespread and common in Europe, extending into temperate Asia.

eyespot variable in size and number, and may even be absent



pale wing fringe



PALAEARCTIC

Time of Flight ☀

Habitat 🌳 🌾 🍄

Wingspan 4–4 5/8 in (1 1/2–1 3/4 in)

Family NYMPHALIDAE

Species *Actinote jellenei*

Author Hübner

SMALL LACE-WING

This butterfly is quite closely related to the *Acraea* butterflies of Africa. The combination of black and orange markings indicates that it is distasteful to birds.

• **EARLY STAGES** The life cycle is unknown, but caterpillars of related species have spiny bodies and smooth heads.

• **DISTRIBUTION** South America from Argentina to Venezuela, and the West Indies.



NEOTROPICAL

unusual, flattened clubs
on antennae

elongate, rounded
forewings



♂

Time of Flight ☀

Habitat 🌿

Wingspan 4.5–5cm (1½–2in)

Family NYMPHALIDAE

Species *Remiasthes apurice*

Author Hewitson

THE WANDERER

Males are black and orange, while the larger females are black and white and have more rounded forewings.

The undersides are similar but have distinctive reddish brown, black-spotted hindwing bases.

The butterflies have a relatively slow flight, and are attracted to flowers. This is a poisonous species that is mimicked by a number of more palatable African butterflies such as *Pseudacraea eurytus*.

• **EARLY STAGES**

The caterpillar is white, with purplish red spots and stripes, and yellow spines. It feeds on *Adenia gummifera* and passion flowers (*Passiflora*).

• **DISTRIBUTION**

This species occurs from Ethiopia and Sudan down to South Africa.




NEOTROPICAL

short, robust
antennae

forewing tip paler
than inner margin

male
forewing has
distinctive,
indented margin

♂



♀

black spotting
on inner hindwing

wing
veins
clearly
visible

Time of Flight ☀

Habitat 🌿

Wingspan 5.5–8cm (2¼–3¼ in)

Family NYMPHALIDAE

Species *Cephaotes helenor*

Author Fabricius


BLUE NIGHT BUTTERFLY

The iridescent blue of males of this species is most unusual in a group of predominantly brown butterflies. The underside is even more striking, with its distinctive black banding. By contrast females are brown, with a narrow, blue, marginal line on the upperside and blue below, with dark bands and eyespots.

• **EARLY STAGES** Nothing is known of the early stages of this species.

• **DISTRIBUTION**

Found from Surinam and Colombia to southern Brazil and the West Indies



NEOTROPICAL

heavy, black
veining on
forewings

♂



the narrow
blue marginal
band occurs in
both sexes

♂ Δ



two very small
eyespots on the
hindwing

Time of Flight ☀

Habitat 🌿

Wingspan 4cm (1.5in)

Family NYMPHALIDAE

Species *Cithaerias esmeralda*

Author Doubleday

THE ESMERALDA

This unusual and attractive butterfly belongs to a group in which the wings are almost entirely transparent. They are tightly sealed, and have veins and margins that appear dark brown. On the hindwing there is a pinkish patch that can vary in colour, and a yellow rimmed eyespot.

This butterfly becomes almost invisible when flying close to the ground in the dense rainforest where the light is poor.

• **EARLY STAGES** Nothing is known about the early stages of this species or its foodplant.

• **DISTRIBUTION**

Found in Brazil and Peru.




NEOTROPICAL

characteristic
rounded wings

thin, brown
margins to fore-
and hindwings

opaque purplish
pink patch on
hindwing

♂



Time of Flight ☀

Habitat 🌿

Wingspan 5cm (2in)

Family NYMPHALIDAE

Species *Geryonis pegala*

Author Fabricius

LARGE WOOD NYMPH


This is a variable species, ranging from light brown to blackish brown in colour. The underside is dark, brownish grey with white-centred, orange-rimmed, black eyespots, which are variable in number. The sexes are similar. It is often called the blue-eyed greyling, due to the bluish colour of the centre of the eyespots. Butterflies are on the wing from early summer to early autumn.

• **EARLY STAGES** The caterpillar is green, with longitudinal yellow lines, and two red tails.

• **DISTRIBUTION** In woodlands and meadows in the USA from central Canada to Florida.



NEARCTIC



Time of Flight ☀

Habitat 🌳 🌿

Wingspan 5–7.5cm (2–3in)

Family Nymphalidae

Species *Coenonympha moronta*

Author Edwards

PLAIN RINGLET


This butterfly is almost indistinguishable from some of the other *Coenonympha* species. The underside of the forewing is orange brown with a grey tip, and sometimes a single, small eyespot. The hindwing is olive-grey with a broken white band, and occasionally a few minute eyespots. Another common name for the butterfly is the prairie ringlet.

• **EARLY STAGES** The caterpillar is reddish brown, or olive-brown, with two tails. It feeds on various grasses.

• **DISTRIBUTION** Found in prairies, meadows, and woodland clearings from Canada to South Dakota and New York.



NEARCTIC




Time of Flight ☀


Habitat 🌳 🌿

Wingspan 2.5–4.5cm (1–1½in)


Family	NYMPHALIDAE	Species	<i>Coenonympha tulia</i>	Author	Müller
<p>LARGE HEATH</p> <p>This is a very variable species with many described subspecies. The ground colour and the spots can vary. Males are usually brighter.</p> <p>• EARLY STAGES The caterpillar is green, with a dark green line along the back, and white bands along each side. It feeds on sedge (<i>Carex</i>) and cotton grass (<i>Eriophorum</i>).</p> <p>• DISTRIBUTION Occurs in central and northern Europe</p>					
Time of Flight	☉	Habitat	☁ ☀ ♂ ♂	Wingspan	3-4 cm (1 1/4-1 1/2 in.)



Family	NYMPHALIDAE	Species	<i>Enodia portlandia</i>	Author	Fabricius
<p>PEARLY EYE</p> <p>The underside of this distinctively spotted butterfly is greyish brown, with dark brown and white bands and lines. The yellow-ringed eyespots are much more prominent on the underside. The hindwing eyespots have pearly white centres.</p> <p>• EARLY STAGES The caterpillar is yellowish green with red-tipped horns on the head and tail. It feeds on giant cane (<i>Arundinaria gigantea</i>).</p> <p>• DISTRIBUTION The USA; from Texas, south to Florida.</p>					
Time of Flight	☉ ☀	Habitat	☁ ☀	Wingspan	4.5-5 cm (1 1/4-2 in.)



Family	NYMPHALIDAE	Species	<i>Euphydryas cymela</i>	Author	Cramer
<p>LITTLE WOOD SATYR</p> <p>The orange-ringed eyespots of this dark brown butterfly each have two or more minute, metallic, silvery blue spots. Similar eyespots occur on the underside, but there is a series of rounded, metallic-silver spots between them.</p> <p>• EARLY STAGES The caterpillar is brown, sprinkled with tiny white, raised spots. It feeds on grasses. There is one brood a year in the north of its range, and two in the south.</p> <p>• DISTRIBUTION Common in woodland clearings from southern Canada to northern Mexico.</p>					
Time of Flight	☉	Habitat	☁ ☀	Wingspan	1.5-5 cm (1 1/4-2 in.)



Family NYMPHALIDAE

Species *Elymnias agestis*

Author Boisduval

PALMFLY


The male's pale, blue-tinged wing margins are more strongly developed in some forms. The underside has an orange patch, enclosing two eyespots, on each hindwing. The females have the same striking black and white pattern on each surface.

• **EARLY STAGES** The caterpillar is not described, but is known to feed on palms (Palmae).

• **DISTRIBUTION** From Papua New Guinea to northern Australia.



INDO-AUSTRALIAN



Time of Flight ☼

Habitat 🌿

Wingspan 7-9cm (2½-3½in)

Family	NYMPHALIDAE	Species	<i>Heteronympha merope</i>	Author	Fabricius
--------	-------------	---------	----------------------------	--------	-----------

COMMON BROWN

The sexes of this butterfly are very different. The male underside is similar to the upper surface, but has fewer dark markings and smaller eyespots. The underside of the female forewing is similar to the upperside, but the hindwing is mottled with reddish brown and greyish brown, and has a few eyespots.


• **EARLY STAGES** The caterpillar is very variable in colour, ranging from green to grey, or light brown, with darker mottling and two short tails. It feeds on grasses. There are one or two generations a year depending on locality.

• **DISTRIBUTION** Found in south-western and south-eastern Australia, including Tasmania.


female forewing is much broader, and less pointed at the tip



NON-AUSTRALIAN



♂



♀

scalloped hindwing margin similar on both sexes

Time of Flight	☺	Habitat	☹ ☹ ☹	Wingspan	5-6in (2-2½in)
----------------	---	---------	-------	----------	----------------


Family	NYMPHALIDAE	Species	<i>Maniola jurtina</i>	Author	Linnaeus
--------	-------------	---------	------------------------	--------	----------

MEADOW BROWN


This extremely common species has many described subspecies and forms. Males are generally smaller and darker. The undersides of both sexes are similar with orange forewings and brown hindwings, but females have more clearly defined light and dark regions.

• **EARLY STAGES** The caterpillar is green with long, white hairs and yellow lines along the sides. It feeds on grasses, particularly *Poa* and *Agrostis*.

• **DISTRIBUTION** Europe to North Africa, across to Iran



EUROPEAN



♂



♀

eyespot deters birds from the delicate body

irregular, dividing line of colours on the hindwing underside

scalloped hindwing margins

Time of Flight	☺	Habitat	☹ ☹ ☹	Wingspan	4-5.5cm (1½-2½in)
----------------	---	---------	-------	----------	-------------------

Family Nymphalidae

Species *Hypocysta gaudie*

Author Hübner

ORANGE RINGLET

This butterfly has golden-brown fore- and hindwings. The underside of the forewing is similar to the upperside but paler, and the hindwing eyespots are encircled by pale, greyish brown outer rings.


• **EARLY STAGES** The caterpillar is pinkish brown, with darker lines. The head is hairy, with a pair of pointed horns. It feeds on grasses.

• **DISTRIBUTION** Can be found in northern and eastern Australia with two described subspecies.



INDO-AUSTRALIAN

brown spot
in hindwing
corner



hindwing eyespots

Time of Flight ☀

Habitat 🌳

Wingspan 3-4 cm (1-1½ in)

Family Nymphalidae

Species *Hipparchia fagi*


Author Seesholtz

WOODLAND GRAYLING

Males tend to have the forewing band suffused with greyish brown and the eyespots are usually less well developed than those of the female. The undersides of the sexes are similar. Butterflies are on the wing in the summer.

• **EARLY STAGES** The caterpillar is pale, greyish brown to yellowish brown, with darker lines and stripes. It feeds chiefly on soft-grasses (*Holcus*). There is one generation a year.

• **DISTRIBUTION** It is widespread in open woodland in central and southern Europe.



jagged white band
to forewing

underside
hindwing pattern
provides good
camouflage when
species is at rest

scalloped
hindwings



PALAEARCTIC

Time of Flight ☀

Habitat 🌳

Wingspan 7-7.5 cm (2¾ in)

Family NYMPHALIDAE

Species *Yponomeuta epiaetha*


Author Linnaeus

MARBLED WHITE

Although quite variable in pattern, this is a very distinctive black and white butterfly. In some forms, the ground color is a strong yellow. The sexes are alike, although females tend to be larger and paler. Butterflies are on the wing in summer, and are attracted to the flowers of thistles (*Cirsium*), and knapweeds (*Centaurea*).

• **EARLY STAGES** The caterpillar is yellowish green or pale brown, with dark lines along the back. It feeds on fescues (*Festuca*).

• **DISTRIBUTION** It is widespread in Europe, extending to North Africa and western temperate Asia.



PALEARCTIC

broken marginal band on underside of hindwing

distinctive chequered pattern distinguishes this from other species



♂ Δ

Time of Flight ☀

Habitat 🌿 🌱

Wingspan 4.5–5.5cm (1 3/4–2 1/4 in)

Family NYMPHALIDAE

Species *Melanitis leda*

Author Linnaeus

EVENING BROWN

This butterfly has a very distinctive shape. The underside is mottled dark brown with very narrow, blackish brown margins, and resembles a dead leaf when the butterfly is resting with its wings closed. These butterflies are usually active at dawn, and just before dusk.


• **EARLY STAGES** The caterpillar is yellowish green, and densely covered with short hairs. It feeds on rice (*Oryza*), sugar cane (*Saccharum*), *Sorghum*, and various grasses.

• **DISTRIBUTION** Common from Africa to South-east Asia, and Australia.

AFROTROPICAL
INDO-AUSTRALIAN

slightly scalloped hindwings with small tails

"square" eyespots on forewing



♂

Time of Flight ☀

Habitat 🌿 🌱

Wingspan 6–8cm (2 1/2–3 1/4 in)

Family NYMPHALIDAE

Species *Minois dryas*

Author Scopoli

DRYAD BUTTERFLY


Males of this distinctive butterfly are smaller and darker than females, and tend to have smaller eyespots. The underside is paler, and there are sometimes grey bands on the hindwing. The butterflies are on the wing from early summer to early autumn.

• **EARLY STAGES** The caterpillar is dirty white, with dark markings, and two blackish brown stripes extending to the forked tail. It feeds on various grasses, especially purple moor grass (*Molinia*).

• **DISTRIBUTION** Can be found in open woodland and on grassy slopes in central and southern Europe, extending across temperate Asia to Japan.



PALAEARCTIC



Time of Flight ☼☼

Habitat ● 🌿 🌳

Wingspan 5–7cm (2–2¼in)

Family NYMPHALIDAE

Species *Pararge aegeria*

Author Linnaeus


SPECKLED WOOD

The sexes of this dappled woodland butterfly are very similar. Females have more rounded forewings. The eyespots on the upperside are much more developed than on the underside. The spots vary from creamy white to deep orange. Speckled wood butterflies often feed from the blossoms of bramble (*Rubus*).

• **EARLY STAGES** The caterpillar is yellowish green with a dark green stripe down the back, and light and dark lines along the sides. It feeds on couch (*Agropyron*) and other grasses.

• **DISTRIBUTION** Widespread in Europe, extending through to central Asia.

pale scalloping to wing edges



PALAEARCTIC

Time of Flight ☼

Habitat ● 🌿

Wingspan 4–4.5cm (1½–1¾in)

Family NYMPHALIDAE

Species *Parnara schukro*


Author Kollar

COMMON WALL BUTTERFLY

Although the upperside of this butterfly is not particularly distinctive, with its black and white eyespots set in orange patches on a brown background, the underside is more easily recognized, with its attractive hindwing row of multi-ringed eyespots, and its "scorched" forewings. These butterflies are active fliers, usually keeping close to the ground. They occur at most times of the year, on sunny hillsides above 2,000m (6,560ft).

• **EARLY STAGES** Although little seems to be known of the early stages, it is almost certain that the caterpillar feeds on grasses.

• **DISTRIBUTION** Occurs from Iran throughout northern India to western China.



PALEARCTIC
INDIAN SUBCONTINENT

marginal row
of double-ringed
eyespots

♀ ♂

distinctive
light and
dark wing
patches



Time of Flight ☀

Habitat: ▲

Wingspan 5.5-6cm (2¼-2½in)

Family NYMPHALIDAE

Species *Tagitis eche*

Author Cramer

NIGHT BUTTERFLY

This brown butterfly has a velvety black centre to the forewing. The underside is similar in coloration to the upperside, and has a marginal band of minute, yellowish white spots on the forewing, becoming larger on the hindwing. The sexes are similar.


• **EARLY STAGES** Little is known of the early stages although other members of the genus have smooth caterpillars that feed on grasses, and bamboos (*Chusquea*).

• **DISTRIBUTION** Found in tropical South America, from Surinam to Brazil. Also occurs in Trinidad.



NEOTROPICAL

forewing tip is suffused
with golden brown



♂

irregular scalloping of
the hindwing margin

dark colour makes
this butterfly difficult to
see when it flies at night

Time of Flight ☀ ☀

Habitat: 🌿

Wingspan 5.7-6cm (2¼-2½in)

Family NYMPHALIDAE

Species *Pierella hyceta*

Author Hewitson


HEWITSON'S PIERELLA

This distinctive angular-shaped butterfly, with its orange-tipped hindwings, belongs to a South American genus of about 50 species. The underside lacks the bright hindwing patch and so is better camouflaged when the butterfly closes its wings. The vertical lines crossing the wing veins are very noticeable.


The sexes are similar.

• **EARLY STAGES** Little is known of the early stages, although related species have dull brown caterpillars with short, double tails, and feed on the foliage of various Heliconiaceae and Marantaceae.

• **DISTRIBUTION** Widespread in South America from Brazil to Guyana



pale brown spot in corner of hindwing



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 1-1.5cm (1/4-3/8")

Family NYMPHALIDAE

Species *Chazara briseis*

Author Linnaeus

THE HERMIT

Females of this butterfly are larger than males, but are otherwise similar. The underside of the forewing is similar to the upperside, but the hindwing is mottled with brown and does not have the pale central band.

• **EARLY STAGES** The caterpillar is greyish white. It feeds mainly at night on blue moor grass (*Sesleria caerulea*).

• **DISTRIBUTION** Widespread in central and southern Europe, Turkey, and Iran



PALAEARCTIC



Time of Flight ☀

Habitat 🌿

Wingspan 4-7cm (1 1/2-2 1/4")

Family NYMPHALIDAE

Species *Trophone oberea*

Author Donovan

SWORD-GRASS BROWN

The orange forewing markings are an unusual shape, and the prominent hindwing eyespots divert predators from the vulnerable head and body. The underside is lighter, with a yellowish white band across the hindwings, and more strongly developed hindwing eyespots. Females are similar to males, but have paler markings.

• EARLY STAGES


The caterpillar is green and hairy. It feeds on sword-grass (*Cynusa*).

• DISTRIBUTION

Occurs in south-eastern Australia.



INDO-AUSTRALIAN



Time of Flight ☉

Habitat

Wingspan 5.5-5.8 cm (2.2-2.3 in.)

Family NYMPHALIDAE

Species *Ypthima asterops*

Author Kipp

AFRICAN RINGLET

This common butterfly is one of a group of very similar species that are difficult to distinguish. The underside is characteristically patterned with fine white lines. The sexes are alike.

• **EARLY STAGES** The caterpillar is undescribed. It feeds on grasses.

• DISTRIBUTION

Occurs in dry bush country throughout Africa, south of the Sahara, and south-western Asia.



AFROTROPICAL



Time of Flight ☉

Habitat

Wingspan 3-4 cm (1 1/4-1 1/2 in.)

Family NYMPHALIDAE

Species *Ypthima baldus*

Author Fabricius

COMMON FIVE RING BUTTERFLY

This species has five yellow-ringed eyespots on the fore- and hindwings. The upperside is brown, and is suffused with a pattern of small whitish lines. The sexes are similar. Adult butterflies are on the wing all year in the south, and in spring and summer in the north.

• EARLY STAGES


The green caterpillar feeds on grasses.

• DISTRIBUTION

This species occurs from India, to Pakistan, and Burma.



INDO-AUSTRALIAN



Time of Flight ☉

Habitat

Wingspan 3.4-5 cm (1 1/4-1 1/2 in.)

Family NYMPHALIDAE

Species *Speyeria sephus*

Author Hewitson

DARK CATSEYE BUTTERFLY

This is one of only three known species in the genus occurring in the region extending from India to China. The brown upperside of both sexes is virtually unmarked, but the underside bears distinctive, yellow-ringed eyespots, which give the species its common name.

Butterflies have a weak flight, and mostly stay in areas of dense bush.

• EARLY STAGES

Nothing seems to be known of the early stages of this species, although the caterpillar probably feeds on grasses.

• **DISTRIBUTION** It is common in the hill ranges of northern India, Pakistan, and Burma.

brown and yellow marginal lines are present on both surfaces

rudiments of an eyespot

upperside much plainer than the underside



slightly scalloped hindwing

white hindwing fringe

paler brown to wing margins

varying sizes of eyespots

small white-framed eyespot



striking, silvery-white band & surrounding hindwing eyespots



INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌿

Wingspan 5.7 cm (2 1/4 in)

Family NYMPHALIDAE

Species *Tellervo sulaw*

Author Fabricius

CAIRNS HAMADRYAS

The underside of this black and white species is similar to the upperside, but has white spots in the black margins. The sexes are similar.

• **EARLY STAGES** The caterpillar is dark grey coloured. It is known to feed on *parsonsia* (*Parsonsia*).

• **DISTRIBUTION** Found from Sulawesi to Papua New Guinea, as well as the Solomon Islands, and northern regions of Australia.

white spotting varies between different subspecies



long slender body



INDO-AUSTRALIAN

Time of Flight ☀

Habitat 🌿

Wingspan 4-4.5 cm (1 1/2 in)

Family NYMPHALIDAE

Species *Mechanitis ismaia*


Author Bates

COMMON MECHANITIS

The common mechanitis is believed to mimic a range of species belonging to several different groups. The underside is similar to the upperside, but with white spots in the black margins. Butterflies fly in bright sunlight and are attracted to flowers, especially those of *Eupatorium*.

• **EARLY STAGES** The caterpillar is pale green, with projections along the sides, each with a black dot at its base. They feed on *Solanum*.

• **DISTRIBUTION** Found from Mexico to the Amazon basin.



bright patterns resemble those of distasteful species

long slender body typical of this group



black bar extends to body

dark bordering borders



NEOTROPICAL

Time of Flight ☀

Habitat 🌿

Wingspan 6–8cm (2½–3in)

Family NYMPHALIDAE

Species *Heliconia hector*

Author Cramer

TIGER BUTTERFLY


This is a very variable butterfly that is mimicked by a wide range of both poisonous and palatable butterfly species. The black spots on the hindwing can be expanded to form a solid transverse band.

• **EARLY STAGES** The early stages of this species are apparently undescribed, but the caterpillars of a similar Central American subspecies are known to feed on *Prestonia*, and *Echites*.

• **DISTRIBUTION** Found throughout Mexico and down through to Brazil.



NEOTROPICAL



long, slender, orange antennae

white chequered wing fringes

characteristic orange marking on body

Time of Flight ☀

Habitat 🌿

Wingspan 5.5–7.5cm (2¼–3in)

Family NYMPHALIDAE

Species *Thyridia themisto*

Author Hübner

SMALL THYRIDIA


Belonging to a group of about seven described species from South America, this impressive butterfly has transparent wings, and strong black veins, bands, and margins. They are mimicked by several other species

of butterfly and moth, including the day-flying Castniid moth, *Gazera lara*.

• **EARLY STAGES** The caterpillar is black with bright yellow rings, indicating that the species is almost certainly poisonous. It feeds on manaca (*Brunfelsia*) shrubs.

• **DISTRIBUTION** Found widely in Argentina and Brazil, where it is often seen in towns.

transparent patches where wing scales are modified to form slender hairs



NEOTROPICAL

Time of Flight ☉

Habitat 🌿

Wingspan 7-8 cm (2 3/4-3 in)

Family NYMPHALIDAE

Species *Melinara lili*

Author Bates

MECHANITIS MIMIC


This highly variable butterfly mimics many different species belonging to various groups. It can be distinguished from similar species by its long, yellow antennae, and its relatively small head. The underside is similar in appearance to the upperside, but with white spots along the dark brown margins. They are on the wing for most of the year. Both sexes visit flowers.

• **EARLY STAGES** The caterpillar is conspicuously ringed. The area behind the head is red and pale orange-pink, and there are two whip-like, black and white filaments that twitch. It feeds on *Markea neorantha*.

• **DISTRIBUTION** Found from Mexico to the Amazon Basin.



NEOTROPICAL

CATERPILLAR OF
MELINARA LILI

the sparkling caterpillar is probably distasteful



black and orange pattern warns that this species may be poisonous

Time of Flight ☉

Habitat 🌿


Wingspan 7-7.5 cm (2 3/4-3 in)

Family	NYMPHALIDAE	Species	<i>Amantia cippus</i>	Author	Stoll
--------	-------------	---------	-----------------------	--------	-------


CHIEF BUTTERFLY

One of a group of very similar species, the chief butterfly varies geographically and has several described subspecies. Identification is further complicated due to the fact that this species is mimicked by certain *Papilio* species. The underside is very similar to the upperside, but has more small, white spots in the margins. The sexes are alike. These butterflies are on the wing at most times of the year.

- **EARLY STAGES** The caterpillar is black with yellow dots. It has five pairs of tapered, black filaments along its back. The head is smooth and black. It feeds on *Tylophora*, *Sesuvium*, *Marsdenia*, and other plants.
- **DISTRIBUTION** Tropical central Africa to South America.



AFROTROPICAL



pointed forewings

irregular, white spotting on forewings

orange-yellow hindwing traversed by black veins

♂


Time of Flight	☉	Habitat	☞	Wingspan	6-8cm (2 1/2 - 3 1/2 in)
----------------	---	---------	---	----------	--------------------------

Family	NYMPHALIDAE	Species	<i>Danais chrysippus</i>	Author	Linnaeus
--------	-------------	---------	--------------------------	--------	----------


PLAIN TIGER

This very common and distinctive butterfly displays warning colours of black and orange. There are many minor variations in pattern, and some forms lack the dark forewing tip with white spots. The underside is similar to the upperside, but is paler. Several other butterfly species are convincing mimics of the plain tiger. Also commonly known as the African monarch, and the lesser wanderer, this species can be seen on the wing at most times of the year.

- **EARLY STAGES** The caterpillar is banded with orange, black and buff white. It feeds on milkweeds (*Asclepias*), and other related plants.
- **DISTRIBUTION** From Africa, to India, Malaysia, Japan, and Australasia.



AFROTROPICAL
INDOAUSTRALIAN
PALEARCTIC



dark brown leading edge

to forewing

black and white wing fringes occur on all forms

♂

size and distribution of hindwing spots distinguishes various forms

Time of Flight	☉	Habitat	☞	Wingspan	7-8cm (2 1/2 - 3 1/2 in)
----------------	---	---------	---	----------	--------------------------

Family NYMPHALIDAE

Species *Euploe core*

Author Cramer


COMMON INDIAN CROW

One of a group of rather similar butterflies, this is the commonest. It has a number of described races and forms which vary greatly in the degree of spotting.

The underside is similar to the upperside, but is paler. The sexes are similar.

• **EARLY STAGES** The caterpillar is white, strongly ringed with dark brown. It has yellow and white stripes along the side, and four pairs of purplish brown filaments along the back. It feeds on a wide range of plants including oleander (*Nerium oleander*) and milkweeds (*Asclepias*).

• **DISTRIBUTION** Found from India to China, Sumatra, and Java, and also in northern and eastern Australia.



Time of Flight ☉

Habitat

Wingspan 8–9.5cm (3¼–3½in)

Family NYMPHALIDAE

Species *Donans gilippus*


Author Cramer

QUEEN BUTTERFLY

This handsome butterfly is dark, orange-brown, with black borders and white spots. The underside is paler, and the hindwings have more prominent black veining.

• **EARLY STAGES** The caterpillar is pale, bluish grey, with transverse black rings, and bands spotted with reddish orange. The caterpillar feeds on milkweeds (*Asclepias*).

• **DISTRIBUTION** Widely distributed from Argentina to Central America and southern parts of North America. This is not a migrant species, unlike most of its relatives.



Time of Flight ☉

Habitat

Wingspan 7–7.5cm (2¾–3in)

Family NYMPHALIDAE

Species *Danaus plexippus*


Author Linnaeus

MONARCH BUTTERFLY



With its bold pattern of black and orange, and wing veins enhanced by dark borders, this is one of the best-known butterflies. The sexes are alike.

• **EARLY STAGES** The caterpillar is banded with black, yellow, and cream, and has tentacles behind the head. It feeds on milkweeds (*Asclepias*), and related plants.

• **DISTRIBUTION** This butterfly is a well-known migrant. It has spread from its home in the Americas to Indonesia, Australasia, and the Canary Islands, and has recently established colonies in Mediterranean countries.



WORLDWIDE



Time of Flight ☀

Hibernates ❄

Wingspan 7.5–10cm (3–4in)

Family NYMPHALIDAE

Species *Euploea mulciber*

Author Cramer

STRIPED BLUE CROW

The uppersides on the forewings of both sexes of this large butterfly are shot with iridescent purple, although it is most evident in the darker male. The female has brown hindwings shot with white lines. The undersides are similar, but lack the iridescence. This species belongs to a large Indo-Australian genus known as crow butterflies because of their iridescent dark colours. Both caterpillars and adults are poisonous.

• **EARLY STAGES** The caterpillar is yellowish brown, with paler and darker bands, and four pairs of black-tipped, red filaments. It feeds on oleander (*Nerium*), fig (*Ficus*), and various pipevines (*Aristolochia*).

• **DISTRIBUTION** India to southern China, Malaysia, and the Philippines.



INDO-AUSTRALIAN



Time of flight ☼

Habitat 🌿

Wingspan ♀ 10cm (3 7/8 in)

Family NYMPHALIDAE

Species *Idea leuconoe*

Author Erichson

LARGE TREE NYMPH

The large wings of this delicate butterfly are translucent greyish white, with distinctive black markings. The wings are often suffused with yellow towards the base.

Large tree nymphs have a slow gliding flight, and prefer to remain just below the forest canopy.

• **EARLY STAGES** The caterpillar is velvety black, with narrow, pale yellow rings, and red spots. There are four pairs of black filaments running along its back. It feeds on *Parsonsia*, *Cynanchum*, and *Tylophora*.

• **DISTRIBUTION** From Thailand to Malaysia, the Philippines, and Taiwan. In Malaysia it is largely coastal, in mangrove swamps.

distinctive,
red and black
• patterning



CATERPILLAR OF
IDEA LEUCONOE

colour and
pattern
continue
on body •

white, zigzag
line parallel to
wing margins •



slightly •
angular
outline to
hindwings

slender body and •
large wings indicate
a weak flier



INDO-AUSTRALIAN

• white spots
give scalloped
effect

Time of Flight ☀

Habitat 🌿

Wingspan 9.5–10.8cm (3¾–4¼ in)

Family NYMPHALIDAE

Species *Ideopsis virna*

Author Blanchard

BLANCHARD'S IDEOPSIS

This beautiful species is very variable with several described subspecies, ranging in colour from white to green.


The darker male's forewings are more slender and pointed than those of the female.

• **EARLY STAGES** The caterpillar and its foodplants are unknown. Other *Ideopsis* species have pale, spotted bodies with one pair of tentacles near the head, and a second pair close to the tail.

• **DISTRIBUTION** Found in woodlands, from Sulawesi, through the Moluccas, to Papua New Guinea.



INDONESIA & EAST MALAYSIA



Time of Flight ☀

Habitat 🌿

Wingspan 7–9.5 cm (2½–3¼ in)

Family NYMPHALIDAE

Species *Lycorea cleobaea*

Author Godart

LARGE TIGER

It's extremely variable butterfly resembles certain *Heliconius* species, but actually belongs to a sub-family of its own.


• **EARLY STAGES**

The caterpillar is white with black rings, and a pair of black, flexible tentacles. It feeds on plants including fig (*Ficus*) and pawpaw (*Carica papaya*).

• **DISTRIBUTION** Mexico to Brazil. Occasionally strays into southern USA.



NEOTROPICAL



Time of Flight ☀

Habitat 🌿

Wingspan 7–8 cm (2½–3¼ in)



MOTHS



THYATRIDAE

THE MOTHS BELONGING to this fairly small family, containing about 100 species, occur in many parts of the world. They are, however absent from the Afrotropical and Indo-Australian regions. Sometimes referred to collectively as the lutestrings, these medium-sized moths are generally fairly dull in colour. Nevertheless,

there are some exceptions that are quite distinctively and attractively marked with pink spots or pale lines.

The smooth caterpillars either live openly on foliage, or else conceal themselves between leaves woven together with silk, where the pupae are formed in their silken cocoons.

Family	THYATRIDAE	Species	<i>Habrosyne scripta</i>	Author	Gosse
<h3>LETTERED HABROSYNE</h3> <p>The fine white markings on the brown forewings of this beautiful moth give rise to the common name. In life the broader white bands are suffused with pink, but this fades in preserved specimens.</p> <ul style="list-style-type: none">• EARLY STAGES The caterpillar is dark brown with black markings. It feeds on birches (<i>Betula</i>) and blackberry (<i>Rubus fruticosus</i>).• DISTRIBUTION Occurs throughout Canada, and southwards to Arkansas and Missouri. <div><p>NEARCTIC</p></div> <div><p>intricate loops are characteristic of species</p><p>wing pattern continues across body</p></div>					
Time of Flight	☾	Habitat	●	Wingspan	3-4cm (1 1/2 - 1 1/2 in)

Family	THYATRIDAE	Species	<i>Thyatira batis</i>	Author	Linnaeus
<h3>PEACH BLOSSOM</h3> <p>The beautiful, pinkish white-ringed, yellow-brown spots on the forewing of this moth give rise to its unusual common name. The ground colour of the forewing is chocolate-brown while the hindwing is a shining, pale greyish brown.</p> <ul style="list-style-type: none">• EARLY STAGES The caterpillar is reddish brown with pale, triangular markings, and a series of small, forward-pointing humps along its back. It feeds on blackberry (<i>Rubus fruticosus</i>).• DISTRIBUTION Europe across temperate Asia to Japan. <div><p>PALEARCTIC</p></div> <div><p>distinctive forewing patches</p><p>distinctly "furry" appearance of the body</p></div>					
Time of Flight	☾	Habitat	●	Wingspan	3-4cm (1 1/2 - 1 1/2 in)

DREPANIDAE

THIS GROUP OF about 800 species occurs throughout the world, with the exception of Central and South America. The most distinctive characteristic of the Drepanidae is the strongly curved forewing tip that is present in many species. This gives rise to the name hook-tips which is popularly applied to this group. Moths have very poorly formed tongues or no tongue at all, and so are unable to feed

in this stage. The caterpillars of this group are distinctive as they lack the pair of claspers at the end of the body that are common in other families. In many species the body tapers to a distinctive pointed tail instead.

Caterpillars usually feed on the foliage of broad-leaved trees and shrubs. The pupae are sometimes covered with an unusual bluish, waxy coating.

Family DREPANIDAE

Species *Drepana arcuata*

Author Walker

ARCHED HOOK-TIP

This distinctive moth has a particularly sharply pointed hook to the wing-tip that distinguishes it from all other North American moths of this group. The ground colour ranges from pale yellowish white to orange-yellow, and the reddish brown markings vary in distinctness. The hindwing is similar to the forewing, but is paler. The sexes are alike. Moths are on the wing from mid-spring to early autumn.

• **EARLY STAGES** The caterpillar feeds on alders (*Alnus*) and birches (*Betula*). It is green and brown with yellow markings.

• **DISTRIBUTION** From Canada to South Carolina.



NE-ARCTIC



feathered antennae of males

distinctive, dark forewing band extends into 'hook-tip'

dark brown marginal line extends round the hindwings

Time of Flight

Habitat

Wingspan 2.5-5cm (1-2in)

Family DREPANIDAE

Species *Oreia warreni*

Author Warren

WARREN'S HOOK-TIP


This genus of about 40 species is mostly found in eastern and south eastern Asia. The male moths of this group are unusual in that they lack the wing-coupling bristle typical of moths. The upperside of Warren's hook-tip has a glossy sheen, and varies in colour from yellowish to dark purplish brown.

• **EARLY STAGES** Nothing is known about the early stages of this species.

• **DISTRIBUTION** Common in north-east Queensland, in Australia, and so can be found in Papua New Guinea.



INDO-AUSTRALIAN



base of forewing has distinctive patch of silvery white scales

hairy appearance of inner hindwing margin

Time of Flight

Habitat

Wingspan 2.5-4.5cm (1-1½in)

URANIIDAE

ALTHOUGH THIS is a fairly small family of moths, it contains some of the most striking species to be found in the world, including the stunning Madagascan sunset moth (see opposite). They are found in the tropics of America, Africa, and Indo-Australia. The day-flying species are more vivid and beautifully coloured than the night fliers; many have

iridescent scaling and very well developed tails to their wings, so that they are often mistaken for butterflies. Those species that fly at night are mostly rather flimsy insects that have white or pale-coloured wings, with darker stripes. Uraniidae are similar to the Geometer moths (Geometridae), to which they are related, but they differ in the arrangement of their wing veins

Family URANIIDAE

Species *Abrides zodiaca*

Author Butler


ZODIAC MOTTH

This is the only member of this genus of eleven day-flying species to occur in Australia. The wings are black with coppery green tones and purplish pink iridescent bands. The hindwing margins are strongly scalloped and have short but distinct, pale bluish green tails. The underside is pale, iridescent bluish green with black bands. The moths commonly visit flowers by day, and in the evening fly high in the forest canopy.


• EARLY STAGES

The caterpillar is black with white bands and an area of bright red on the back, behind the head. It feeds on the foliage of a large vine, *Omphalea queenslandiae* and also on *Endospermum*.

• **DISTRIBUTION** Papua New Guinea and north-eastern Australia



INDO-AUSTRALIAN



Time of Flight ☀

Habitat 🌿

Wingspan 8-10cm (3 1/4-4in)

Family URANIIDAE

Species *Chrysiridia rhipheus*

Author Hübner


MADAGASCAN SUNSET MOTH

This is often regarded as the most spectacular and distinctive of all moths. Its colours made it popular with the Victorians, who used its wings to make jewellery. The hindwings have numerous short and slender tails.

- **EARLY STAGES** The caterpillar is yellow and black with long, club-tipped hairs. It feeds on the foliage of *Omphalea*. The poisonous foodplant and bright colours of the moth suggest that it is distasteful to birds and animals.
- **DISTRIBUTION** Confined to Madagascar.



AFROTROPICAL



Time of flight ☀

Habitat 🌿

Wingspan 8–10cm (3¼–4in)

Family URANIIDAE

Species *Uranus sloanus*

Author Cramer

SLOANE'S URANIA


One of the most spectacular Caribbean day-flying moths, Sloane's urania has hindwings marked with multicoloured, iridescent scales. The underside is pale, metallic-bluish green with narrow black bands. This is the South American counterpart of the Madagascan sunset moth (see above).

- **EARLY STAGES** The caterpillars are marked black, blue, and white, indicating that they are probably poisonous. They have distinctive clubbed hairs and feed on the foliage of *Omphalea*.
- **DISTRIBUTION** Confined to Jamaica.



NEOTROPICAL

these moths are distinguished by their long hindwing tails



Time of flight ☀

Habitat 🌿

Wingspan 5–7cm (2–2½in)

GEOMETRIDAE

THIS is the second largest family of moths, containing approximately 15,000 described species. Geometridae or "Geometers" typically have fairly large, rounded wings and slender bodies, and their flight is weak and fluttering. In such a large group, however, there are many deviants. In a number of species, the wings of the females are reduced to tiny vestiges so

that they are unable to fly. Although most species are rather dull in colour and will frequently display camouflage patterns, there are a few tropical groups that are actually very brightly coloured. The name Geometridae refers to the looper caterpillars of this family, which are so-called because of their wholly characteristic, ungainly walk. They are also known in the USA as inchworms.

Family GEOMETRIDAE

Species *Archaea infans*

Author Möscher

THE INFANT


The infant is a distinctive, little moth with a hairy appearance, enhanced by its long, coarse wing fringes. The forewings are blackish brown sprinkled with white scales, while the hindwings are orange making this an easy species to recognize. The sexes are similar. These moths are on the wing from early to late spring and may be seen flying on warm afternoons.

• **EARLY STAGES** The caterpillar is green to reddish brown, with fine yellowish white lines along the body. It feeds on the foliage of birch (*Betula*).

• **DISTRIBUTION** Occurs in birch woodlands from Canada to northern USA.



NEARCTIC



Time of Flight ☀

Habitat 🌳

Wingspan 3-4cm (1¼-1½in)

Family GEOMETRIDAE

Species *Alophila pametaria*

Author Harris

FALL CANKERWORM MOTTH

The males of this species are pale greyish brown with a greyish white, serrated line crossing both pairs of wings. Females are totally flightless, their wings having been reduced to tiny vestiges. The moths fly in early winter.

• **EARLY STAGES** The brown and white, or green and white, striped caterpillar is a pest of apple (*Malus domestica*) and other fruit trees, broad-leaved trees such as maple (*Acer*) and oak (*Quercus*).

• **DISTRIBUTION** Widespread in northern USA and southern Canada. A similar species, the March moth (*Alophila vesicularia*), occurs in Europe.

wing veins are clearly visible in this lightly scaled moth



NEARCTIC

Time of Flight ☾

Habitat 🌳

Wingspan (males) 2.5-3cm (1-1¼in)

Family GEOMETRIDAE

Species *Oenochroma vinaria*

Author Guenée

HAKEA MOTH

This moth varies in colour from grey, to purplish red and lobster-pink. The sexes are alike, although females are generally larger. Hakea moths are on the wing throughout the year.

- **EARLY STAGES** The caterpillar is green to reddish brown or purplish red, with a pair of small warts in the middle of its back. It feeds on *Grevillea* and *Hakea*, resting stretched out on twigs by day.
- **DISTRIBUTION** Widespread in eastern and southern Australia, including Tasmania.

caterpillar is in a typical resting position




CATERPILLAR OF
OENOCHROMA VINARIA

hooked up in forewings

dark bands are present in all colour forms



characteristic dark purple spot on underside of forewing



INDO-AUSTRALIAN

Time of Flight

Habitat

Wingspan 4.5–5.5cm (1½–2¼in)

Family GEOMETRIDAE

Species *Chlorocoma dichloraria*

Author Guenée

GUENEE'S EMERALD

Guenée's emerald is the largest of about 20 species of this genus occurring in southern Australia, many of which are bluish green in colour. The females are unusual in that they lack the wing-coupling bristles. The underside is similar to, but paler than, the upperside. The sexes are similar but only males have feathered antennae.

- **EARLY STAGES** The looper caterpillar feeds on foliage of acacia.
- **DISTRIBUTION** Widespread in eastern and southern Australia, including Tasmania.



INDO-AUSTRALIAN

characteristic zigzag white lines



striking red wing fringes

Time of Flight


Habitat

Wingspan 2.5–3cm (1 1/4in)

Family	GEOMETRIDAE	Species	<i>Aporandria specularia</i>	Author	Guenée
LARGE GREEN APORANDRIA <p>This large green moth has brown markings on the hindwing. The underside is a pale, slightly iridescent green. The sexes are similar, although males have more strongly feathered antennae.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is undescribed. It feeds on mango (<i>Mangifera indica</i>). • DISTRIBUTION Widespread from India and Sri Lanka to Malaysia, Sumatra, the Philippines, and Sulawesi. 					
Time of Flight		Habitat		Wingspan 4.5–6cm (1½–2½in)	




INDO-AUSTRALIAN



Family	GEOMETRIDAE	Species	<i>Geometra papilionaria</i>	Author	Linnaeus
LARGE EMERALD <p>This bluish green moth is large and distinctively shaped. The wings are patterned with inconspicuous broken white lines. The sexes are similar, except that males have feathered antennae.</p> <ul style="list-style-type: none"> • EARLY STAGES The yellowish green caterpillar feeds on birch (<i>Betula</i>), beech (<i>Fagus sylvatica</i>), alder (<i>Alnus</i>), and hazel (<i>Corylus</i>). • DISTRIBUTION Widespread in Europe, extending across temperate Asia to Japan. 					
Time of Flight		Habitat		Wingspan 4.5–6cm (1½–2½in)	



PALEARCTIC



Family	GEOMETRIDAE	Species	<i>Omphax planitaria</i>	Author	Guenée
SMOOTH EMERALD <p>This moth belongs to a large group of African species, many of which are bright green or blue-green. This species is a uniform green with purplish red and cream lines around the margins. There is a line of purplish red along the body towards the tail. The sexes are similar.</p> <ul style="list-style-type: none"> • EARLY STAGES Little is known about the early stages, except that it has a looper caterpillar which feeds on the foliage of <i>Vangueria</i>. • DISTRIBUTION Extends through southern Africa from Zimbabwe and Mozambique to Transvaal and Natal. 					
Time of Flight		Habitat		Wingspan 3–4cm (1¼–1½in)	



AFROTROPICAL



Family GEOMETRIDAE

Species *Crypsophona ocularia*

Author Donovan

RED-LINED GEOMETRID

The distinctive feature of this grey and white moth is its strikingly coloured underside, which has bold, red and black bands on the white, scalloped hindwings. The upperside's grey wing patterning is continued on the body. The sexes of this moth are similar. These moths are on the wing at most times of year, and are commonly found in the dry sclerophyll forests in southern Australia.

• **EARLY STAGES** The caterpillar is bluish green with a yellowish white line along the sides, making it well camouflaged when it feeds on young or mature foliage of eucalyptus.

• DISTRIBUTION

This species is found in Eastern and southern Australia, from Queensland to Victoria and Tasmania.



INDO-AUSTRALIAN

yellowish
marking on
wing bases

feathered
outcrops of
male moth

white
wing
margins

hindwing
has strongly
scalloped
fringes

♂ Δ

Time of Flight ☾

Habitat 🌿

Wingspan 4-5cm (1½-2in)

Family GEOMETRIDAE

Species *Dysphania cuprina*

Author Fiedler

COPPERY DYSPHANIA

This species is one of a large group of brightly coloured, mainly day-flying, tropical moths. They are generally regarded to be distasteful to birds and are distinctively patterned in the warning colours of orange, black, and white. They often fly in company with similarly coloured butterflies. The underside is similar to the upperside, with the orange coloration being even brighter.

The sexes are similar.

• **EARLY STAGES** Although little is known of the biology of this species, caterpillars of *dysphania* moths are generally yellow with a distinctive pattern of black or bluish black markings. Some species are known to feed on the foliage of species of *Carallia*.

• DISTRIBUTION

Widespread from India and Pakistan to Indonesia, the Philippines, and Papua New Guinea.



INDO-AUSTRALIAN

bright colours
of wings
indicate moth
is probably
poisonous

distinctively
shaped,
angular
hindwing


♀

Time of Flight ☾ ☼


Habitat 🌿

Wingspan 7-7.5cm (2¾-3in)

Family	GEOMETRIDAE	Species	<i>Rhodometra saccharia</i>	Author	Linnaeus
THE VESTAL <p>The colour of the forewings varies from pale yellow to deep straw-coloured, with the diagonal band ranging from pinkish-red to brown. Bright red forms may occur if the pupae are exposed to extremes of temperature.</p> <ul style="list-style-type: none"> • EARLY STAGES The long, thin caterpillar is pale brown or green. It feeds on knorgrass (<i>Polygonum</i>), camomile (<i>Anthemis</i>), and other plants. • DISTRIBUTION A migrant species occurring throughout Europe, and ranging to North Africa and northern India. 					
Time of Flight	☾	Habitat	☹ ☹ ☹	Wingspan	2.5–3cm (1–1¼in)



PALAARCTIC




♂



Family	GEOMETRIDAE	Species	<i>Eratina staudingeri</i>	Author	Snellen
STAUDINGER'S LONGTAIL <p>This unusual moth belongs to a large, tropical American group of species with the hindwings ranging from rounded to extremely elongate. This species is one of the most striking examples of its group. The black and orange pattern suggest it is poisonous. The underside is a rich reddish brown to orange, banded and lined with lemon-yellow.</p> <ul style="list-style-type: none"> • EARLY STAGES Nothing seems to be known of the early stages. • DISTRIBUTION Found in the tropical forests of Venezuela. 					
Time of Flight	☉	Habitat	☹	Wingspan	3–4cm (1¼–1½in)



NEOTROPICAL



♀



Family	GEOMETRIDAE	Species	<i>Operophtera brumata</i>	Author	Linnaeus
WINTER MOTH <p>While males have normally developed wings, patterned with greyish brown, the wings of the female are reduced to short stubs.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is green, usually with a dark line along the back. It feeds on the foliage of broad-leaved trees, including fruit trees such as apple (<i>Malus domestica</i>) and pear (<i>Pyrus communis</i>). It will also feed on heather (<i>Calluna vulgaris</i>). • DISTRIBUTION Widespread and common throughout Europe, ranging across temperate Asia to Japan. Also occurs in Canada. 					
Time of Flight	☾	Habitat	☹ ☹ ☹	Wingspan	(male) 2.5–3cm (1–1¼in)



HOLARCTIC



♂



Family GEOMETRIDAE

Species *Rheumaptera hastata*

Author Linnaeus

ARGENT AND SABLE


This striking, black and white patterned moth has an appropriate common name. The sexes are alike. In North America it is also called the spear-marked black.

• **EARLY STAGES** The caterpillar is olive-green to brown with a dark line along the back. In Europe it feeds on birches (*Betula*) and bog myrtle (*Myrica gale*), but in North America it feeds on a wide range of trees and shrubs.

• **DISTRIBUTION** Found in Europe, extending to temperate Asia and North America



HOLARCTIC



Time of Flight ☾

Habitat 🌳 🌿 🍄

Wingspan ♂ 5–4cm (1 7/16 in)

Family GEOMETRIDAE

Species *Venusia cumbriae*

Author Curtis

WELSH WAVE

The forewings of this pale coloured moth are characteristically patterned with greyish brown.


The hindwings are plain cream. The sexes are similar.

• **EARLY STAGES** The caterpillar is yellowish green and variably marked with patches of reddish brown. It feeds on rowan (*Sorbus aucuparia*), and a wide range of other trees such as alder (*Alnus*) and apple (*Malus domestica*) in North America.

• **DISTRIBUTION** Widespread in Europe, ranging across temperate Asia to Japan. Also occurs in Canada and northern USA.



HOLARCTIC



Time of Flight ☾

Habitat 🌳 🌿 🍄

Wingspan ♂ 5–3cm (1–1 1/4 in)

Family GEOMETRIDAE

Species *Xanthorhoe fluctuata*

Author Linnaeus

GARDEN CARPET


This is a very common and variable species with both pale forms and more anic forms that are almost black. It can usually be recognized by the square black markings on the mid-frontal area of the forewings. They are to be seen on the wing from mid-spring to mid-autumn.

• **EARLY STAGES** The caterpillar is coloured grey, brown, or green. It feeds on cabbage (*Brassica*) and related plants, and curls up when resting.

• **DISTRIBUTION** Very common in gardens and hedgerows throughout Europe, ranging to North Africa and Japan.



PALEARCTIC




Time of Flight ☾


Habitat 🌳 🌿 🍄

Wingspan ♂ 2.5–3cm (1–1 1/4 in)

Family	GEOMETRIDAE	Species	<i>Abraxas grossularia</i>	Author	Linnaeus
MAGPIE MOTH <p>This is a very variable moth ranging from white with narrow, yellow and black bands, to black with white wing bases. The typical form is illustrated.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is yellowish white with black spots and an orange-red line along the side. It feeds on the foliage of a wide range of shrubs and it is sometimes a pest of gooseberry (<i>Ribes grossularia</i>). • DISTRIBUTION Widespread in Europe, extending across temperate Asia to Japan. 					
Time of Flight	☾	Habitat	● on shr.	Wingspan	4–5 cm (1½–2 in)




PALEARCTIC




Family	GEOMETRIDAE	Species	<i>Angerona prunaria</i>	Author	Linnaeus
ORANGE MOTH <p>This moth has several different colour forms, ranging from pale yellow with minute, brown flecks, to dark brown with orange markings. Females are similar to males, but do not have feathered antennae.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is yellowish brown with a pair of conical projections on the back near the tail. It feeds on blackthorn (<i>Prunus spinosa</i>), hawthorn (<i>Crataegus</i>), and many other trees and shrubs. • DISTRIBUTION Europe, extending to temperate western Asia. 					
Time of Flight	☾	Habitat	● on shr.	Wingspan	4–5.5 cm (1½–2¼ in)



PALEARCTIC



Family	GEOMETRIDAE	Species	<i>Diston betularia</i>	Author	Linnaeus
PEPPERED MOTH <p>The common name of this moth derives from the typical form that is white, peppered with black scales. A black form has evolved in industrial regions, where tree trunks on which the moth may settle are polluted with soot.</p> <ul style="list-style-type: none"> • EARLY STAGES The twig-like caterpillar is green or brown. It feeds on oak (<i>Quercus</i>) and other broad-leaved trees and shrubs. • DISTRIBUTION Widespread in Europe, ranging across temperate Asia to Japan. 					
Time of Flight	☾	Habitat	●	Wingspan	4.5–6 cm (1½–2½ in)



PALEARCTIC



Family GEOMETRIDAE

Species *Boarmia ruboraria*

Author Denis & Schiffermüller

GREAT OAK BEAUTY


This large and attractive species is very variable and many forms occur that are darker than the one shown here.

• **EARLY STAGES** The caterpillar is brownish with greyish brown swellings on the back which make it resemble a twig. It feeds on the foliage of oak (*Quercus*).

• **DISTRIBUTION** Occurs in Europe, and extends across temperate Asia to Japan.



PALEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 6–7cm (2½–2¾ in)

Family GEOMETRIDAE

Species *Cathorata millari*

Author Hampson

MILLAR'S TIGER


Millar's tiger is one of several species in the genus, all having similar patterns of orange, grey, and black. They resemble distasteful *Hypsa* moths and may also be poisonous themselves. The underside is similar to the upperside.

• **EARLY STAGES** Nothing seems to be known about the early stages of this moth, or its foodplants.

• **DISTRIBUTION** Occurs in South Africa



AFROTROPICAL



Time of Flight ☀

Habitat 🌳, 🌾

Wingspan 5.5–6cm (2¼–2½ in)

Family GEOMETRIDAE

Species *Fennosia subsignaria*


Author Hübner

ELM SPANWORM MOTH

This pure white moth is easily distinguished from other white species by the unusually angled outer edge of the forewing. Another common name for the adult moth is the snow-white linden.

• **EARLY STAGES** The looped caterpillar feeds on the foliage of apple (*Malus domestica*), elm (*Ulmus*), and many other broad leaved trees and shrubs. It can be a pest.

• **DISTRIBUTION** Widespread in Canada and the USA.



NEARCTIC

Time of Flight ☾


Habitat 🌳

Wingspan 3–4cm (1¼–1½ in)

Family	GEOMETRIDAE	Species	<i>Epimectis hortaria</i>	Author	Fabricius
TULIP-TREE BEAUTY A large and beautiful moth, the tulip-tree beauty is very variable, with some forms strongly banded and others almost black. Females are larger than males and have thread-like antennae. These moths can be seen on the wing from spring to autumn. <ul style="list-style-type: none"> • EARLY STAGES The looper caterpillar feeds on the foliage of poplars (<i>Populus</i>), tulip-tree (<i>Liriodendron tulipifera</i>), and pawpaw (<i>Carica papaya</i>). • DISTRIBUTION Widespread from southern Canada to Florida. 					
Time of Flight	☾	Habitat	☿	Wingspan	4.5–5.5 cm (1½–2¼ in)



NEARCTIC



males have feathered antennae

strongly scalloped edge to hindwings

♂

Family	GEOMETRIDAE	Species	<i>Erannus defoliaria</i>	Author	Clerck
MOTTLED UMBER Males of this common moth are very variable, ranging from pale straw with brown bands to almost black. The wingless females also have a black form in industrial regions, where they have had to adapt to the surroundings. <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is brown with patches of yellow and reddish brown along the sides. It feeds on oak (<i>Quercus</i>), birch (<i>Betula</i>), and many other broad-leaved trees and shrubs, and can sometimes be a pest. • DISTRIBUTION Widespread in Europe, extending into regions of temperate Asia. 					
Time of Flight	☾	Habitat	☿	Wingspan (male)	3–4.5 cm (1¼–1½ in)



PALAARCTIC



triangular forewing shapes


dark speckling on hindwings

♂

Family	GEOMETRIDAE	Species	<i>Lycia hirtaria</i>	Author	Clerck
BRINDLED BEAUTY The brown and white pattern of this furry-looking moth provides effective camouflage when it rests on tree trunks. A black form has evolved in sooty industrial regions. They are on the wing in spring. <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is brown to greenish grey, speckled with black, and spotted with yellow. It feeds on the foliage of most broad-leaved trees. • DISTRIBUTION Widespread throughout Europe. 					
Time of Flight	☾	Habitat	☿	Wingspan	4–5 cm (1½–2 in)

wings of female suffused with pale yellowish brown

leading edge of forewings paler in females



♀



♂



PALAARCTIC

Family GEOMETRIDAE

Species *Mimodesa nodosa*

Author Prout

HOOP PINE MOTH


This is one of a genus of about 40 species, all with bright metallic colours that are quite unlike any other Geometer moths. The sexes are alike, although females tend to drink nectar from flowers while males feed on rotting animal and vegetable material found on the ground.

• **EARLY STAGES** The caterpillar is yellowish white with brown stripes. It feeds on hoop pine (*Araucaria cunninghamii*), causing extensive damage in plantations.

• **DISTRIBUTION** Found in the highlands of Papua New Guinea.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat ☿

Wingspan 4–5 cm (1½–2 in)

Family GEOMETRIDAE

Species *Quercuphryx sambucaria*

Author Linnaeus

SWALLOW-TAILED MOTH

This striking, pale yellow moth is often mistaken for a butterfly when disturbed by day. As its name suggests, it has a small tail-like extension on the hindwings. The sexes of this moth are similar.

• **EARLY STAGES** The long and slender looper caterpillar is brown with pale stripes along the sides. It feeds on the foliage of hawthorns (*Crataegus*), privet (*Ligustrum vulgare*), ivy (*Hedera*), and many other trees and shrubs.

• **DISTRIBUTION** Widespread in Europe, extending into temperate Asia.



PALEARCTIC



Time of Flight ☾

Habitat ●

Wingspan 4.5–6 cm (1½–2½ in)

Family GEOMETRIDAE

Species *Plagalis dolabraria*

Author Linnaeus

SCORCHED WING


The unusual wing shape of this moth, coupled with the dark brown lines and patches on the wings, give it the appearance of having been scorched by fire. In fact, it is well camouflaged in the woodland localities it frequents. The sexes are alike. These moths can be seen on the wing in late spring and early summer.

• **EARLY STAGES** The twig-like, brown looper caterpillar feeds on oaks (*Quercus*), willows (*Salix*), and birches (*Betula*).

• **DISTRIBUTION** Widespread in Europe, extending across temperate regions of Asia to Japan.





PALEARCTIC







Time of Flight ☾

Habitat ●

Wingspan 3–4 cm (1¼–1½ in)

Family	GEOMETRIDAE	Species	<i>Prochoerodes transversata</i>	Author	Drury
<h2>LARGE MAPLE SPANWORM MOTH</h2> <p>This large, pale yellowish brown moth with dark brown lines can be distinguished from other species by the small, tail-like projections on the hindwings. The sexes are similar.</p> <ul style="list-style-type: none"> • EARLY STAGES The looper caterpillar feeds on maples (<i>Acer</i>), apple (<i>Malus domestica</i>), and other plants, including grasses. • DISTRIBUTION Widespread from Canada to the eastern USA. <div style="display: flex; justify-content: space-around; align-items: center;">   </div> <p style="text-align: center;">NEARCTIC</p>					
Time of Flight	☾	Habitat	☿ ● ♀	Wingspan	3–5 cm (1 1/4–2 in)

Family	GEOMETRIDAE	Species	<i>Selenia tetralunaria</i>	Author	Hübner
<h2>PURPLE THORN</h2> <p>The purple thorn belongs to a group of moths with distinctively ragged wing margins. The banding and marking are characteristic, but there is some seasonal variation with spring broods having more white markings.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is brown and twig-like. It feeds on the foliage of birches (<i>Betula</i>), alders (<i>Alnus</i>), oaks (<i>Quercus</i>), and other deciduous trees. • DISTRIBUTION Occurs in Europe, extending across temperate Asia to Japan. <div style="display: flex; justify-content: space-around; align-items: center;">   </div> <p style="text-align: center;">PALEARCTIC</p>					
Time of Flight	☾	Habitat	●	Wingspan	4–5 cm (1 1/2–2 in)

Family	GEOMETRIDAE	Species	<i>Semiothisa bisignata</i>	Author	Walker
<h2>RED-HEADED INCILIWORM MOTH</h2> <p>The wings of this small Geometer are dirty pinkish white, powdered with brown scales, and with distinctive, chocolate-brown patches on the forewings. The head is a vivid, reddish brown. The sexes are alike. These moths can be seen on the wing from late spring to late summer.</p> <ul style="list-style-type: none"> • EARLY STAGES The green looper caterpillar feeds on eastern white pine (<i>Pinus strobus</i>) and other <i>Pinus</i> species. • DISTRIBUTION Widespread in Canada and the northern USA. <div style="display: flex; justify-content: space-around; align-items: center;">   </div> <p style="text-align: center;">NEARCTIC</p>					
Time of Flight	☾	Habitat	●	Wingspan	2–3 cm (3/4–1 1/4 in)

Family GEOMETRIDAE

Species *Thalaina clara*

Author Walker

CLARA SATIN MOTH


This is one of a group of about ten species, mostly with satin-white wings, occurring in Australia. It has a characteristic pattern of bright orange-brown, angled lines on the forewings.

• **EARLY STAGES** The caterpillar is green with a pattern of fine, yellowish white lines. It feeds on wattle (*Acacia decurrens*).

• **DISTRIBUTION** Found in eastern and south-eastern Australia, and northern Tasmania.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌳

Wingspan 4–5 cm (1½–1¾ in)

Family GEOMETRIDAE

Species *Henoplectya croceiparata*

Author Knab

ORANGE SWALLOW-TAILED MOTH


The wings are orange-yellow, except for the forewings' leading edges, which are spotted with greyish brown. The sexes are similar.

• **EARLY STAGES** The caterpillar is reddish brown with paler lines and a pale brown head.

• **DISTRIBUTION** Occurs from India and Sri Lanka to China, Japan, Malaysia, and Java.

INDO-AUSTRALIAN
PALAEOARCTIC

short hindwing tails with dark spot at base



Time of Flight ☾

Habitat 🌳

Wingspan 4–5 cm (1½–2 in)

Family GEOMETRIDAE

Species *Xanthostichus neoziscon*

Author Prout

WHITE-HEADED THORN

Males are pale yellow to orange-brown and are finely speckled with darker brown. Females are similar except that the tips of the forewings are more strongly hooked and the wings are more heavily speckled with reddish brown or grey.

• **EARLY STAGES** The caterpillar is apparently undescribed, but is known to feed on pine (*Pinus*) and cypress (*Cupressus*).

• **DISTRIBUTION** From Angola, Zambia, and Malawi, to Mozambique and the Transvaal.



AFROTROPICAL

forewings are hooked at the tips

distinctive white head gives rise to its common name



Time of Flight ☾

Habitat 🌳

Wingspan 3–4.5 cm (1¼–¾ in)

LASIOCAMPIDAE

T HIS IS A FAMILY of about 1,000 species of medium- to large-sized moths occurring around the world. They are generally rather dull in colour, mostly banded with various shades of brown. Lasiocampidae have two unusual characteristics: they lack the typical wing-coupling device of most moths, and the tongue is reduced and non-functional. Caterpillars of this

group are particularly hairy; some have long haired lobes or lappets along their sides, giving rise to their common name of lappet moth.

Pupae are formed in robust cocoons. The egg-like shape of these cocoons provides the origin of the name "eggar", which is applied to many moths in this family

Family LASIOCAMPIDAE

Species *Geoparcha gaeafata*

Author Linnaeus

LAPPET MOTTH


The reddish brown wings of this robust moth have a purplish brown sheen. The sexes are similar. When a lappet moth rests, the wings are folded in a curious way over the body, to resemble a bunch of dead leaves.

• **EARLY STAGES** The grey caterpillar has fleshy lappets, covered with long, brown hairs, on its body. It feeds on blackthorn (*Prunus spinosa*), hawthorn (*Crataegus*), and other plants.

• **DISTRIBUTION** Occurs in Europe, across temperate Asia to China and Japan.



PALEARCTIC



distinctive, scalloped
• wing margins

• hindwings smaller
and more rounded
than forewings

Time of Flight ☾

Habitat 🌳

Wingspan 4-7 cm (1½-3in)

Family LASIOCAMPIDAE

Species *Dendrolimus pini*

Author Linnaeus

PINE-TREE LAPPET


This is a very variable moth, ranging in colour from greyish white to almost any shade of grey or brown. The forewings are distinctively banded.

• **EARLY STAGES** The hairy caterpillar is brown or greyish brown with bands of white, scale like hairs along the back. It feeds on pine (*Pinus*), spruce (*Picea*), fir (*Abies*), and various other conifers.

• **DISTRIBUTION** Europe, excluding the British Isles, to North Africa and central Asia.



PALEARCTIC



white spot present on
forewing of both sexes

short,
furry body

Time of Flight ☾

Habitat 🌳

Wingspan 5-8 cm (2-3¼in)

Family LASIOCAMPIDAE

Species *Eucraera gemmata*

Author Distant

BUDDED LAPPET


This robust species of moth is a pale yellowish brown to olive-brown with three white bands on the fore- and hindwings.

• **EARLY STAGES** The caterpillar is brown, patterned with yellow and red lines and dots, and covered with long, dark brown hairs. It feeds on the foliage of *Launaea*, *Brachystegia*, and *Julbernardia*.

• **DISTRIBUTION** Occurs from Angola, westwards as far as Mozambique



AFROTROPICAL



Time of Flight ☾

Habitat 🌳 🌿 🌾

Wingspan 3–5cm (1¼–2in)

Family LASIOCAMPIDAE

Species *Duglesia enattalanae*

Author Fabricius

WATTLE SNOUT MOTH

The colour of this moth varies from yellow to reddish brown with a distinctive pattern of dark lines and spots. Females are larger than males and have more elongate wings. Males have strongly feathered antennae.

• **EARLY STAGES** The hairy caterpillar of this species is greenish grey in colour. It feeds on acacia and *Exocarpos*.

• **DISTRIBUTION** This species occurs in eastern and southern Australia.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌳 🌿 🌾

Wingspan 2.5–5cm (1–2in)

Family LASIOCAMPIDAE

Species *Bombyropsis indecora*

Author Walker

INDECOROUS EGGER


This is a very variable species of moth. The forewings range in colour from greenish brown to reddish brown, and have darker tips. The hindwings range from cream to brown.

• **EARLY STAGES** The caterpillar is reddish brown with tufts of hairs along the sides of the body, especially towards the head. It feeds on *Leurosema* and *Protea*.

• **DISTRIBUTION** From equatorial western Africa to Zambia, and the Transvaal in South Africa.




AFROTROPICAL




Time of Flight ☾

Habitat 🌳 🌿 🌾

Wingspan 2.5–6cm (1–2½in)

Family	LASIOCLAMPIDAE	Species	<i>Geometra postica</i>	Author	Walker
DARK CHOPPER <p>Moths of this group are called choppers because of the razor-edged appearance to the male hindwing. Females are much larger than males and have a different wing shape.</p> <p>• EARLY STAGES The hairy caterpillar is black with orange, yellow, or white tufts along the sides of the body. The body hairs are irritant. The caterpillar feeds on the foliage of acacia, <i>Brachystegia</i>, and <i>Elephantorrhiza</i>, and various other plants.</p> <p>• DISTRIBUTION Ranges from Zimbabwe to Mozambique, the Transvaal in South Africa, Botswana, and Namibia.</p>					
 <p>diffuse, transverse, greyish brown bands on forewings</p> <p>AFROTROPICAL</p> <p>cream-coloured base to female hindwing</p> <p>abdomen clothed with pale, hair-like scales</p> <p>♀</p>					
Time of Flight	☾	Habitat	arb. shr.	Wingspan	4–9cm (1½–3½in)

Family	LASIOCLAMPIDAE	Species	<i>Grammodes nigrolineata</i>	Author	A. J. Villius
BLACK-LINED EGGAR <p>This distinctive moth has cream-coloured forewings with four orange-red streaks and double, blackish brown lines along the veins. Males have pale cream hindwings while the larger females have greyish brown hindwings with cream-coloured fringes.</p> <p>• EARLY STAGES The hairy caterpillar is pale yellowish brown with brown and orange speckling and oblique, white streaks. It feeds on the foliage of <i>Cassia</i> and <i>Albizia</i>.</p> <p>• DISTRIBUTION Range extends from Tanzania, Zambia, Zimbabwe, and Malawi to Transvaal.</p>					
 <p>female antennae are short</p> <p>♂</p> <p>deep cream coloured wing fringes on female moth</p> <p>red forewing streaks present in both sexes</p> <p>♀</p> <p>AFROTROPICAL</p>					
Time of Flight	☾	Habitat	arb. shr.	Wingspan	4–6cm (1½–2½in)

Family LASILOCAMPIDAE

Species *Lasiacampa quercus*


Author Linnaeus

OAK EGGER

Males are much smaller than females, and their wing bases are dark chocolate-brown in contrast to the paler brown margins. The female's wings are more uniform in colour with a pale, central band. Oak eggars are on the wing in spring and summer, the males flying by day.

• **EARLY STAGES** The hairy caterpillar is dark brown with black rings. It feeds on bramble (*Rubus*), oak (*Quercus*), heather (*Calluna*), and many other plants.

• **DISTRIBUTION** Range extends from Europe to North Africa.



dark-ringed, white spot on forewing, characteristic of both sexes

pale hindwing margin on male



PALAEARCTIC

female is paler than male although dark forms do occur

Time of Flight ☀️ ♀ ☾ ♂

Habitat 🌳 🌱 🌾

Wingspan 5-7.5cm (2-3in)

Family LASILOCAMPIDAE

Species *Malacosoma americanum*

Author Fabricius

EASTERN TENT CATERPILLAR MOTH


The wings of this moth vary from light to dark chocolate brown, and are lightly dusted with white scales. The forewing has two oblique, white or yellowish white lobes, while the hindwing is a uniform chocolate-brown.

• **EARLY STAGES** The hairy caterpillar is greyish black with blue and reddish brown markings.

• **DISTRIBUTION** Widespread in the USA and southern Canada.



NEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 4-5cm (1½-2in)

Family Lasiocampidae	Species <i>Trabala viridana</i>	Author Joicey & Talbot
----------------------	---------------------------------	------------------------

MOSS-GREEN LAPPET

This beautiful moth belongs to a large complex of similar species, many occurring in South-east Asia. The female is much larger than the male and has strongly triangular forewings with large, pale brown patches towards the base. In museum specimens the beautiful, green colour of these moths will often fade quite badly.


• **EARLY STAGES** Little is known of the life-cycle but caterpillars of related species are hairy and have two forward-pointing tufts of bristles situated just behind head. They are known to feed on *Barringtonia*, *Eugenia*, *Rubus*, and *Shorea robusta*.

• **DISTRIBUTION** Range extends from Malaysia to Sumatra, Java, and Borneo.



INDO-AUSTRALIAN

distinctively
scalloped
hindwings



Time of Flight ☾	Habitat 🌿	Wingspan 4-6cm (1½-2½in)
------------------	-----------	--------------------------

Family Lasiocampidae	Species <i>Pinnia ferrea</i>	Author Walker
----------------------	------------------------------	---------------

GUM SNOUT MOTH

The forewings of this robust moth are brownish grey with darker grey lines and spots. The hindwings are brownish yellow without markings. The sexes are similar but females are larger than males. Gum snout moths are on the wing in summer.


• EARLY STAGES

The hairy caterpillar is grey and has a single knob-like projection on the back near to the tail. If threatened, it arches its body to display two black patches behind the head. It feeds at night on the foliage of eucalyptus, resting by day on the bark where it is very well camouflaged.

• **DISTRIBUTION** Occurs in southern parts of Australia, including Tasmania.



INDO-AUSTRALIAN



Time of Flight ☾	Habitat 🌿	Wingspan 4.5-7.5cm (1½-3in)
------------------	-----------	-----------------------------

Family Lasiocampidae

Species *Parra octata*

Author Walker


EUCALYPTUS LAPPET

This furry-looking moth is grayish brown with chocolate brown and white markings on the forewing. The fringes are chequered with dark brown and white. Males have a tuft on the tail.


• **EARLY STAGES** The hairy caterpillar feeds on the foliage of eucalyptus, as well as *Leptospermum flavescens*.

• **DISTRIBUTION**

South Queensland to Victoria and South Australia.



AUSTRALIAN



Time of Flight ☾

Habitat 🌳

Wingspan 2-4 cm (1-1½ in.)

Family Lasiocampidae

Species *Tolype celleda*

Author Stoll

LARGE TOLYPE

This beautiful, grey and white moth is very distinctively patterned, and the body is particularly hairy. Males are smaller than females and have strongly feathered antennae. These moths are on the wing in autumn.


• **EARLY STAGES** The caterpillar feeds on the foliage of birch (*Betula*), oak (*Quercus*), and other trees.

• **DISTRIBUTION**

Widespread from southern Canada to the USA.



NEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 3-5 cm (1½-2 in.)

Family Lasiocampidae

Species *Pachypasa bilinea*

Author Walker

TWIN-LINE LAPPET

The distinctive "twin-line" pattern occurs on the forewing of the female. The much smaller males have an additional irregular, marginal line on the forewing. The hindwings lack any markings or patterning at all.


• **EARLY STAGES** The caterpillar feeds on the foliage of *Annona* and *Bauhinia* species.

• **DISTRIBUTION**

Range extends from equatorial East and West Africa south to Zambia, Malawi, and Zimbabwe.



AFROTROPICAL



Time of Flight ☾

Habitat 🌳

Wingspan 5-10 cm (2-4 in.)

EUPTEROTIDAE

A SMALL FAMILY of just over 300 species of medium- to large-sized moths, the Eupterotidae are related to the emperor moths (Saturniidae). They are found in the tropical parts of Africa and Indo-Australia. They are mostly fairly dull-coloured with shades of brown and grey predominating. Because of their hairy appearance, they are often

known as “monkeys”. The caterpillars are covered in long hairs, which are often highly irritant and cause rashes.

Many of the caterpillars belonging to this family are gregarious and live in communal webs. Some species are known to be pests of certain trees, including the eucalyptus, and cause serious damage to them.

Family	EUPTEROTIDAE	Species	<i>Tagora pallida</i>	Author	W. A. Ker
--------	--------------	---------	-----------------------	--------	-----------


PALLID MONKEY MOTH

This large, brownish white moth is delicately patterned and lined with darker brown. Females are larger than males and have darker markings and a translucent, white spot in the middle of the forewing.

- **EARLY STAGES** The caterpillar is covered with long, dark, woolly hair which conceals poisonous stinging bristles. It feeds on a wide range of different plants.
- **DISTRIBUTION** Widespread from India to Malaysia, Sumatra, and Borneo.



INDO-AUSTRALIAN



Time of Flight	☾	Habitat	🌳 🌿 🍄	Wingspan	10.8–11cm (4¼–4½in)
----------------	---	---------	-------	----------	---------------------

Family EUPTERIDAE

Species *Ionomeris westwoodi*

Author Aurivillius


INQUISITIVE MONKEY

This large and handsome moth has a distinctly furry appearance. It varies in colour from pale fawn to brownish yellow with a pattern of dark brown lines on both the fore- and hindwing. The hindwing has a black spot at the base.

- **EARLY STAGES** The large caterpillar is densely covered with long, back-swept, black and white hairs which have irritant properties. It feeds on *Bauhinia*.
- **DISTRIBUTION** Range extends from Zimbabwe to Zambia and Zaire.



AFROTROPICAL



Time of flight ☾

Habitat 🌳 🌿

Wingspan 7.5–10cm (3–4in)

Family EUPTERIDAE

Species *Panacea lewiniae*

Author Lewin

LEWIN'S BAG-SHELTER MOTH


Males of this species have dark, banded, reddish brown forewings that are hooked towards the tips. Females have reddish to purplish brown wings.

- **EARLY STAGES** The hairy caterpillar feeds at night on eucalyptus, *Lophostemon*, *Agaphora*, and *Syncarpia*. It lives in a silken bag spun among twigs of the tree on which it feeds.

- **DISTRIBUTION** Range in Australia extends from southern Queensland to southern NSW.



INDO-AUSTRALIAN



Time of flight ☾

Habitat 🌳 🌿

Wingspan 2.5–4cm (1–1½in)

ANTHELIDAE

THIS SMALL FAMILY of less than 100 species of moth is confined to Australia and Papua New Guinea, and is closely related to the families Eupterotidae and Lasiocampidae. Many of the species are distinctively patterned with lines and bands of

brown, yellow, and red. The greatly reduced tongues of these moths means that they are unable to feed in the adult stage. The caterpillars of most species are covered with tufts of hair, which are sometimes irritant. Many feed on eucalyptus or acacia species

Family	ANTHELIDAE	Species	<i>Chelepteryx collessi</i>	Author	Gray
--------	------------	---------	-----------------------------	--------	------

GIANT ANTHELID

The large, bat like female of this species can attain a wingspan of 16cm (6¼in). The blackish brown forewings of both sexes are banden and heavily dusted with white and brownish yellow scales. The dark hindwings have a straight inner line of white and a scalloped outer line of orange-yellow. If alarmed, the male rears up to reveal its white underside and dark forelegs, and resembles a large spider.

• **EARLY STAGES** The caterpillar is greyish white with black, transverse bands across the back, and tufts of stout, irritant hairs. It feeds on eucalyptus species.

• **DISTRIBUTION** Range extends from southern Queensland to NSW and Victoria in Australia.




INDO-AUSTRALIAN

stout, black stripes along body



CATERPILLAR OF CHELEPTERYX COLLESSI



scalloped margin line on hindwing

unusual pointed tip to hindwing

Time of Flight	Habitat	Wingspan	12-16cm (4¼-6¼in)
----------------	---------	----------	-------------------

Family ANTHELIDAE

Species *Anthela ocellata*

Author Walker

EYESPOT ANTHELID


This brownish white moth has distinctive, dark brown forewing bands and black eyespots which are more strongly developed in females. The pale hindwings have a marginal band of dark spots and a large, inner, black spot. Females are larger than males and have thread-like antennae. Eyespot anthelids are on the wing in the summer months. They are rather inactive and readily feign death if threatened. Moths are on the wing throughout the summer months, and there are thought to be two generations a year.

• **EARLY STAGES** The caterpillar is undescribed, but is known to feed on various native and introduced grasses. When fully grown it forms its pupa within a double-walled, grey cocoon incorporating caterpillar hairs.


• **DISTRIBUTION** Widely distributed throughout eastern and southern Australia, including Tasmania.



INDO-AUSTRALIAN



two comma-shaped markings on forewing



Time of Flight ☾

Habitat 🌿

Wingspan 4.5-5cm (1½-2in)

Family ANTHELIDAE

Species *Natasa flavescens*



Author Walker

YELLOW-HEADED ANTHELID

Males of this species are brownish red in colour with pale yellow bands on both the fore- and hindwings. The larger females are greyish brown in colour with a large, white patch on the forewing, in the middle of which is a black spot. In contrast with the male, the female body is long and heavy, with a whitish band near the end.

• **EARLY STAGES** The pale-coloured, hairy caterpillar has two dark patches on the back behind the head, and a small, black hump towards the tail. It is known to feed on the foliage of acacia.

• **DISTRIBUTION** Range extends from southern Queensland to Victoria and Tasmania in Australia.



INDO-AUSTRALIAN

Time of Flight ☾

Habitat 🌿

Wingspan 3-4cm (1¼-1½in)

BOMBYCIDAE

ALTHOUGH THIS IS a relatively small family of some 300 species, mostly confined to the oriental region, it contains some of the most famous of all moths – the silkmoths.

Moths of this family have rounded, furry bodies. Many species have slightly hooked forewing tips. Their mouthparts are not developed so they

are unable to feed as adults. The caterpillars are usually rather swollen at the front and have a single, fleshy horn at the tail. Although they often appear smooth, the caterpillars are, in fact, covered with numerous minute hairs. Many species of this family feed on the foliage of plants of the nettle family (Urticaceae). They form their pupae within silken cocoons

Family	BOMBYCIDAE	Species	<i>Bombyx mori</i>	Author	Linnaeus
--------	------------	---------	--------------------	--------	----------


SILKMOTH

This moth has been bred in captivity for thousands of years. The wings are usually white, although some strains occasionally produce brown forms. These moths have attractive white wings, but they cannot fly.

- **EARLY STAGES** The caterpillar is usually white, variably marked with brown, and has pinkish eyespots on the back. It is reared commercially on trays of white mulberry (*Morus alba*).
- **DISTRIBUTION** No wild colonies remain, but it is believed that its origins are in China where the silkmoth industry was founded around 2,640 BC.



PALEARCTIC




Flightless	Habitat	Wingspan	4-6cm (1½-2 in)
------------	---------	----------	-----------------

Family	BOMBYCIDAE	Species	<i>Oenota luteola</i>	Author	Westwood & Guenée
--------	------------	---------	-----------------------	--------	-------------------


SMALL SILKMOTH

Males of this moth are quite variable, the forewings ranging in colour from grey to brownish grey with fine, dark lines and spots. These moths rest with the forewings held at right angles to the body and the hindwings beneath. The females are pale brown.

- **EARLY STAGES** The caterpillar is brown beneath and white above, with two pairs of red markings on the back, and a fleshy horn on the tail. It feeds on the foliage of figs (*Ficus*) and various other plants.
- **DISTRIBUTION** Ranges from Zimbabwe to Transvaal.



AFROTROPICAL



Time of Flight	Habitat	Wingspan	2-3cm (¾-1½ in)
----------------	---------	----------	-----------------

Family BOMBYCIDAE

Species *Theophila religiosae*

Author Helfer

INDIAN SILKMOTH

This moth is quite closely related to the cultivated silkmoth. It has distinctly curved forewing tips marked with dark chocolate-brown. Both fore- and hindwings have characteristic sinuous pale lines. This species is bred commercially for its silk.


• **EARLY STAGES** The caterpillar is mottled and streaked with yellow, brown, and black. It is known to feed on mulberry (*Morus*).

• **DISTRIBUTION**

Northern India to Malaysia



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌿 🌳

Wingspan 4–5cm (1½–2in)

Family BOMBYCIDAE

Species *Penutifera apicalis*

Author Walker

MUSLIN BOMBYX

Males have white, semi-translucent wings, marked with grey and black. The leading edge of the forewing is usually streaked with black and there is a strong black spot above the centre of the wing. Females are coloured white.

• **EARLY STAGES** The caterpillar is brown with humps along the back and a horn at the tail. It feeds on fig (*Ficus*).

• **DISTRIBUTION** From the Himalayas to Burma, Malaysia, and the Philippines.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌿

Wingspan 2.5–5cm (1–2in)

Family BOMBYCIDAE

Species *Gnada ochracea*

Author Walker

OCHRACEOUS BOMBYX


This species is among the most brightly coloured and attractive in a family of rather dull-coloured moths. The ground colour has various shades of reddish brown, and the forewings have a central area shaded with grey. The larger females have golden-yellow to brownish yellow forewings, and lighter hindwings.

• **EARLY STAGES** Little is known of the early stages.

• **DISTRIBUTION** From northern India to Malaysia, Sumatra, and the Philippines.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌿

Wingspan 4–6cm (1½–2½in)

BRAHMAEIDAE

THIS is a very small family of only 20 or so described species of moth, confined to Africa, Asia, and Europe. These are medium- to large-sized, and are rather like emperor moths (Saturniidae, p.218) in appearance, but have such a distinctive pattern of their own that they are always easy to recognize. The Brahmaeid moths have well-developed

cyclospots, earning for some species the common name of owl moth, although this is a term generally reserved for the family Noctuidae (see p.252). Unlike moths of many related families, adults of this group have well-developed tongues, so they can feed. The caterpillars have long projections on the body in the early stages but these are lost in the final stage.

Family Brahmaeidae	Species <i>Brahmaea mallicolia</i>	Author Gray
--------------------	------------------------------------	-------------

OWL MOTH

One of the largest and most handsome species in the Brahmaeidae family, the owl moth has very well-developed eyespots at the base of the forewings and a characteristic pattern of blackish brown lines. The robust body is coloured blackish brown with a distinctive pattern of orange-brown stripes. The males of this species are smaller than females. Although owl moths are active in the evening, they tend to remain resting on tree trunks or on the ground with wings outspread by day. If this moth is disturbed, it rocks back and forth rather than flying off.

• **EARLY STAGES** In captivity the caterpillar will eat privet (*Ligustrum*), lilac (*Syringa*) and elder (*Sambucus*)

• **DISTRIBUTION** Occurs from northern India to Nepal, Burma, China, Taiwan, and Japan.



PALEARCTIC
INDO-AUSTRALIAN

characteristic, marginal pattern of black and orange lines

large eyespot at base of forewing

pale brown hindwing margins

small, triangular white markings on hindwing margin



Time of Flight	Habitat	Wingspan 9-16cm (3½-6¼in)
----------------	---------	---------------------------

Family **Brahmaeidae**

Species *Acanthobrahmaea europaea*

Author Hartig

HARTIG'S BRAHMAEA


This distinctive European moth was discovered less than 30 years ago.

• **EARLY STAGES** The caterpillar is shiny black with white lines and spots on the back and sides, except for the front segments which are patterned with yellow. It feeds on the foliage of ash (*Fraxinus excelsior*).

• **DISTRIBUTION** In woodlands, on the shores of a volcanic lake in Lucania, Italy. It is now protected by law.



PALAEARCTIC



• characteristic dark spot at the wing tip

• wing veins visible through the translucent scales

♂

Time of Flight ☾

Habitat 🌿

Wingspan 5–7cm (2–2 1/2 in)

Family **Brahmaeidae**

Species *Dactylocerus swazii*

Author Butler

BUTLER'S BRAHMIN

This particular moth is distinguishable from other Brahmaeidae moths by its more elongate, curved forewings. The forewing eyespot is poorly developed in this species, being represented by a tear-shaped, dark brown spot. The marginal band along the fore and hindwings is lined with black and orange-brown.


• **EARLY STAGES** Surprisingly, very little seems to be known about the biology of this large and attractive African moth. The caterpillar is said to have paired, conical, hairy spines on each body segment, and it is believed to feed on the foliage of plants of the family Oleaceae.

• **DISTRIBUTION** Occurs in tropical forests of Africa.



AFROTROPICAL

distinctively curved forewing edge •



characteristically short antennae

brown, crescent-shaped markings along wing margins

pale brown line runs down fore and hindwings

♂

Time of Flight ☾

Habitat 🌿

Wingspan 12–16cm (4 3/4–6 1/2 in)

SATURNIIDAE

THIS VAST, worldwide family of over 1,000 species includes many of the world's largest and most spectacular moths. Because of their size and handsome colours, Saturniid moths are often referred to as emperor moths. Many species have well developed eyespots or transparent patches on both the fore and hindwings. A number of species have

long tails on the hindwings. Male and female wing patterns can often be totally different. In adult Saturniid moths the tongue is reduced, or absent so that they are unable to feed.

When fully grown, the caterpillars spin large cocoons to protect their pupae. These cocoons are sometimes used in the manufacture of coarse silks.

Family SATURNIIDAE	Species <i>Citheronia regalis</i>	Author Fabricius
--------------------	-----------------------------------	------------------

REGAL MOTH


The forewings of this moth are grey with deep orange veins and pale yellow, oval spots. The hindwings are orange-brown. The sexes are similar, although females are larger than males. Another common name for the adult moth is the royal walnut moth.

• **EARLY STAGES** The striking caterpillar is green with a group of large, branched horns behind the head. It feeds on a wide range of trees, including walnut (*Juglans*) and hickory (*Carya*), and is known as the hickory horned devil.

• **DISTRIBUTION** Range extends throughout south-eastern U.S.A.



NEARCTIC



Time of Flight	Habitat	Wingspan 9.5-16cm (3 7/8-6 1/4 in)
----------------	---------	------------------------------------

Family SATURNIIDAE

Species *Eacles imperialis*

Author Drury

THE IMPERIAL MOTH

This moth is easily distinguished by its large size and yellow wings, which are variably spotted, banded, and speckled with pinkish brown.

• **EARLY STAGES** The hairy caterpillar is green or brown with short, fleshy, yellow or reddish brown filaments on the back. It feeds on the foliage of a wide variety of trees.


• **DISTRIBUTION** Found in the USA and into southern Canada, with several subspecies.

wavy, brownish band dissects yellow hindwing



NEARCTIC

small, brown eyespots



Time of Flight



Habitat



Wingspan ♂ 7.5cm (3.4 in)

Family SATURNIIDAE

Species *Callisanura promethea*

Author Drury

PROMETHEA MOTHS

Males of this species are mainly blackish brown except for the pale borders, while females are coloured bright reddish brown to dark brown, with pale lines and spots in the middle of the wings.

• **EARLY STAGES**


The caterpillar is green with four red, peg-like protuberances on the back near the head, and a single yellow peg near the tail. It feeds on a wide range of trees and shrubs, including spicebush (*Benzoim*) and various orchard trees.

• **DISTRIBUTION** Range extends from southern Canada to the south-eastern USA.

white zigzag marking



NEARCTIC



marginal pattern present in both sexes

Time of Flight



Habitat




Wingspan ♂ 7.5-9.5cm (3-3 1/2 in)

IO MOTH

Males of this species have yellow forewings, while those of the females are reddish to purplish brown. The females are larger than the males. The markings are variable in both sexes, and there are many named races.

• **EARLY STAGES** The caterpillar is pale green, with branched, stinging spines along the back, and red and white lines along the sides. It is known to feed on a wide range of plant species, which include birch (*Betula*), maize (*Zea mays*), and clover (*Trifolium*).

• **DISTRIBUTION** Range extends from southern Canada, through to the USA and south to Mexico.



CATERPILLAR OF
AUTOMERIS IO

striking eyespots on hindwings give rise to the alternative common name, the bulls' eye moth

♂

strongly feathered antennae on male

marginal bands on hindwings occur in both sexes



NEARCTIC

♀

Time of Flight



Habitat



Wingspan 5-8.25cm (2-3 1/4 in)

Family SATURNIIDAE

Species *Attacus atlas*


Author Linnaeus

ATLAS MOTH

This is the world's largest moth in overall size, although the owl moth (*Thysania agrippina*, see p.265) has a greater wingspan. Distinctively shaped, its wings are richly patterned in various shades of brown. The sexes are similar.

• **EARLY STAGES** The caterpillar is pale yellowish green with long, fleshy spines, which are heavily powdered with a white, waxy substance. It can grow up to 10cm (4in) long. It feeds on a wide range of plants, and in captivity will eat willow (*Salix*), poplar (*Populus*), and privet (*Ligustrum*).

• **DISTRIBUTION** Occurs from India and Sri Lanka to China, Malaysia, and Indonesia



CATERPILLAR OF
ATTACUS ATLAS

red flush on
curved tip of
forewings

triangular,
translucent
patches on
wings

curved
wing tips

brick red line
continues from
fore- to hindwings

♂
pale-edged
brown spots along
wing margins



INDO-AU STRALIAN

Time of Flight ☞

Habitat 🌿

Wingspan 15.9–30cm (6¼–12in)

Family SATURNIIDAE

Species *Actias luna*

Author Linnaeus

AMERICAN MOON MOTH

This beautiful and distinctive species with long hindwing tails varies in colour from yellowish green to pale bluish green, depending on location and season. The sexes are similar, but males have more strongly feathered antennae.

• **EARLY STAGES** The plump, green caterpillar has dark, pinkish red, raised spots. It feeds on the foliage of many broad leaved trees, including birch (*Betula*) and alder (*Alnus*).


• **DISTRIBUTION**

Widespread from the USA south to Mexico. This species occurs, but is scarce in southern Canada.

red border to
fore- and
hindwings



NEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 7.5–10.8 cm (3–4 1/4 in)

Family SATURNIIDAE

Species *Agria tau*

Author Linnaeus

TAU EMPEROR

Males of this very attractive, tan-coloured species are smaller and darker than females. They fly in the morning, while females are active at night. They rest with their wings folded back, in the manner of butterflies.

• **EARLY STAGES**

The hump-backed caterpillar has reddish yellow spines. It feeds on broad leaved trees.

• **DISTRIBUTION**

Occurs in Europe, across temperate Asia to Japan.



PALAEARCTIC



Time of Flight ☀ ♂ ☾ ♀

Habitat 🌳

Wingspan 5.5–9 cm (2 1/4–3 1/2 in)

Family SAT. RN. DAY

Species *Actias selene*


Author Hübner

INDIAN MOON MOTH

This great favourite of moth breeders is coloured a beautiful, pale bluish green, while its long hindwing tails are suffused with yellow and pink. The sexes are similar, but males have more strongly feathered antennae. There are numerous described races.

• **EARLY STAGES** The plump caterpillar is bright yellowish green with dark yellow or orange, raised warts. It feeds on a wide range of broad-leaved trees and shrubs.

• **DISTRIBUTION** Occurs from India and Sri Lanka, to China, Malaysia, and Indonesia.



INDO-AUSTRALIAN

purplish brown
leading edge to
forewings

strongly feathered
antennae

eyespots are
characteristic
of moon moths

furry,
white body

yellowish edge
to hindwing
margin continues
on to tails

pink, crescent-
shaped marking
on hindwing tails

Time of Flight ☾

Habitat 🌳 🍄

Wingspan 8–12cm (3¼–4½in)

Family SATURNIIDA

Species *Argema mimosae*

Author Boisduval


AFRICAN MOON MOTH

This moth is very similar to the Indian moon moth (*Actias selene*, see p.223), although it belongs to a different genus. Its beautiful colour tends to fade in museum specimens. Females can be recognized by their more curved tails.

• **EARLY STAGS** The caterpillar is green with green or yellow warts on the back, which bear short, black and yellow bristles. It feeds on the leaves of maroda plum (*Sclerocarya caffra*), but in captivity will eat walnut (*Juglans*)

• **DISTRIBUTION** Ranges from Kenya and Zaire to subtropical South Africa.

CATERPILLAR OF
ARGEMA MIMOSAE



distinctive fleshy
projections
along back

brown band
along top of
forewings

bi coloured
eyespots on
hindwings

juicy body
of moth

brownish
margin to
hindwing
border

reddish brown
tail markings



AFROTROPICAL

Time of Flight ☾

Habitat ☿

Wingspan 12–13cm (4½–5in)

Family *SATURNIIDAE*Species *Anthraea polyphemus*

Author Cramer

POLYPHEMUS MOTH

The ground colour of this moth's wings varies from yellow to reddish brown, but the distinctive pattern of bands and eyespots makes it an easy species to recognize. The sexes are similar. There are one or two broods a year, with moths on the wing in summer.

• **EARLY STAGES** The plump, bright yellow-green caterpillar is humped along the back and has raised, red spots. It feeds on the foliage of many broad-leaved trees and shrubs, especially that of apple (*Malus domestica*).

• **DISTRIBUTION** Common and widespread in the USA and northern Canada.

green caterpillar is well camouflaged among foliage

hairs growing from red spots




CATERPILLAR OF
ANTHRAEA POLYPHEMUS

red-margined line near base of forewings

feathered antennae characteristic of males

two dark patches at forewing tip



NEARCTIC

Time of Flight

Habitat

Wingspan 10–13cm (4–5in)

Family SATURNIIDAE

Species *Enpackardia calleta*



Author Westwood

CALLETA SILKMOTH

The blackish brown wings of this moth are banded with white, and each wing has a white V-shaped mark at its centre. Females are larger than males, and their wings are more rounded.

• **EARLY STAGES** The caterpillar is green with blue and black, spiny warts on red bases. It feeds on *Leucophyllum*, *Fouquieria*, *Prosopis*, and acacia, and in captivity will eat the foliage of ash (*Fraxinus*), privet (*Ligustrum*), and other trees.

• **DISTRIBUTION** Range extends from southern USA to central Mexico.




NEARCTIC

Time of flight



Habitat



Wingspan 8.2–11 cm (3¼–4½ in)

Family SATURNIDAE

Species *Hyalophora cecropia*

Author Linnaeus

ROBIN MOTH

This easily recognized species gained its name from its red body, distinctively banded with white. The dark brown wings are banded with white and pinkish red. The sexes are similar, but males have smaller bodies. Another common name is the cecropia moth.

• **EARLY STAGES** The caterpillar is green with bright yellow, club-shaped protuberances along the back and blue protuberances below. It feeds on a wide range of broad-leaved trees and shrubs.

• **DISTRIBUTION** Widely distributed in forests, arable land, and gardens, from southern Canada through the USA to Mexico.

silvery patch to
forewing tip


dark eyespots
near wing-tips

small, reddish
marking on
wing-tip

white collar
behind head is
present in both
sexes

pale, crescent-
shaped spots in
center of hindwings

reddish brown
and pale brown
striped body



NEARCTIC

Time of Flight ☾ ☉

Habitat 🌳 🍄

Wingspan 11–13cm (4¼–6in)

Family SATURNIIDAE

Species *Coscinocera hercules*

Author Miskin

HERCULES MOTH


The common name of this moth refers to its size. Males have distinctive, long tails, while the paler females have broad hindwings with a double lobe in place of a tail.

• **EARLY STAGES** The caterpillar is pale bluish green with yellow spikes on the back, and can grow up to 17cm (6½in) long. It feeds on the foliage of bleeding heart tree (*Hematanthus populifera*), *Dysoxylum*, and *Panax*.

• **DISTRIBUTION** Range extends from Papua New Guinea to northern Australia.



INDO-AUSTRALIAN



Time of flight ◀

Habitat ☞

Wingspan 16.5-25cm (6½-10in)

Family SATURNIIDAE

Species *Gruellia satellae*

Author Graells

SPANISH MOON MOTH

The Spanish moon moth is considered by many to be the most beautiful of all European moths. The veins on the wings are strongly marked with reddish brown, and outlined with dark brown. Each wing bears a white-centred eyespot, half of which is yellow, and half of which is purplish blue with a reddish brown bar. Males have long, curved hindwing tails; those of females are shorter and broader.

• **EARLY STAGES** The caterpillar is yellowish green, finely spotted with white, and banded with chestnut-brown and white. It is covered with long, fine, brown hairs. It feeds on pines, particularly *Pinus sylvestris* and *Pinus laricio*.

• **DISTRIBUTION** Forests in the mountainous regions of central Spain and the Pyrenees.

male forewings are more sharply angular in shape than female forewings

♂

pale brown leading edge to forewings

underwing margins have distinct yellowish green suffusion

hindwing tails reduced to pointed lobes in female moth

yellow and brown banded female body is larger than that of male



PALAEARCTIC

Time of Flight

Habitat

Wingspan 6–10cm (2½–4in)

Family SATURNIIDAE

Species *Loepa katinka*

Author Westwood

GOLDEN EMPEROR

This attractive yellow moth has a streak of dark brown along the leading edge of the forewings. Each wing has a reddish brown ringed eyespot at its centre. The wings are also patterned with fine wavy lines of reddish brown. The sexes are alike.

• **EARLY STAGES** Caterpillar is dark brown marbled with light brown and black, and has metallic blue warts. Along the sides are triangular yellow patches.

The caterpillar feeds on vines (*Vitis* and *Parthenocissus*).

• **DISTRIBUTION**

Widespread from North India to China.

CATERPILLAR OF
LOEPA KATINKA



warts
each bear
bristly
hairs

slender, elongated
forewings of male
moth

forewings of male
more angular than
those of female

black eyespot
marking at
forewing tips

pale brown leading
edge to forewing

white,
crescent-shaped
marking at
forewing tips

fine, white, wavy
line along wing
margins



INDO-AUSTRALIAN

Time of Flight



Habitat



Wingspan 9–10cm (3½–4in)

Family SATURNIIDAE

Species *Hunania alamine*

Author Stoll


COMMON EMPEROR

The common emperor varies in colour from reddish brown to dark purplish brown, with striking, pale bands on the fore- and hindwings.

- **EARLY STAGES** The dull black caterpillar has long, black spines behind the head, and yellowish white coloured protuberances along the rest of the body. It feeds on many types of plant, including *Celtis* and *Terminalia*.
- **DISTRIBUTION** Widespread throughout Africa, south of the Sahara, and also in Madagascar.



AFROTROPICAL



Time of Flight ☾

Habitat 🌳

Wingspan 10–16cm (4–1½ in)

Family SATURNIIDAE

Species *Opodiphthera eucalypti*

Author Scott


EMPEROR GUM MOTH

This is a handsome moth with black-speckled, white margins to the leading edge of the forewing. The hindwing eyespots are large and strongly ringed with black. Paler, greyish buff forms occur in both sexes of the species.

- **EARLY STAGES** The caterpillar is green with blue-tipped, orange and red warts, and yellowish white stripes along the sides. Although it is brightly patterned, it is well camouflaged among the young foliage of eucalyptus on which it usually feeds. It also eats the foliage of many trees, including pepper tree (*Schinus molle*), silver birch (*Betula pendula*), and other trees.
- **DISTRIBUTION** In Australia, from the Northern Territory to Queensland, Victoria, and New Zealand.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌳 🌿

Wingspan 8–13cm (3¼–5 in)

Family	SATURNIIDAE	Species	<i>Nudaurelia cytherea</i>	Author	Fabricius
--------	-------------	---------	----------------------------	--------	-----------

PINE EMPEROR

This moth is banded and shaded with reddish, yellowish, and purplish brown. The forewing eyespots are ringed with black and orange, and have translucent, oval centres. The hindwing eyespots are broadly ringed with black and orange, and have minute, rounded, transparent centres.

• **EARLY STAGES** The caterpillar is strikingly beautiful with its black body speckled with green, yellow, and silver. There are also striking, broad bands of brownish red across the back. This species is a particularly notorious pest of pine trees (*Pinus*), but also feeds on the foliage of cypress (*Cupressus*), and acacia, apple (*Malus domestica*), guava (*Psidium guajava*), and other wild and cultivated trees and shrubs.

• **DISTRIBUTION** Widespread and common in South Africa



AFROTROPICAL



unmistakable
speckled
patterning

CATERPILLAR OF
NUDAURELIA CYTHEREA



long, hair-like
scales at wing
bases

markings
distinctively
outlined with
purplish grey

Time of Flight	Habitat	Wingspan
		4-13cm (1½-5in)

Family SATURNIIDAE

Species *Rothschildia orizaba*


Author Westwood

ORIZABA SILKMOTH

A handsome and distinctive moth, this silkmoth belongs to a largely South American genus of moths which are characterized by the presence of large, translucent, window-like patches on both fore- and hindwings. The reddish brown wings are lined and patterned with white, black, and various shades of brown. Females have more rounded hindwings.

• **EARLY STAGES** The caterpillar is yellowish green above and bluish green below. The foodplants of this moth are apparently unknown. It has been successfully reared in captivity on the foliage of privet (*Ligustrum*).

• **DISTRIBUTION** Central and tropical South America, and can occur in southern Texas, USA.



caterpillar in
• resting position

CATERPILLAR OF
ROTHSCHILDIA ORIZABA


small, black rudiments
of an eyespot near
forewing tips

antennae of male
moth more feathered
• than female



pale-ringed
brown spots along
hindwing margin

purple-brown
wavy marking
on hindwings



NEOTROPICAL

Time of Flight ☾

Habitat 🌿

Wingspan 11–14.5cm (4½–5½in)

Family SATURNIIDAE

Species *Samia cynthia*

Author Drury


AILANTIUS SILKMOTH

The ground colour of this large moth varies from khaki brown to an olive-green or orange-brown. The broad, pale band that traverses both fore- and hindwings is characteristic, as are the narrow, crescent-shaped, translucent patches in the centre of each wing. Males have more elongate forewings than the females, and their antennae are more strongly feathered. Another common name for the adult is the en silkmoth.

• **EARLY STAGES** The fleshy, spined caterpillar is bluish green, overlaid with a white, waxy powder.

As its common name suggests, it feeds on the foliage of tree of heaven (*Ailanthus altissima*), although in captivity it eats privet (*Ligustrum*) or lilac (*Syringa*). The caterpillars are reared for the silk of their cocoons.

• **DISTRIBUTION** Originating from Asia, this species has been introduced into North America and is now established in parts of Europe.



CATERPILLAR OF
SAMIA CYNTHIA

white spots on
hairy thorax

♂

narrow,
crescent-shaped
markings
characteristic
of this species

vertical, black
line runs down
length of wings



HOL ARCTIC

Time of Flight ☾

Habitat 🌿 🌳 🌾

Wingspan 9-14cm (3½-5½in)

Family SATURNIIDAE

Species *Saturnia pyri*

Authors Denis & Schiffermüller

GREAT PEACOCK MOTH

The great peacock moth is Europe's largest native moth, and as such is easy to recognize. It has red, black, and brown ringed eyespots on all wings. The wings are brown with light and dark bands, and the leading edge of the forewing is extensively suffused with silvery white. The sexes are similar. Other common names for the adult moth are the giant emperor and the Viennese emperor.

▪ **EARLY STAGES** The caterpillar is bright yellowish green with raised, blue warts bearing tufts of black hairs. It feeds on the foliage of apple (*Malus domestica*), pear (*Pyrus communis*), and other broad-leaved trees, and it is occasionally a minor orchard pest.

• **DISTRIBUTION** Widespread in central and southern Europe, extending to north Africa and western Asia.

CATERPILLAR OF
SATURNIA PYRI


caterpillar is yellowish-green with white line along its side

small, dark marking on forewing tip

feather-like antennae

body pattern echoes wing pattern

pale, inner marginal band on both fore- and hindwings



PALEARCTIC

Time of Flight ☾

Habitat 🌳 🍏

Wingspan 10–15cm (4–6in)

SPHINGIDAE

THIS is a worldwide family of about 1,000 medium to large-sized moths. Their very distinctive, streamlined wing shapes and robust bodies set them apart from other moths, making them one of the easiest groups to recognize. Because of their structure, they are extremely powerful fliers, some even reaching speeds of up to 50km (30 miles) per hour. It is

probably owing to their speed in flight that they have earned their common name of hawk-moths.


Moths from this family usually have well-developed tongues enabling them to rake nectar from even the most deep-throated, tubular flowers. Some species are day-fliers, and may be seen hovering over flower beds in gardens.

Family	SPHINGIDAE	Species	<i>Acherontia atropos</i>	Author	Linnaeus
--------	------------	---------	---------------------------	--------	----------

DEATH'S HEAD
HAWK-MOTH


Many superstitions were at one time based around this distinctive moth, and it was generally considered to be a portent of death or grave misfortune. The moths have a very stout, strong tongue, which they use to pierce the wax cells of beehives so that they can feed on the honey inside.

- **EARLY STAGES** The caterpillar ranges from yellow to green or brown. It feeds on the foliage of potato (*Solanum*), deadly nightshade (*Atropa*) and related plants.
- **DISTRIBUTION** Mediterranean, North Africa. It migrates northwards into Europe.



common colour form
of the caterpillar

CATERPILLAR OF
ACHERONTIA ATROPOS



brightly
coloured
hindwings

striking skull-like shape
on thorax gives rise to
common name of species

black and
orange-yellow
bands on body



AFROTROPICAL

Time of Flight	Habitat	Wingspan
☾	☿ ☿ ☿	10-14cm (4-5½in)

Family SPHINGIDAE


Species *Agrius cingulata*

Author Fabricius

PINK-SPOTTED HAWK-MOTH

This streamlined moth has well camouflaged forewings, with an intricate pattern of grey and greyish brown. The hindwings are a so grey with black bands but are strongly flushed with pink towards the base. The most distinctive feature of the pink-spotted hawk-moth is a pattern of pink cross-bars which are evident on the body.

- **EARLY STAGES** The caterpillar is variable, ranging in colour from green to olive-brown or blackish brown. All forms have paler, diagonal stripes along the sides. This species is a well-known pest of sweet potato (*Ipomoea*), and is also known as the sweet potato hornworm.
- **DISTRIBUTION** Range extends from South and Central America to southern parts of the USA, including Hawaii and sometimes southern Canada.



Time of Flight ☾

Habitat 🌿 🌳 🌲

Wingspan 8–12cm (3¼–4¾in)

Family SPHINGIDAE


Species *Sphinx ligustri*

Author Linnaeus

PRIVET HAWK-MOTH

The forewings of this very distinctive species are dark brown, shaded with pale greyish brown, and finely streaked with black. The hindwings are pale, dusky pink with black bands. The body is deep pink with black bands and a central, pale brown, longitudinal stripe. The sexes are alike.

- **EARLY STAGES** The plump caterpillar is bright yellowish green with a series of striking, oblique, purple stripes along the sides, and a sharply pointed, shiny, black tail-horn. It mostly feeds on the foliage of common privet (*Ligustrum vulgare*) and lilac (*Syringa vulgaris*).
- **DISTRIBUTION** Widespread and common in Europe, extending across temperate Asia to China.



Time of Flight ☾

Habitat 🌿 🌳

Wingspan 8–11cm (3¼–4¾in)

Family SPHINGIDAE

Species *Manduca sexta*

Author Linnaeus


CAROLINA SPHINX

This is a predominantly grey moth with blackish brown and white lines and bands. The wing fringes are characteristically spotted with white, and there are usually six pairs of orange-yellow, square spots along the body of the moth.

• EARLY STAGES

The large, green caterpillar has oblique, white stripes along the sides of the body, and a red tail horn. It feeds on the foliage of tobacco (*Nicotiana*), potato (*Solanum*), and related plants. This caterpillar is sometimes known as the tobacco hornworm.

• **DISTRIBUTION** Tropical South and Central America to many parts of North America, although it is more common in the south.



Time of flight ☾

Habitat ☿

Wingspan 10.5–12cm (4¼–4¾ in)

Family SPHINGIDAE

Species *Xanthopan morgani*


Author Walker

MORGAN'S SPHINX

This large moth has yellowish brown forewings patterned with black and brown lines. The hindwings are blackish brown with large patches of dull orange-yellow at the base. The most striking feature of this species is its long tongue, which can extend to a length of more than 25cm (10in), and enables it to feed from the long, slender nectaries of orchids such as *Angraecum sesquipedale*.

• **EARLY STAGES** The caterpillar is turquoise-green, covered with white hairs, and has a curved, black and purple tail-horn. It is said to feed on custard apple (*Annona*) and *Uvaria*.

• **DISTRIBUTION** Occurs in tropical Africa.



Time of flight ☾

Habitat ☿

Wingspan 10–13.5cm (4–5¼ in)

Family SPHINGIDAE

Species *Coccyzus anticus*


Author Drury

GIANT SPHINX

As its name suggests, the giant sphinx is the largest moth of this family. The forewings are yellowish grey, mottled and streaked with black and brown. There is a broad, outer border of black. The sexes are similar in appearance, but females are much larger than males. These moths are on the wing at all times of the year.

• **EARLY STAGES** The caterpillar is green with faint, oblique stripes along the sides, a pink line down the back, and a pink and grey horn on the tail. It feeds on custard apple (*Annona*)

• **DISTRIBUTION** Range extends from tropical South and Central America, northwards to the USA, as far as southern Florida.



Time of Flight ☾

Habitat 🌿 🌳 🌴

Wingspan 13–17.5cm (5–7in)

Family SPHINGIDAE

Species *Aethya populi*


Author Linnaeus

POPLAR HAWK-MOTH

This common moth has strongly scalloped wing borders. The forewings are pale grey to purplish grey with darker bands and a darker wing border.

• **EARLY STAGES** The caterpillar is yellowish or bluish green, finely dotted with white. It feeds on poplar (*Populus*).

• **DISTRIBUTION** Widespread in Europe, extending into temperate Asia. It can often be found in urban areas.



Time of Flight ☾

Habitat 🌿 🌳

Wingspan 7–8cm (2½–3in)


Family SPHINGIDAE	Species <i>Coequesa triangularis</i>	Author Donovan
-------------------	--------------------------------------	----------------

DOUBLE-HEADED HAWK-MOTH

This spectacularly large hawk moth has distinctively shaped, brown forewings with a large and prominent, dark brown, triangular marking on the leading edge.

• **EARLY STAGES** The unusual-looking caterpillar is green but covered with small, white-tipped, yellow warts. It has a raised, white-centred, black “eye” on the hind claspers, creating the appearance of a lizard’s head. It feeds on *Banksia*, *Grevillea*, and *Macadamia*, and other plants belonging to the family Proteaceae.

• **DISTRIBUTION** Eastern Australia, particularly NSW.



Time of Flight ☾	Habitat 🌳	Wingspan 15–16 cm (6–6 1/2 in)
------------------	-----------	--------------------------------


Family SPHINGIDAE	Species <i>Mimastis</i>	Author Linnaeus
-------------------	-------------------------	-----------------

LIME HAWK-MOTH


This moth ranges from dusky pink to reddish or yellowish brown with olive-green markings on the forewing.

• **EARLY STAGES** The caterpillar is green, speckled with yellowish white dots and has yellow stripes along the sides. It feeds on the foliage of lime (*Tilia*) and other broad-leaved trees.

• **DISTRIBUTION** Commonly found across Europe through to Siberia and also in Japan.



PALAEARCTIC



Time of Flight ☾	Habitat 🌳	Wingspan 6–7 cm (2 1/2–3 in)
------------------	-----------	------------------------------

Family SPHINGIDAE

Species *Smerinthus jamaicensis*

Author Drury

TWIN-SPOTTED SPHINX

While the forewings of this hawk-moth are light and dark greyish brown, the hindwings are deep pink with striking, black ringed, blue eyespots.


• **EARLY STAGES** The caterpillar is green with white, diagonal stripes along the sides of the body and a straight, purplish pink or blue tail-horn. It feeds on the foliage of apple (*Malus domestica*).

• **DISTRIBUTION**

Canada and the USA.



NEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 5–8cm (2–3 1/4 in)

Family SPHINGIDAE

Species *Protambulyx strigilis*



Author Linnaeus

STREAKED SPHINX

The streaked sphinx belongs to a genus of Central and South American species characterized by their long, narrow forewings. It can be distinguished from similar species by a dark brown line along the outer margin of the forewings.

• **EARLY STAGES** The caterpillar is yellowish green with greenish white or yellowish green, oblique bands along the sides, and a distinct horn on the tail. It feeds on the foliage of *Anacardium spondias* and other related plants.

• **DISTRIBUTION** From Argentina to Florida, USA.

CATERPILLAR OF
PROTAMBULYX STRIGILIS


NEOTROPICAL

Time of Flight ☾

Habitat 🌳


Wingspan 9.5–12cm (3 3/4–4 1/4 in)

Family	SPHINGIDAE	Species	<i>Cephonodes kingi</i>	Author	Marlesay
KING'S BEE-HAWK <p>This bee-hawk has a distinctive, olive-green colour. On emergence from the pupa, the wings are completely covered with scales, but most of these are lost in flight, leaving clear patches with dark veins.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar varies in colour from green to greenish black and has an S-shaped horn at the tail. It feeds on the foliage of <i>Ceanothus</i>. • DISTRIBUTION From Western Australia and Queensland to NSW. 					
Time of Flight	☀	Habitat	🌳 🌿	Wingspan	4-6.5cm (1½-2½in)




INDO-AUSTRALIAN

Family	SPHINGIDAE	Species	<i>Hemaris thysbe</i>	Author	Fabricius
HUMMINGBIRD CLEARWING <p>This is one of a group of North American species with large, clear areas on both fore- and hindwings. The clear areas are surrounded by dark reddish brown borders, but the wing bases and front half of the body are olive-green.</p> <ul style="list-style-type: none"> • EARLY STAGES The plump, yellowish green caterpillar has pale stripes along the back and a yellow and green tail-horn. It feeds on hawthorn (<i>Crataegus</i>) and related species. • DISTRIBUTION Common in Canada and the USA 					
Time of Flight	☀	Habitat	🌳 🌿	Wingspan	4-6cm (1½-2½in)



NEARCTIC

Family	SPHINGIDAE	Species	<i>Cizara ardeniae</i>	Author	Lewin
CIZARA HAWK-MOTH <p>This remarkable hawk-moth is quite unlike any other species and belongs in a genus of its own. Where the cross-bar reaches the leading edge of the forewings there is a small, white, translucent spot.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is undescribed but is known to feed on <i>Coprosma</i>. • DISTRIBUTION Queensland to NSW. 					
Time of Flight	☾	Habitat	🌳 🌿	Wingspan	3-7cm (2-2½in)



INDO-AUSTRALIAN

Family SPHINGIDAE

Species *Pseudosphinx tetrio*

Author Linnaeus


GIANT GREY SPHINX

The forewings of this large, strong-flying hawk-moth are patterned with various shades of grey and greyish white.

Females are larger than males.

• **EARLY STAGES** The large, snake-like caterpillar is ringed with orange and black and has black-dotted orange back-shields behind the head and near the tail. It feeds on frangipani (*Plumeria*) and jasmine (*Jasminum*).

• **DISTRIBUTION** From Paraguay to the West Indies and the southernmost USA.



Time of Flight ☾

Habitat 🌿

Wingspan 13–16cm (5–6 1/2 in)

Family SPHINGIDAE

Species *Macroglossum stellatarum*


Author Linnaeus

HUMMINGBIRD HAWK-MOTH

This distinctive and robust, little hawk-moth has greyish brown forewings with black lines. The sexes are similar. This moth is often mistaken for a hummingbird when it is seen hovering in front of flowers to feed on their nectar through its extended tongue.

• **EARLY STAGES** The caterpillar is green or brown with a blue horn on the tail. It feeds on bedstraw (*Galium*).

• **DISTRIBUTION** Native to southern Europe and North Africa, and across Asia to Japan.



Time of Flight ☼

Habitat 🌿

Wingspan 4–5cm (1 1/2–2 in)

Family SPHINGIDAE

Species *Daphnis nerii*

Author Linnaeus


OLEANDER HAWK-MOTH

Perhaps the most spectacular of all the hawk-moths, this large species is intricately patterned with shades of green and purplish pink. The hindwings are greyish brown. The body is patterned in a similar way to the forewings so that the entire moth is extremely well camouflaged when it settles among foliage.

In the tropics this moth occurs throughout the year.

• **EARLY STAGES** The large caterpillar is olive-green with two large, blue eyespots on the body behind the head. The tail-horn is yellow, tipped with black. It feeds on oleander (*Nerium oleander*), periwinkle (*Vinca*) and grapevine (*Vitis vinifera*).

• **DISTRIBUTION** Widespread in Africa and southern Asia, migrating northwards to Europe. It has also been recorded in Hawaii.



Time of Flight ☾

Habitat 🌿

Wingspan ♂ 12cm (3¼–4½in)

Family SPHINGIDAE

Species *Ecchloron megera*

Author Linnaeus


VERDANT SPHINX

This is arguably the most distinctive of all hawk-moths. The body and forewings are a deep shade of green; the hindwings are orange-yellow with black and reddish brown markings on the outer margin.

The underside has varying amounts of green, but it is also suffused with pinkish red or reddish brown. There are two silvery patches on the underside of the body.

• **EARLY STAGES** The horned caterpillar is reddish pink with an eyespot on the body some distance behind the head; there are also two white stripes along the back. It feeds on the foliage of grapevine (*Vitis vinifera*) and Virginia creeper (*Parthenocissus*).

• **DISTRIBUTION** Widespread in Africa south of the Sahara, ranging from equatorial west Africa to Zambia and Natal.



Time of Flight ☾

Habitat 🌿

Wingspan 7–12cm (2¾–4½in)

Family SPHINGIDAE

Species *Hipotion celerio*


Author Linnaeus

SILVER-STRIPED HAWK-MOTH


The brown forewings strongly striped with silvery white give this moth its common name. The hindwings are bright pink at the base, becoming paler towards the margin.

• **EARLY STAGES** The caterpillar is very variable with a ground colour of dark brown, light brown, or green. Caterpillars feed on bedstraw (*Galium*) and Virginia creeper (*Parthenocissus*).

• **DISTRIBUTION** Africa to Australia, and southern Europe.



AFROTROPICAL
INDO-AUSTRALIAN
PALAEARCTIC



small •
line on
hindwing

forewing •
pointed at
rear margin

Time of Flight ☾

Habitat 🌿 🌳 🌾

Wingspan 7–8cm (2½–3¼in)

Family SPHINGIDAE

Species *Hyles lineata*


Author Fabricius

STRIPED HAWK-MOTH


This worldwide species has dark olive brown forewings, banded and streaked with pinkish white; the pink hindwings are margined with black. It visits flowers such as honeysuckle (*Lonicera*) and valerian (*Valeriana*).

• **EARLY STAGES** The caterpillar of this species is dark green or black, with yellow dots. It feeds on many plants, including bedstraw (*Galium*).

• **DISTRIBUTION** North and South America, Europe, Africa, Asia, and Australia.



WORLDWIDE



pinkish white
streaks along
distinctively
patterned body

• pale greyish
brown margins
to fore- and
hindwings

Time of Flight ☾ (1)

Habitat 🌿 🌳 🌾

Wingspan 7–8cm (2½–3¼in)

Family SPHINGIDAE

Species *Deilephila elpenor*


Author Linnaeus

ELEPHANT HAWK-MOTH


The forewings of this moth are olive brown, banded with dusky pink, while the hindwings are deep pink. The underside is predominantly bright pink.

• **EARLY STAGES** The large caterpillar is green or greyish brown with prominent, false eyespots on the body behind the head. It feeds on willowherb (*Epilobium*) and bedstraw (*Galium*).

• **DISTRIBUTION** Widespread in Europe, and across temperate Asia to Japan.



PALAEARCTIC



forewing tip tapers
• abruptly to a point

white •
hindwing
fringes

pink and
olive-brown
stripes on
• body

Time of Flight ☾

Habitat 🌿 🌳 🌾

Wingspan 5.5–6cm (2¼–2½in)

NOTODONTIDAE

THIS is a large family of more than 2,500 small- to medium-sized species with a worldwide distribution. The moths generally have rather long forewings and a longish body. The predominant wing colours are brown, grey, and green, but some species are more brightly coloured. One of the characteristic features of many of the members in this group is a tuft of scales projecting from the middle of

the hind edge of the forewing. When the wings are folded, these tufts project conspicuously, giving rise to the common name "prominents".

The caterpillars of this family display a great variety of forms, ranging from hairy species that live in communal nests – the "processionary" caterpillars – to smooth species with humps on their backs, or with whip-like tails.

Family NOTODONTIDAE

Species *Cerura vinula*



Author Linnaeus

PUSS MOTH

The white forewings of this distinctive species are patterned with greyish black, zigzag lines. The hindwings lack markings but are heavily suffused with grey and have dark veins. The sexes are alike. These moths are on the wing in spring and summer.

• **EARLY STAGES** The striking caterpillar is bright green with a purple, saddle-shaped marking in the middle of the back and two long tails at the rear end. When the caterpillar is disturbed, these tails are thrust forwards over the head and emit slender, whip-like, pink filaments. The caterpillar can also squirt formic acid from a gland in the throat. It feeds on willow and salix (*Salix*), and poplar (*Populus*).

• **DISTRIBUTION** Widespread in Europe, ranging to North Africa, and across temperate Asia to Japan.



PALAEARCTIC

Time of flight

Habitat

Wingspan 6–9 cm (2½–3½ in)

Family NOTODONTIDAE

Species *Chloris cresus*


Author Cramer

CROESUS PROMINENT

The family Notodontidae is richly represented in South America but very little is known about the individual species. This beautiful moth belongs to a genus of about ten described species, most of them with metallic markings on the forewing. The forewings of the Croesus prominent are patterned with a network of dark brown lines and suffused with a scattering of golden brown scales – hence the common name, which refers to the wealthy Lydian King Croesus of antiquity. The striking, silver spots are grouped in the centre of the wing and at the base.

• **EARLY STAGES** The caterpillar of this species has not been described and its foodplants are unknown.

• **DISTRIBUTION** Occurs throughout tropical South and Central America.



Time of Flight ☾

Habitat 🌿

Wingspan 4.5–5.5cm (1½–2¼in)

Family NOTODONTIDAE

Species *Danina banksiae*

Author Lewin


BANKSIA MOTH

The banksia moth is one of the most distinctive members of this family in Australia. Its grey forewings are patterned with black.

The hindwings of the female are a glossy, brownish grey, but those of the smaller male are almost white. The body is orange-yellow. Banksia moths are on the wing at most times of year but are especially common in spring.

• **EARLY STAGES** The caterpillar is a glossy, reddish brown and has white patches and a short, blunt, black horn on the tail. It feeds by day on the foliage of *Banksia marginata* and *Hakea*, and if disturbed it rears up the front part of the body in a threatening posture. The pupae are formed underground.

• **DISTRIBUTION** This species occurs throughout Australia.



Time of Flight ☾

Habitat 🌿

Wingspan 6–8cm (2¼–3¼in)

Family NOTODONTIDAE

Species *Desmocraera latex*

Author Druce

OLIVE PROMINENT


This is a very variable species of moth, with the forewings ranging in colour from brown with a green suffusion to almost grass-green. The hindwing in both sexes is a pale, shining brown.

• **EARLY STAGES** The caterpillar is brown with white streaks and dark spots along its sides. It feeds on the foliage of fig (*Ficus*) and *Mimusops*.

• **DISTRIBUTION** West Africa to Malawi, Angola and down as far as South Africa.



AFROTROPICAL



Time of Flight ☾

Habitat ☀️ 🌳 🌿

Wingspan 4-6 cm (1½-2½ in)

Family NOTODONTIDAE

Species *Nerue indentata*

Author Walker

DOUBLE-TOOTHED PROMINENT


The "double-tooth" in the common name refers to a white-edged, blackish brown line that extends across the forewings, and the thorax, and divides the brown front portion from the pale grey rear portion.

• **EARLY STAGES** The caterpillar has a series of triangular projections along its back, which resemble the edge of the elm leaf (*Ulmus*), on which it feeds.

• **DISTRIBUTION** Southern Canada and the USA.



NEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 3-4 cm (1½-1½ in)

Family NO. ODONTIDAE

Species *Notodonta decemdata*

Author Linnaeus

IRON PROMINENT


The forewings of this moth are usually richly coloured with shades of purplish and reddish brown. In northern regions, however, they tend to be darker and suffused with grey.

• **EARLY STAGES** The caterpillar varies from yellowish green to reddish brown. It feeds on the foliage of birch (*Betula*), oak (*Quercus*), and other broad-leaves.

• **DISTRIBUTION** Central and northern Europe, extending to Scandinavia.



PALEARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 4-8 cm (1½-3 in)

Family NOCTUIDAE

Species *Oenosa boisdualis*

Author Newman

BOISDUVAL'S AUTUMNAL MOTH


Recently it has been suggested that this distinctive moth belongs in a separate family of its own, the Oenosinidae. Males are smaller than females and have grey forewings speckled with black.

• **EARLY STAGES** The caterpillar is black with a brown head, and has white spots on its back. It feeds on eucalyptus.

• **DISTRIBUTION** Occurs in wooded areas of southern Australia.



INDO-AUSTRALIAN



angled forewings on female •
body strongly banded with black and orange

Time of Flight ♀

Habitat

Wingspan 4-5 cm (1.5-2 in)

Family NOCTUIDAE

Species *Schizura ipomoeae*

Author Doubleday

MORNING-GLORY PROMINENT

This species is very variable, with the greyish brown ground colour either patterned with fine, dark lines and spots, or broadly banded or streaked with black to dark brown. Females are larger than males.

• **EARLY STAGES** The green and brown caterpillar feeds on the foliage of birch (*Betula*), roses (*Rosa*), and other plants.

• **DISTRIBUTION** From the USA to southern Canada.



NEARCTIC



pale, triangular spots on forewing margin

pale-rumped, dark spot in middle of forewing

Time of Flight ♀

Habitat

Wingspan 4-5 cm (1.5-2 in)

Family NOCTUIDAE

Species *Stauropus fagi*

Author Linnaeus

LOBSTER MOTH


This large, greyish brown species has long, narrow forewings and small, rounded hindwings. Dark forms also occur in which the ground colour is dark grey.

• **EARLY STAGES** The name "lobster" derives from the caterpillar, which has a swollen, lobster-like tail. It feeds on beech (*Fagus sylvatica*).

• **DISTRIBUTION** Europe across to temperate regions of Asia and Japan.



PALEARCTIC



distinctive line of dark dots on forewing •


very pale hindwing fringes



fuzzy tip to abdomen

Time of Flight ♀

Habitat

Wingspan 5.5-7 cm (2 1/4-2 1/2 in)

Family	NOTODONTIDAE	Species	<i>Glastera albosignata</i>	Author	Fitch
<h2>SIGMOID PROMINENT</h2> <p>The pale brown forewings of this moth are patterned with light and dark lines and tipped with dark chocolate-brown. The common name derives from the white, sigma-shaped marking on the forewing.</p> <ul style="list-style-type: none"> ▪ EARLY STAGES The caterpillar is black, covered with fine, white hairs, and has four orange-yellow lines along the back. It feeds on poplar (<i>Populus</i>). ▪ DISTRIBUTION Found in southern Canada and the USA 		 <p>distinctively shaped, dark tip to forewings</p> <p>slightly concave leading edge to forewings</p> <p>♂</p> <p>pale hindwings with no patterning</p>			
Time of Flight	☾	Habitat	• vvv vvv	Wingspan	3-4cm (1 1/2-1 3/4")

Family	NOCTUIDAE	Species	<i>Datana ministra</i>	Author	Drury
<h2>YELLOW-NECKED CATERPILLAR MOTH</h2> <p>This fairly large prominent belongs to a group of similar species called hand-maid moths. It can be distinguished from other similar species by the distinctively scalloped outer margin, shaded with black, that gives it an almost scorched appearance.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is striped black and yellow. It feeds on the foliage of many broad-leaved trees, including apple (<i>Malus domestica</i>). • DISTRIBUTION Common in southern Canada and USA. 			 <p>♀</p>		
 <p>NEARCTIC</p>			<p>Time of Flight ☾</p> <p>Habitat 🌳</p> <p>Wingspan 4-5cm (1 1/2-2")</p>		

Family	NOCTUIDAE	Species	<i>Phalera lusephala</i>	Author	Linnaeus
<h1>BUFF-TIP</h1> <p>The buff-tip is a very distinctive species with its purplish grey forewings suffused with light silvery grey and lined with black and brown. The common name derives from the forewing that camouflages the moth when it rests.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar is orange-yellow with black bands. It feeds on the foliage of various broad-leaved trees and shrubs. • DISTRIBUTION Widespread in Europe, and eastwards to Siberia. 		<p>buff patch resembles end of a twig</p> <p>pale hindwings are concealed when moth is at rest</p> <p>scalloped pattern along forewing margins</p> <p>PALAEARCTIC</p>			
Time of flight	☾	Habitat	🌳	Wingspan	5.5–7cm (2¼–2¾in)

Family NOTODONTIDAE

Species *Anaphe panda*


Author Boisduva

BANDED BAGNEST


The white forewings of this striking moth are strongly patterned with dark chocolate-brown; the white hindwings lack markings. The sexes are similar.

• **EARLY STAGES** The hairy caterpillar is an off-white colour. It feeds on the foliage of *Diplorkynchus* and *Bridelia*.

• **DISTRIBUTION** Ranges from West Africa through to Kenya, Mozambique, and Natal



AFROTROPICAL



Time of Flight ☾

Habitat ☿

Wingspan 4–5.5cm (1½–2in)

Family NOTODONTIDAE

Species *Epiconna melanosticta*

Author Donovan

COMMON EPICOMA MOTH


This beautiful species has white forewings speckled with black scaling and margined with a chequered pattern of black and yellow. The hindwings are blackish and richly margined with a golden, yellow, toothed pattern.

• **EARLY STAGES** The caterpillar is dark brown in colour and has tufts of short, brown hairs. It tends to feed on the foliage of eucalyptus.

• **DISTRIBUTION** Widespread in eastern and southern Australia.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat ●

Wingspan 4–5cm (1½–2in)

Family NOTODONTIDAE

Species *Thaumetopoea pityscampa*


Author Denis & Schiffenmiller

PINE PROCESSIONARY MOTH


This is a rather drab species with greyish white forewings banded with dark, greyish brown.

• **EARLY STAGES** The greyish black caterpillar is covered with fine, white hairs along the sides, and has reddish brown warts. Caterpillars move in a head-to-tail procession in search of pine needles on which they feed. They can cause damage to forest plantations.

• **DISTRIBUTION** Found in Mediterranean countries, including those of North Africa.



PALAARCTIC



Time of Flight ☾


Habitat ●


Wingspan 4–5cm (1½–2in)

Noctuidae

THIS IS ONE OF THE LARGEST and most important of all moth families, with more than 25,000 species occurring worldwide. Noctuid moths are quite robust, and range in size from extremely small to very large. Most are nocturnal and for this reason are often known as owlet moths. The majority of the species are rather drab in colour, ranging from brown to grey,

but others are quite bright and may even mimic butterflies. This family contains two important groups of caterpillars that are notorious pests: cutworms that bite through plant stems at ground level; and armyworms that swarm in bands and can devastate entire crops. The pupae of many species of Noctuid moths are formed in the soil at the base of the foodplant.

Family	NOCTUIDAE	Species	<i>Agrotis infusa</i>	Author	Borlundaal
BOGONG MOTH The forewings of this moth range in colour from dark brown to greyish black, and are patterned with brown; the hindwings are dark greyish brown. • EARLY STAGES The smooth cutworm caterpillar varies in colour from black to greenish brown or grey. In numbers it can cause serious damage to cultivated crops such as cereals and vegetables. • DISTRIBUTION Can be found throughout temperate regions of southern Australia.					
Time of Flight	☾	Habitat	☎ 🌱 🏠	Wingspan	3-5.5cm (1 1/4-2 1/4)

Family	NOCTUIDAE	Species	<i>Agrotis ipsilon</i>	Author	Hufnagel
DARK SWORD-GRASS The forewings of this species are pale brown with dark brown and black markings. The hindwings are translucent, greyish white with brown veins. • EARLY STAGES The smooth caterpillar is dark purplish or greenish brown with grey lines and grey spots. It feeds on potatoes (<i>Solanum</i>), tobacco (<i>Nicotiana</i>), cabbage (<i>Brassica</i>), and cotton (<i>Gossypium</i>). In many regions it is regarded as a serious pest. • DISTRIBUTION Throughout the world, including the temperate regions of North and South America, Asia, Australia, Africa, and Europe.					
Time of Flight	☾	Habitat	☎ 🌱 🏠	Wingspan	4-5.5cm (1 1/4-2 1/4in)

Family NOCTUIDAE

Species *Heliothis armigera*

Author Hübner

OLD WORLD BOLLWORM

This is a very variable moth. The forewing colour ranges from pale brownish yellow to reddish brown with darker lines or bands. The hindwings are translucent, pale grey with blackish brown veins and marginal bands. It is also known as the scarce bordered straw.

• **EARLY STAGES** The caterpillar has many colour forms ranging from brown to green, with granular skin and yellowish white lines along the back and sides. It feeds on a wide range of low-growing plants, including cultivated crops

such as cotton (*Gossypium*), tomatoes (*Lycopersicon*) and maize (*Zea mays*), and is a serious pest.

• **DISTRIBUTION**

Range extends from Europe to Africa, Asia, and Australia. It is so migrates to the British Isles, where it is called the scarce bordered straw.

highly effective camouflage



CATERPILLAR OF
HELIOTHIS ARMIGERA

minute, black dots along forewing margin



PALEARCTIC,
AFROTROPICAL,
INDO-AUSTRALIAN

Time of Flight ☾

Habitat 🌱 🌾 🍷

Wingspan 3–4cm (1¼–1½in)

Family NOCTUIDAE

Species *Noctua pronuba*

Author Linnaeus

LARGE YELLOW UNDERWING

This distinctive moth is variable in both sexes. The forewings of the males range in colour from mid brown to brownish black, while those of the females vary from reddish brown to yellowish or greyish brown. The hindwings of both sexes are deep yellow with a black border.

• **EARLY STAGES** The caterpillar is variable in colour, ranging from greyish brown to bright green, but can be recognized by the two rows of black dashes along the back. It feeds on dock (*Rumex*), dandelion (*Taraxacum*), and grasses, and is a minor pest of garden flowers and vegetables.

• **DISTRIBUTION** Europe, ranging to North Africa and western Asia.




distinctive, black marking near forewing tip



deep, black border to hindwings

bright yellow hindwing gives rise to the common name




PALEARCTIC

Time of Flight ☾


Habitat 🌱 🌾 🍷

Wingspan 5–6cm (2–2½in)


Family NOCTUIDAE	Species <i>Peridroma tanais</i>	Author Hübner
<p>PEARLY UNDERWING</p> <p>This notorious pest has reddish brown or greyish brown forewings, variably patterned with blackish brown. The hindwings are pearly grey, with brown veins and a dark brown suffusion towards the margins.</p> <p>• EARLY STAGES The plump caterpillar is coloured greyish brown tinged with purplish red on its back.</p> <p>• DISTRIBUTION Europe to Turkey, India, North Africa, and the Canary Isles, and North America.</p>		
Time of Flight ☾	Habitat ⚡ ⚡ ⚡ ⚡ ⚡	Wingspan 4.5-5cm (1 1/2-2in)




HOLARCTIC



Family NOCTUIDAE	Species <i>Antleria geminata</i>	Author Linnaeus
<p>ANTLER MOTH</p> <p>This distinctive species gets its name from the antler-shaped, yellowish white markings on the brown forewings. These markings are variable and are often interspersed with dark brown streaks. It is attracted to thistles (<i>Cirsium</i>) and other flowers.</p> <p>• EARLY STAGES The caterpillar is bronze, and has three pale brown stripes and a wrinkled, glossy skin. It feeds on various grasses.</p> <p>• DISTRIBUTION Europe, across temperate Asia to Siberia, and North America.</p>		
Time of Flight ☾ ~	Habitat ⚡ ⚡ ⚡	Wingspan 2.5-3cm (1-1 1/4in)




PALAEARCTIC



Family NOCTUIDAE	Species <i>Manestra brassicae</i>	Author Linnaeus
<p>CABBAGE MOTH</p> <p>The forewing of this dark brown, mottled moth is distinctively marked with shining, white spots and lines. The hindwing is dark greyish brown, becoming paler towards the base.</p> <p>• EARLY STAGES The caterpillar is green when young, but in the final stage it is brown with a broad, orange band along each side. As its name suggests, this species feeds on cabbage (<i>Brassica</i>), as well as various other plants.</p> <p>• DISTRIBUTION Europe, and Asia, from India to Japan.</p>		
Time of Flight ☾	Habitat ⚡ ⚡ ⚡	Wingspan 3-5cm (1 1/4-2in)



PALAEARCTIC



Family NOCTUIDAE


Species *Utetheisa anisopuncta*

Author Haworth

WHITE-SPECK

This distinctive, cinnamon brown moth has a small, white spot in the middle of the forewings, which are often speckled with black and sometimes tinged with orange. The brown-veined hindwings are a glossy, translucent grey suffused with dark brown.

- **EARLY STAGES** The caterpillar is greyish brown and has an orange band along the sides. It feeds on grasses.
- **DISTRIBUTION** North and South America, Mediterranean Europe, and parts of Africa.



HOLARCTIC



silvery white
fringes on hindwing

Time of Flight ☾

Habitat 🌿 🌾 🍄

Wingspan 3–4cm (1½–1½in)

Family NOCTUIDAE



Species *Xanthopastis tenebris*

Author Cramer

SPANISH MOTH

With its pink forewings marked with black and orange, this species is unmistakable. However, despite its bright colours, this moth is well camouflaged when it rests on tree trunks with folded wings.

- **EARLY STAGES** The caterpillar is greyish black spotted with white. It feeds on the foliage of fig (*Ficus*) and narcissi (*narcissus*).
- **DISTRIBUTION** Tropical South and Central America, into the USA.

NEOTROPICAL
NEARCTIC

Time of Flight ☾

Habitat 🌿 🌾 🍄

Wingspan 4–4.5cm (1½–1½in)

Family NOCTUIDAE

Species *Guculia conserpennis*

Author Grote & Robinson


BROWN HOODED OWLET

This moth belongs to a large and distinctive group known collectively as the sharks, presumably because of the streamlined appearance of their folded wings when they are at rest.

- **EARLY STAGES** The caterpillar is striped with red and black. It feeds on the flowers of aster, golden rod (*Solidago virgaurea*), and various other low-growing plants.
- **DISTRIBUTION** Widespread in the USA, extending northwards into southern Canada.



NEARCTIC



Time of Flight ☾

Habitat 🌿 🌾 🍄

Wingspan 4–5cm (1½–2in)

Family NOCTUIDAE

Species *Xanthia rogata*


Author Esper

PINK-BARRED SALLOW


The common name of this brightly coloured moth is misleading as it is not pink-banded at all. Its forewings are yellow to orange-yellow, with a broad red or purple band. The sexes are alike.

• **EARLY STAGES** The caterpillar is reddish or purplish brown with dark speckling. It feeds on willow catkins (*Salix*) and low plants.

• **DISTRIBUTION** Occurs from Europe to temperate Asia; also in southern Canada and the northern USA.



HOLARCTIC



Time of flight ☾

Habitat

Wingspan 3-4cm (1 1/4-1 1/2 in.)

Family NOCTUIDAE

Species *Acronicta psi*


Author Linnaeus

GREY DAGGER


The forewings of this moth vary in colour from greyish white to dark grey, but they all have the distinctive dagger shaped marking on the margin that gives rise to the common name. The sexes are similar, but females have darker hindwings.

• **EARLY STAGES** The caterpillar is dark bluish grey with a broad band of yellow along the back and red spots along the sides. It feeds on deciduous trees.

• **DISTRIBUTION** Occurs in Europe, through North Africa, and Central Asia.



PALAEARCTIC



Time of flight ☾

Habitat

Wingspan 3-4 cm (1 1/4-1 1/2 in.)

Family NOCTUIDAE

Species *Amphiprora pyramoides*

Author Guenée

AMERICAN COPPER UNDERWING


This attractive moth is easily recognized by its coppery brown hindwings. The dark brown forewings are variably patterned with light and dark lines. The sexes are similar.

• **EARLY STAGES** The green caterpillar feeds on a wide range of broad-leaved trees and shrubs, including apple (*Malus domestica*) and species of hawthorn (*Crataegus*).

• **DISTRIBUTION** Widespread from southern Canada through the USA south to Mexico.



NEARCTIC



Time of flight ☾

Habitat

Wingspan 4-5cm (1 1/2-2 in.)

Family NOCTUIDAE

Species *Russocla fovea*

Author Fuller

MAIZE STALK-BORER MOTH

This notorious maize and sorghum pest has rather rectangular forewings, varving in colour from reddish brown to dark blackish brown. The hindwings are shining brownish white. The sexes are similar.

• **EARLY STAGES** The caterpillar is dusky, purplish pink with a reddish brown head and greyish brown spots along the sides.


• **DISTRIBUTION** Occurs in wet savanna regions of Africa, south of the Sahara, where cereal crops are grown.



AFROTROPICAL

oblique dark band
• on forewings

dark rectangular
marking in centre
• of forewings



• characteristic,
heavy body

Time of Flight ☾

Habitat 🌿 🌾 🌳

Wingspan 2.5–3cm (1–1¼in)

Family NOCTUIDAE

Species *Phlogopora iris*

Author C. Lence

OLIVE ANGLE SHADES

This distinctive moth is prettily patterned on the forewings with olive green and pinkish brown. The hindwings are brownish white, shaded with dark brown at the margin, with pinkish brown, marginal lines. The wing margins are scalloped.

• **EARLY STAGES** The caterpillar is known to feed on various types of low-growing plants, such as dandelion (*Taraxacum*) and docks (*Rumex*).

• **DISTRIBUTION** Occurs in eastern and central Canada and the northern USA.



NEARCTIC

distinctive, black "scribble"
• on forewings



• sharply scalloped
margin of forewings

Time of Flight ☾

Habitat 🌿 🌾 🌳

Wingspan 4–4.5cm (1½–1¾in)

Family NOCTUIDAE

Species *Spodoptera litura*

Author Fabricius

ORIENTAL LEAFWORM MOTH

The brown forewings of this widespread pest moth are intricately and variably patterned with pale lines and dark streaks. The hindwings are much paler, with translucent, silvery white and dark veins. The sexes are alike.

• **EARLY STAGES** The caterpillar ranges from greenish brown to dark grey, finely speckled with white. It feeds on a wide range of native and cultivated plants.

• **DISTRIBUTION** Range extends from India to South east Asia and Australia.



INDO-AUSTRALIAN

black streak, on purplish
• grey band of forewings

forewing
pattern
continues on
• thorax




• dark, marginal line
around hindwings

Time of Flight ☾


Habitat 🌿 🌾 🌳

Wingspan 3–4cm (1¼–1½in)

Family NOCTUIDAE	Species <i>Spodoptera exigua</i>	Author Hübner
SMALL MOTTLED WILLOW MOTH <p>This greyish brown, mottled moth is a notorious pest species in many parts of the world. It has translucent, pearly white hindwings with dark brown veins.</p> <ul style="list-style-type: none"> • EARLY STAGES The caterpillar varies in colour from green to dark grey, with black markings on the back and a pinkish brown line along the sides. It feeds on crops such as maize (<i>Zea mays</i>) and cotton (<i>Gossypium</i>). • DISTRIBUTION Virtually throughout the world, in both tropical and temperate regions. 		
Time of flight ☾	Habitat 🌿 🌾 🍷	Wingspan 2–3cm (1 1/4in)



WORLDWIDE




♂

Family NOCTUIDAE	Species <i>Spitheta nigrivitta</i>	Author Guenee
BLACK TURNIP MOTH <p>(One of two species in an exclusively Australian genus, this is a very dark moth with black forewings patterned with intense jet black.)</p> <ul style="list-style-type: none"> • EARLY STAGES The green caterpillar has two white spots on the back near the tail. It feeds on a range of wild and cultivated plants, and is sometimes a serious pest of such field crops as turnip (<i>Brassica</i>), sugar beet (<i>Beta vulgaris</i>), and maize (<i>Zea mays</i>). • DISTRIBUTION From southern Queens and to south-western Australia and Tasmania. 		
Time of flight ☾	Habitat 🌿 🌾 🍷	Wingspan 4–4.5cm (1 1/2–1 3/4in)




INDO AUSTRALIAN




♀

Family NOCTUIDAE	Species <i>Earias biplaga</i>	Author Walker
SPINY BOLLWORM MOTH <p>This pretty little moth is one of a group of species that are major pests of cultivated cotton in Africa and Asia. This species is very variable, ranging in forewing colour from moss-green to greenish yellow, and is sometimes strongly suffused with purplish red.</p> <ul style="list-style-type: none"> • EARLY STAGES The small, greyish brown caterpillar is finely banded with white and spotted with red, and has spines along the back and sides. It feeds on cotton (<i>Gossypium</i>) and related plants. • DISTRIBUTION Widespread in Africa, south of the Sahara. 		
Time of flight ☾	Habitat 🌿 🌾 🍷	Wingspan 2–2.5cm (3/4–1in)



AFROTROPICAL



♀

Family NOCTUIDAE

Species *Pseudorhyssa jaganii*

Author Fabricius


GREEN SILVER-LINES

This aptly named moth has three silvery white, oblique lines on its green forewings, although a form exists in which there are only two lines. The forewing fringes are sometimes strongly tinged with red. Males have pale greenish yellow hindwings with white bases, whereas those of the female are pure white.

• **EARLY STAGES** The plump, green caterpillar is spotted and patterned with yellowish white. It has broad lines of the same colour along its back. The rear claspers are extra long and striped with red. It feeds on the foliage of many broad-leaved trees, particularly oaks (*Quercus*) and beech (*Fagus sylvatica*).

• DISTRIBUTION

Widespread in Europe, extending across temperate Asia to Siberia and Japan.



Time of Flight ☾

Habitat 🌳

Wingspan 3–4cm (1¼–1½in)

Family NOCTUIDAE

Species *Achaea janata*

Author Linnaeus

CASTOR SEMI-LOOPER MOTH

The forewings of this large Noctuid moth are variably lined and banded with shades of brown, but it is the distinctively patterned black and white hindwings that make this species easy to recognize.


• **EARLY STAGES** The long, slender caterpillar ranges in colour from black with fine, broken lines of orange-red, to pale pinkish brown with dark bands and pale mottling. It moves in a characteristic "looping" manner, hence the common name. The caterpillar feeds on castor oil plant (*Ricinus communis*), cowpea (*Vigna unguiculata*), chilli pepper (*Capsicum annuum*), rose (*Rosa*), and many other plants.

• DISTRIBUTION

From India to Taiwan, Australia, and New Zealand.



CATERPILLAR OF
ACHAEA JANATA



INDO-AUSTRALIAN

Time of Flight ☾

Habitat 🌳 🌾


Wingspan 5.5–6cm (2¼–2½in)

Family NOCTUIDAE	Species <i>Catocala fraxini</i>	Author Linnaeus
------------------	---------------------------------	-----------------

CLIFDEN NONPAREIL

The forewings of this handsome species have a camouflage pattern of greyish white and dark greyish brown. The hindwings are blackish brown with a distinctive band of dusky blue. The sexes are similar.

- **EARLY STAGES** The long caterpillar is grey, mottled with brown. It is well camouflaged when it rests on a twig. It feeds primarily on ash (*Fraxinus excelsior*), and aspen (*Populus tremula*).
- **DISTRIBUTION** Widespread in central and northern Europe. Formerly resident in the British Isles, it now occurs there as an occasional migrant. Ranges across temperate Asia to Japan.



extremely slender antennae •

PALEARCTIC

Time of Flight ☾

Habitat 🌳


Wingspan 7.5–15cm (3–3 1/2 in)

Family NOCTUIDAE	Species <i>Catocala illia</i>	Author Cramer
------------------	-------------------------------	---------------

ILIA UNDERWING

This is one of a large number of red underwing moths in North America. The camouflaged forewings are quite variable in pattern, ranging from mottled dark greyish brown to almost black. The pinkish red hindwing has two broad, black, irregular bands. This species is also known as the beloved underwing or the wife. The sexes are alike. Moths are on the wing from summer to autumn.

- **EARLY STAGES** The long grey caterpillar has a distinctly rough skin and is well camouflaged when resting pressed to the surface of a twig. It feeds on the foliage of oaks (*Quercus*).
- **DISTRIBUTION** One of the most widespread and abundant of the Underwings in North America, ranging from southern Canada to Florida. A similar species, the dark crimson underwing (*Catocala sponsa*) occurs throughout Europe.



intricate patterning on forewings •

pink mark in middle of forewing is sometimes white •

distinguishing indentation of band on hindwings •

robust body •

NEARCTIC

Time of Flight ☾

Habitat 🌳

Wingspan 7–8cm (2 1/4–3 1/4 in)

Family NOCTUIDAE

Species *Grammodes stolidus*

Author Fabricius

THE GEOMETRICIAN

The forewings are brown banded with cream and dark chocolate brown while the hindwings are brown with white bands and chequered fringes.

The sexes are similar.

• **EARLY STAGES** The caterpillar feeds on oaks (*Quercus*), brambles (*Rubus*), jujuba (*Zizyphus jujuba*), and other trees and shrubs

• **DISTRIBUTION**

Med terranean Europe, Africa, India, and South-east Asia



PALAEARCTIC
AFROTROPICAL
INDO-AUSTRALIAN



♀

Orange-brown
• band on forewings

• distinctive, white
spot on hindwings

Time of Flight ☾

Habitat 🌿 🌳 🌲

Wingspan 2.5–4 cm (1–1½ in)

Family NOCTUIDAE

Species *Chrysodeixis intusilem*

Author Walker

AUSTRALIAN CABBAGE LOOPER

The forewings of this moth are reddish brown with greyish brown bands and distinctive, silvery white markings. The hindwings are greyish brown with greyish white at the base. The sexes are similar.

• **EARLY STAGES** The semi-looper caterpillar is known to be a pest of field and glasshouse crops.

• **DISTRIBUTION** Found in South and south-eastern Australia and central Queensland. It also occurs in Papua New Guinea, and two other islands, New Caledonia, and Fiji



INDO-AUSTRALIAN



♀

distinctive silvery
white line of
• forewings

• pale brown fringe

Time of Flight ☾

Habitat 🌿 🌳 🌲

Wingspan 2.5–4 cm (1–1½ in)

Family NOCTUIDAE

Species *Antigrapha gamma*

Author Linnaeus

SILVER “Y” MOTH

The greyish brown forewing colour is variable. The hindwings are greyish white at the base with broad dark grey margins. The sexes are alike.

• **EARLY STAGES** The caterpillar is bright yellowish to bluish green with a pattern of fine white lines. It eats a variety of plants including clover (*Trifolium*) and lettuce (*Lactuca sativa*)

• **DISTRIBUTION** Resident in southern Europe, North Africa and western Asia, but migrates northwards as far as the Arctic Circle each year.



PALAEARCTIC



♀



gamma-shaped marking gives rise
• to the scientific name



scalloped
• hindwing margin



Time of Flight ☾ ☼

Habitat 🌿 🌳 🌲

Wingspan 3–5 cm (1½–2 in)

Family	NOCTUIDAE	Species	<i>Triothisa</i>	Author	Hubner						
<h3>THE NI MOTH</h3> <p>The forewings are mottled with brown, but they can be distinguished by a silvery white, U-shaped marking and a white spot. The hindwings are dark greyish brown, but paler towards the base.</p> <ul style="list-style-type: none">• EARLY STAGES The green caterpillar is lined and spotted with white. It feeds on cabbage (<i>Brassica</i>), marze (<i>Zea mays</i>), and other crops.• DISTRIBUTION Widespread in Europe, North Africa, and the temperate northern hemisphere <div><p>HOLARCTIC</p></div> <div><p>♂</p></div> <div><table border="1"><tr><td>Time of Flight</td><td>☾</td><td>Habitat</td><td>grass, etc.</td><td>Wingspan</td><td>3-4cm (1 1/4-1 1/2in)</td></tr></table></div>						Time of Flight	☾	Habitat	grass, etc.	Wingspan	3-4cm (1 1/4-1 1/2in)
Time of Flight	☾	Habitat	grass, etc.	Wingspan	3-4cm (1 1/4-1 1/2in)						

Family	NOCTUIDAE	Species	<i>Hypocrita</i>	Author	Linnaeus						
<h3>THE SNOOT</h3> <p>The snout is so-called because of the long, sensory mouthparts called palps that project in front of its head. The brown forewings are distinctively shaped and strongly pointed at the tips. The large, rounded hindwings are greyish brown. The sexes are alike.</p> <ul style="list-style-type: none">• EARLY STAGES The long, slender caterpillar is green with yellowish rings and pale lines along the back and sides. It feeds on stinging nettles (<i>Urtica dioica</i>).• DISTRIBUTION Found where nettles abound throughout Europe into temperate Asia <div><p>PALEARCTIC</p></div> <div><p>♂</p></div> <div><table border="1"><tr><td>Time of Flight</td><td>☉ ☾</td><td>Habitat</td><td>grass, etc.</td><td>Wingspan</td><td>4-4.5cm (1 1/2-1 7/8in)</td></tr></table></div>						Time of Flight	☉ ☾	Habitat	grass, etc.	Wingspan	4-4.5cm (1 1/2-1 7/8in)
Time of Flight	☉ ☾	Habitat	grass, etc.	Wingspan	4-4.5cm (1 1/2-1 7/8in)						

Family	NOCTUIDAE	Species	<i>Apha</i>	Author	Linnaeus						
<h3>EASTERN ALCHYMIST</h3> <p>This species is most easily recognized by the distinctive hindwings, which have pure white bases and white spots on the fringe. The dark brown forewings may be marked with white.</p> <ul style="list-style-type: none">• EARLY STAGES The caterpillar is bluish grey with orange-yellow stripes. It is known to feed on sweet potato (<i>Ipomoea batatas</i>), and skeleton weed (<i>Chondrilla juncea</i>).• DISTRIBUTION Widespread in the Indo-Australian region and parts of southern Europe. <div><p>INDO-AUSTRALIAN PALEARCTIC</p></div> <div><p>♂</p></div> <div><table border="1"><tr><td>Time of Flight</td><td>☾</td><td>Habitat</td><td>grass, etc.</td><td>Wingspan</td><td>3-4cm (1 1/4-1 1/2in)</td></tr></table></div>						Time of Flight	☾	Habitat	grass, etc.	Wingspan	3-4cm (1 1/4-1 1/2in)
Time of Flight	☾	Habitat	grass, etc.	Wingspan	3-4cm (1 1/4-1 1/2in)						

Family NOCTUIDAE

Species *Alabama argillacea*


Author Hübner

COTTON MOTH


The forewings of this moth vary from pinkish to olive-brown. The adults can pierce the skins of fruit with their tongues, causing damage.

• **EARLY STAGES** The caterpillar is yellowish green, marked with black, with white lines along the back. It feeds on cotton plants (*Gossypium*), and is a serious pest of cultivated cotton in the USA

• **DISTRIBUTION** Tropical South and Central America to the temperate USA and Canada



NEOTROPICAL
NEARCTIC



♂

Time of Flight ☾

Habitat 🌿 🌳 🌲

Wingspan 3–4cm (1¼–1½in)

Family NOCTUIDAE

Species *Ascalapha odorata*

Author Linnaeus

BLACK WITCH


This large, dark brown moth has sharply pointed forewings and rather square hindwings. The forewings each have a dark, comma-shaped marking, while the hindwings have large and irregular-shaped eyespots. Black witches have hairy bodies. Females have a pale purplish pink band crossing their fore- and hindwings.

• **EARLY STAGES** The caterpillar is dark brown, becoming paler towards the tail. It feeds on *Cassia* and related plants.

• **DISTRIBUTION** Occurs in tropical South and Central America, also California and other southern parts of the USA



NEOTROPICAL
NEARCTIC



♂

Time of Flight ☾

Habitat 🌿 🌳 🌲


Wingspan 11–15cm (4¼–6in)

Family NOCTUIDAE	Species <i>Calyptra eustrigata</i>	Author Hampson
------------------	------------------------------------	----------------


VAMPIRE MOTH

The vampire moth belongs to a group of moths noted for their ability to pierce the skin of fruits. This species has a barbed tongue capable of piercing the skin of mammals such as cattle and deer, and feeds on their blood.

- **EARLY STAGES** Little seems to be known of the caterpillar or its foodplants.
- **DISTRIBUTION** From India and Sri Lanka to Malaysia



NEOAUSTRALIAN



Time of Flight ◀

Habitat 🌿 🌳 🌾 🍷


Wingspan 3-4cm (1½-1¾ in)

Family NOCTUIDAE	Species <i>Scythris phlox</i>	Author Linnaeus
------------------	-------------------------------	-----------------


THE HERALD

A very distinctive moth, the herald has reddish brown to purplish brown forewings with pale lines and bright orange scales towards the base.

- **EARLY STAGES** The long, slender caterpillar is velvety green with two fine, yellow lines along its back. It feeds on the foliage of willows (*Salix*), and poplars (*Populus*).
- **DISTRIBUTION** Europe to North Africa, across temperate Asia to Japan; also in North America.



HOLARCTIC



Time of Flight ◀

Habitat 🌿 🌳 🌾 🍷


Wingspan 4-5cm (1½-2 in)

Family NOCTUIDAE	Species <i>Dipthera festiva</i>	Author Fabricius
------------------	---------------------------------	------------------


HIEROGLYPHIC MOTH

This appropriately named moth is quite unmistakable, with yellow forewings distinctively patterned with metallic greyish blue, and three rows of blue-grey spots along the margin.

- **EARLY STAGES** The caterpillar is slate-blue to greenish grey with black stripes. It feeds on the foliage of sweet potato (*Ipomoea batatas*).
- **DISTRIBUTION** From tropical South and Central America to Florida and Texas in southern USA.



NEOTROPICAL



Time of Flight ◀

Habitat 🌿 🌳 🌾 🍷

Wingspan 4-5cm (1½-2 in)

Family NOCTUIDA

Species *Adriana fulvipes*


Author (Clerck)

TROPICAL FRUIT-PIERCER


This is a very distinctive, large moth with orange or orange-yellow hindwings with black markings.

• **EARLY STAGES** The long caterpillar varies in colour from green to black, and has well developed false eyespots on the body.

• **DISTRIBUTION** Tropical Africa, South east Asia, to Australia.



AFRICA
SOUTH EAST ASIA
AUSTRALIA



Time of Flight

Habitat

Wingspan 8-10cm (3 1/4-4 in)

Family NOCTUIDA

Species *Thysania agrippa*


Author (Cramer)

GIANT AGRIPPA


The giant agrippa has the largest wingspan of any moth in the world. Both fore- and hindwings are greyish white with an intricate pattern of blackish brown lines.

• **EARLY STAGES** The caterpillar is undescribed but feeds on Leguminosae shrubs.

• **DISTRIBUTION** Southern Brazil through Central America.



NEOTROPICS



Time of Flight

Habitat

Wingspan 23-30cm (9-12 in)

AGARISTIDAE

T HIS RELATIVELY small family of moths is composed of about 300 species that occur throughout the tropical forest regions of the world. They are similar in general appearance to moths of the family Noctuidae, but can usually be distinguished by their distinctive antennae which tend to be

thickened towards the tips. Most of the Agaristid moths are day fliers; they have a rapid, powerful flight


Many species are brightly coloured, and their caterpillars also appear to be avoided by predators, suggesting that they are distasteful to birds.

Family	AGARISTIDAE	Species	<i>Agarista agricola</i>	Author	D. novak
--------	-------------	---------	--------------------------	--------	----------


LARGE AGARISTA

This striking and distinctive, black moth is variably patterned with bright orange, yellow, red, and metallic greyish blue. Males are generally smaller and darker with less extensive yellow markings at the base of the forewing.

- **EARLY STAGES** The caterpillar is patterned with bands of orange, yellowish white, and black. When fully grown, the white bands turn orange. It is known to feed by day on the foliage of various vines, including grapevine (*Vitis vinifera*), *Cissus*, and *Cayratia*.
- **DISTRIBUTION** From northern Australia to Queensland and central NSW.



INDO-AUSTRALIAN




Time of Flight	☀	Habitat	🌿 🌳 🏠	Wingspan	5.5–7 cm (2 1/4–2 3/4 in)
----------------	---	---------	-------	----------	---------------------------

Family	AGARISTIDAE	Species	<i>Alipia octomaculata</i>	Author	Fabricius
--------	-------------	---------	----------------------------	--------	-----------


EIGHT-SPOTTED FORESTER

The North American representative of a largely tropical group, this species can be recognized by the distinctive wing spots. The forewing spots are pale yellow; the hindwing spots are white.

- **EARLY STAGES** The caterpillar is black with orange stripes and has a black-spotted, orange head. It feeds on grapevine (*Vitis vinifera*) and Virginia creeper (*Parthenocissus*).
- **DISTRIBUTION** From south-eastern Canada right through the USA as far south as Texas.



NEARCTIC



Time of Flight	☀	Habitat	🌿 🌳 🏠	Wingspan	3–4 cm (1 1/4–1 1/2 in)
----------------	---	---------	-------	----------	-------------------------

LYMANTRIIDAE

THIS LARGE FAMILY of some 2,500 species occurs worldwide, but is most strongly represented in the tropics of Africa. The moths are similar to those of the family Noctuidae, but they are generally rather hairy in appearance. The wings are usually pale or dull in colour, although some tropical species are more brightly patterned. Some females have greatly reduced wings so they are unable to

fly. Lymantriid moths like some other moth families lack functional tongues and cannot feed in the adult stage.

The caterpillars are hairy and often brightly coloured. Many species have body hairs grouped in distinctive toothbrush-like tufts, giving rise to the common name of tussock moths. The hairs of many of these caterpillars are irritant, and can cause rashes.

Family LYMANTRIIDAE

Species *Lymantria dispar*

Auk or Linnaeus

GYPSEY MOTH




The sexes of this well-known pest moth are very different from each other. Males are pale yellowish brown with dark brown patterning on the forewings and dark brown borders to the hindwings, while the larger females are predominantly white with distinctive, black markings on the forewings.

Gypsy moths are on the wing in summer.

Males fly by day, but the sluggish females do not fly at all, and seldom move far from their emergence place.

• **EARLY STAGES** The caterpillar is bluish grey with raised, red and blue, tufted spots on the back. Although showing a preference for oaks (*Quercus*), they will eat the foliage of most trees and shrubs and are often a serious pest, sometimes stripping the foliage from large areas of forest. There is one generation a year.

• **DISTRIBUTION** Originally a native of Europe and temperate Asia, this moth was introduced into North America in the mid-19th century with a view to using it for silk production. However, moths escaped and the species became established as one of the worst insect pests in North America. It is not regarded as such a serious pest in Europe.



HOLARCTIC

Time of Flight C

Habitat

Wingspan 4-6cm (1½-2 in)

Family	LYMANTRIIDAE	Species	<i>Calliteara pudibunda</i>	Author	Linnaeus
--------	--------------	---------	-----------------------------	--------	----------

PALE TUSOCK

Males of this heavy bodied moth have pale greyish white forewings with a dark greyish brown, central band. The pale hindwings have a dark brown band. Females are larger with white forewings, suffused and finely lined with greyish brown.

• **EARLY STAGES** The hairy caterpillar is yellow or pale green with two black bands between the body segments, and a bright pink tuft of hairs near the tail. It feeds on the foliage of many broad leaved trees

• **DISTRIBUTION** Widespread in Europe extending across temperate Asia to Japan.



PALEARCTIC



heavily feathered antennae of male



crescent shaped marking darker than on female

pale crescent-shaped marking on hindwing

dark spotting to forewing margin

Time of Flight	☾	Habitat	🌳	Wingspan	5-7cm (2-2 1/2in)
----------------	---	---------	---	----------	-------------------

Family	LYMANTRIIDAE	Species	<i>Euproctis chrysorrhoea</i>	Author	Linnaeus
--------	--------------	---------	-------------------------------	--------	----------

BROWN-TAIL, MOTH

This distinctive, white moth is appropriately named because of the large tuft of loose brown scales at the tip of the body of the female. The male lacks the distinctive tuft, and has a slender brown "tail". These moths are on the wing in summer. This moth is single brooded

• **EARLY STAGES** The hairy, brown caterpillar has orange-red markings on its back, and white, scale-like hairs along its sides. It lives in a communal silken nest, and feeds on the foliage of blackthorn (*Prunus spinosa*), hawthorns (*Crataegus*), and various fruit and ornamental trees. The caterpillar has barbed hairs, which can cause a painful rash.

• **DISTRIBUTION** Widespread throughout Europe, including the British Isles, south to North Africa and the Canary Islands. It was introduced into North America, but now it is mainly confined to the north-east coast of the USA.



HOLARCTIC



distinctive red spots on back

CATERPILLAR OF EUPROCTIS CHRYSORRHOEA

pure white wings lack markings



tuft of poisonous hairs provide a protective cover for the eggs

Time of Flight	☾	Habitat	🌳 🌳 🌳	Wingspan	3-4.5cm (1 1/4-1 1/2in)
----------------	---	---------	-------	----------	-------------------------

Family LYMANTRIIDAE

Species *Euproctus edwardsii*


Author Newman

MISTLETOE BROWNTAIL MOTH


This hairy-looking, greyish brown moth lacks distinctive markings, but the forewings appear rather thinly scaled. The hindwing margins are lightly tinged with yellowish brown.

• **EARLY STAGES** The hairy caterpillar is dark reddish brown with a white band along the back. The hairs can cause serious skin rashes. It feeds on mistletoe (*Ameyma*).

• **DISTRIBUTION** Australia, from Queensland and NSW to Victoria and South Australia.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌳

Wingspan 4.5-5.7cm (1 3/4-2 1/4 in)

Family LYMANTRIIDAE

Species *Disphrys pyrrhoma*

Author Hampson

FIERY TUSOCK


The fiery tussock is a striking white member of this large genus of moths. The forewings of the male are patterned with a series of very pale, brownish yellow lines, which are more suffused in the otherwise similar female. The abdomen is patterned with bright orange-red bands and tufts.

• **EARLY STAGES** The caterpillar is apparently undescribed. Its foodplants are *Fuirena*, *Parinari*, and *Protea*.

• **DISTRIBUTION** Range extends from Zimbabwe to Transvaal and Natal.



AFROTROPICAL



Time of Flight ☾

Habitat 🌳

Wingspan 4.5cm (1 3/4 in)

Family LYMANTRIIDAE

Species *Euproctus hemivittata*

Author Collenette

COLLENETTE'S VARIEGATED BROWNTAIL

This is one of a large group of South-east Asian browntails that are variably patterned with brown and yellow. Collenette's variegated browntail is characterized by the presence of black spots in the yellow margin of the forewing.


• **EARLY STAGES** Nothing is known of the immature stages of this moth.

Many species in this group feed on the foliage of tropical fruit, Cocoa (*Coccoloba*), *Lantana*, Acacia and cultivated trees.

• **DISTRIBUTION** Found in tropical forests of Sumatra.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌳

Wingspan 3-4.5cm (1 1/4-1 3/4 in)

Family LYMANTRIIDAE

Species *Orga leucostigma*

Author Smith

WHITE-MARKED TUSSOCK MOTH

Males of this species have dark brownish grey wings. The forewings are banded with brown. The greyish white females are wingless.

• **EARLY STAGES** The brownish yellow caterpillar has long, plume like tufts of black and white hairs at the head and tail. It feeds on a wide range of broad-leaved and coniferous trees and is sometimes a pest in forest plantations.

• **DISTRIBUTION** Found in North America and many other parts of the USA.



NEARCTIC



distinctive, black, marginal
line on forewing

small white patch gives
rise to the common name

Time of Flight ☾

Habitat 🌳

Wingspan 2.5-4cm (1-1 1/2 in)

Family LYMANTRIIDAE

Species *Leptocera retacta*


Author Walker

CEDAR TUSSOCK

This rather dull brown moth is one of two species in the genus which is confined to Australia. The forewing has distinctive dark brown markings and an indistinct, brown, marginal line. The hindwings of the male are a pale translucent brown with darker fringes, and a pale brown marking.

• **EARLY STAGES** The hairy caterpillar feeds on the foliage of white cedar (*Melia azedarach*), and trees that grow in urban areas.

• **DISTRIBUTION** Northern Queensland to southern NSW.



INDO-AUSTRALIAN



faint, dark dots along
forewing margin

characteristic, dark
marking on hindwing

Time of Flight ☾

Habitat 🌳 🌿

Wingspan 3-7cm (1 1/4-2 1/2 in)

Family LYMANTRIIDAE

Species *Arce discalis*

Author Walker

BANDED VAPOURER


The sexes of this moth are completely different. Males are dark reddish brown, with pale orange markings on the forewings and broad orange bands on the hindwings. Females have orange yellow wings and their forewings are patterned with brown lines. The body is orange and black.

• **EARLY STAGES** The hairy caterpillar is dark brown. It feeds on various grasses.

• **DISTRIBUTION** Range extends from Kenya and Zaire to Angola, Mozambique, and South Africa.



AFROTROPICAL



characteristic line of black spots
along forewing margin of female

distinctive, orange and
black banded hindwing

Time of Flight ☾ ☀

Habitat 🌿

Wingspan 3-4cm (1 1/4-1 1/2 in)

Family LYSANTRIIDAE

Species *Lymantria monacha*


Author Linnaeus

BLACK ARCHES

This moth is easily recognized by its white forewings with black, zigzag bands, and its greyish brown hindwings with black-spotted, white fringes. The larger females have more elongate forewings.

• **EARLY STAGES** The hairy, grey caterpillar is lined and spotted with black on the back. It is known to feed on the foliage of oak (*Quercus*) and other broad-leaves.

• **DISTRIBUTION** Europe, including the British Isles, to temperate Asia and Japan.



PALAEARCTIC

male has feathered antennae •



• characteristic, black-banded, pink abdomen

Time of Flight ☾

Habitat 🌳

Wingspan 4–5 cm (1½–2 in)

Family LYSANTRIIDAE

Species *Yponomeuta evonymella*

Author Walker

PAINTED APPLE MOTTH

Males of this tussock moth are aptly named due to their orange-marked hindwings. The forewings are banded with shades of brown and black.

• **EARLY STAGES** The hairy caterpillar has a reddish brown head and four long tufts of bristles along the back. The body hairs may cause a rash if handled. The caterpillar feeds on the foliage of various broad-leaved trees and shrubs, and can be a minor pest in orchards.

• **DISTRIBUTION** Australia, from Queensland to South Australia, and Tasmania.



INDO-AUSTRALIAN

distinctive, brown wing pattern



bright orange patches on hindwing

Time of Flight ☾

Habitat 🌳 🌿

Wingspan 2.5–3 cm (1 1/4 in)

Family LYSANTRIIDAE

Species *Orgyia antiqua*

Author Linnaeus

THE VAPOURER MOTTH

Males of this species are easily recognized by their rich reddish brown forewings. The females are virtually wingless and unable to fly.

• **EARLY STAGES** The hairy caterpillar is dark grey with red spots, and has four yellow or pale brown "toothbrush" tufts along its back, the hairs of which are irritant. It feeds on the foliage of various trees and shrubs.

• **DISTRIBUTION** Found throughout Europe, temperate Asia, Siberia, and USA.



HOLARCTIC

crescent shaped white spot



hairy hindwing margin •

Time of Flight ☼

Habitat 🌳


Wingspan 2–3 cm (¾–1½ in)


Family LAMANTRIDAE	Species <i>Palasa albimacula</i>	Author Wallengren
--------------------	----------------------------------	-------------------

WHITE BARRED GYPSY

The white barred gypsy moth has a central band of translucent, yellow white spots on the forewing. The hindwings are a translucent, yellowish brown with brown veins.

- **EARLY STAGES** The hairy, orange-brown caterpillar is darker on the back, and has a black stripe along the sides. It is known to feed on the foliage of *Commiphora*.
- **DISTRIBUTION** Angola, Zambia, and Zimbabwe to Mozambique, Transvaal, Natal, and Cape Province






Time of Flight ☾	Habitat 🌿 🌳	Wingspan 2.5-4.5cm (1-1½in)
------------------	-------------	-----------------------------


Family LAMANTRIDAE	Species <i>Psala africana</i>	Author Kiriakoff
--------------------	-------------------------------	------------------

PENNANT TUSSOCK

The distinctively shaped forewing of this moth is pale yellowish brown with a broad, purplish grey band across the middle. The hindwing is colored red white to yellow-white.

- **EARLY STAGES** The caterpillar is yellow or yellowish brown with black markings, black plumes of hair, and silky white tufts in the middle of the back. It is known to feed on *Lycorrhena*.
- **DISTRIBUTION** Throughout Africa.






Time of Flight ☾	Habitat 🌿 🌳	Wingspan 3-4.5cm (1¼-1½in)
------------------	-------------	----------------------------


Family LAMANTRIDAE	Species <i>Perina nuda</i>	Author Fabricius
--------------------	----------------------------	------------------

TRANSPARENT TUSSOCK

The transparent forewings and unusually shaped hindwings of the males of this species are quite unlike those of other tussock moths. The females have rounded, pale brown wings with darker brown scales on the forewing.

- **EARLY STAGES** The caterpillar has two tufts of dense, black hairs on the back, and greyish black hair tufts along the sides. It feeds on cultivated fig (*Ficus*).
- **DISTRIBUTION** From India and Sri Lanka to Burma, China, and Taiwan





Time of Flight ☾	Habitat 🌿 🌳	Wingspan 3-4.5cm (1¼-1½in)
------------------	-------------	----------------------------

ARCTIIDAE

THIS IS A LARGE family containing some 10,000 species of moths occurring worldwide, with the greatest numbers present in the tropics. Many are brightly patterned with warning colours, either because they are distasteful, or because they mimic less palatable species. The brightly striped patterns of some species have given rise to the common name of tiger

moths. Arctiidae moths have robust wings and bodies; moths belonging to the sub-family Lithosiinae tend to be generally smaller, with delicate wings and much more slender bodies.

The caterpillars of many Arctiids often feed on poisonous plants, storing the toxins in their bodies where they provide protection from predators.

Family ARCTIIDAE

Species *Apantesis virgo*

Author Linnaeus

VIRGIN TIGER-MOTH

This species can be distinguished by its large size and the presence of black spots on the hindwing. Although the hindwings and abdomen are usually red in colour, a less common yellow form also occurs.


• **EARLY STAGES** The hairy, black caterpillar is known to feed on various low-growing plants including clover (*Trifolium*), plantain (*Plantago*), lettuce (*Lactuca*), and *Chenopodium*.

• **DISTRIBUTION**

South-eastern Canada. Most of the USA, except the extreme west.



NEARCTIC



distinctive forewing pattern continues on thorax

characteristic cream border to forewing

brightly coloured wings warn that this moth is distasteful

Time of Flight

Habitat

Wingspan 4.5-7cm (1½-2½in)

Family ARCTIIDAE

Species *Amsacta morganiata*

Author Donovan

DONOVAN'S AMSACTA

This beautiful, white moth is very variable. Moths from northern regions of Australia have fewer black markings, while those in the south often have extensive black markings and a pinkish white ground colour.


• **EARLY STAGES** The caterpillar is black with tufts of long hair. It feeds on capeweed (*Arctotheca calendula*) and other plants.

• **DISTRIBUTION**

North-western Australia to South Australia.



INDO-AUSTRALIAN



characteristic red leading edge to forewing

black-banded abdomen

long, slender forewings with pointed tips

Time of Flight

Habitat

Wingspan 4-4.5cm (1½-1¾in)

Family ARCTIIDAE

Species *Arctia caja*

Author Linnaeus


GARDEN TIGER

With its distinctive brown and white forewings and bluish black-spotted, red hindwings, this handsome moth is unmistakable. The markings on both fore- and hindwings are very variable. Rare yellow forms also occur.

• **EARLY STAGES** The black woolly bear caterpillar has rusty red hairs along the lower parts of the body and around the first body segments. It feeds on the foliage of a wide range of low-growing plants and broad-leaved shrubs.

• **DISTRIBUTION** Europe, across temperate Asia to Japan. Occurs less frequently in Canada and the northern USA.

CATERPILLAR OF ARCTIA CAJA




red-colored body hair



furry, brown thorax

black-ringed greyish markings

pale orange hindwing fringes



HOI ARCTIC

Time of Flight

Habitat

Wingspan 5-7.5 cm (2-3 in)

Family ARCTIIDAE

Species *Estigmene acrea*

Author Drury

ACREA MOTH

This common species can be recognized by the black-spotted forewings, which are tinged with pale yellow in the male. The hindwings each bear three or four black spots. The ground colour of the male hindwings is orange-yellow, while that of the female is white.

• **EARLY STAGES** The caterpillar is mottled light and dark brown and covered with long, brown hairs. It feeds on foliage of various low-growing plants and broad-leaved trees, and is often a pest of cabbage (*Brassica oleracea*), and clover (*Trifolium*).

• **DISTRIBUTION** Widespread in south-eastern Canada, and eastern parts of the USA.



♂

furry white thorax

+



♀

distinctive black spotted, orange abdomen

faint broken, black line around hindwing margin



NEARCTIC

Time of Flight

Habitat

Wingspan 4.5-7 cm (1 1/4-2 1/2 in)

Family ARCTIIDAE

Species *Epantheria scribonia*

Aut. id: Ser

GIANT LEOPARD MOTH

This striking species can be recognized quite easily by the distinctive pattern of blackish brown to bluish black, ring-like markings on the forewing.

• **EARLY STAGES** The hairy caterpillar is black with crimson rings between the segments, which are revealed when it curls up in a defensive position. It feeds on a many plants, including cherry (*Prunus*), and banana (*Musa*).

• **DISTRIBUTION** South-eastern Canada through eastern USA to Mexico. Common in the southern part of its range.



NEARCTIC

Time of Flight ☾

Habitat 🌿 🌳 🏡

Wingspan 6-9cm (2 1/2-3 1/2 in)

Family ARCTIIDAE

Species *Eupseudosoma nivalum*

Author Sepp

SNOWY EUPSEUDOSOMA


In a largely tropical genus moths, the snowy eupseudosoma is the only species to reach North America. This is a pretty snowy white species, distinguished by its striking red abdomen, which is white on the underside.

• **EARLY STAGES** The pale yellow, hairy caterpillar feeds on guava (*Psidium*) as well as *Eugenia* species.

• **DISTRIBUTION** Tropical South and Central America to the southern USA.



NEOTROPICAL



Time of Flight ☾

Habitat 🌿 🌳 🏡

Wingspan 3-4cm (1 1/4-1 1/2 in)

Family ARCTIIDAE

Species *Hyphantria cunea*

Author Drury


FALL WEBWORM MOTH

This moth is sometimes marked with greyish brown spots on the forewing and black spots on the hindwing. The degree of spotting can vary.


• **EARLY STAGES** The caterpillar is green with black spots, and is covered with long, white hair. It feeds on the foliage of various broad-leaved trees and shrubs.

• **DISTRIBUTION**

Southern Canada and the USA. Also in central Europe and Japan.



HOLARCTIC



Time of Flight ☾

Habitat 🌳

Wingspan 2.5–4 cm (1–1½ in)

Family ARCTIIDAE

Species *Lophocampa caryae*

Author H. L. Lins


HICKORY TUSsock Moth

Also known as the hickory tiger moth, this is a distinctive species with golden-brown forewings patterned with translucent, white spots.

• **EARLY STAGES** The caterpillar is covered with pale grey hairs with a few black tufts on the back. It feeds on the foliage of hickory (*Carya*), walnut (*Juglans*), and other broad-leaved trees.

• **DISTRIBUTION**

Southern Canada through the USA to Central America.

NEARCTIC
NEOTROPICAL

Time of Flight ☾

Habitat 🌳

Wingspan 4–5.5 cm (1½–2¼ in)

Family ACTINIDAE

Species *Paraclet latouchei*

Author Barnes

WATER TIGER

Males of this brown moth tend to have darker brown forewings and pale hindwings; the larger females have yellow-brown fore- and hindwings.


• **EARLY STAGES** The hairy, black, woolly bear caterpillar is capable of living underwater and can swim with ease. Air is trapped between the dense body hairs allowing it to remain underwater. It feeds on water plants of the genus *Najas*.

• **DISTRIBUTION**

This species is found in tropical South America.



NEOTROPICAL



Time of Flight ☾

Habitat 🌿

Wingspan 3–4.5 cm (1¼–1¾ in)

Family ARCTIIDAE

Species *Premnotis semirufa*

Author Walker

SEMI-ROUFUS TIGER

A pretty moth, it has yellow-brown patterned forewings. Its hindwings and body are flushed with pink as a warning that it is distasteful.


• **EARLY STAGES** The hairy caterpillar lives around the rubber tree (*Hevea brasiliensis*). It is notorious among rubber tappers as its body hairs are highly irritant if touched.

• **DISTRIBUTION**

Occurs in tropical South America.



NEOTROPICAL



Time of Flight ☾

Habitat 🌿

Wingspan 4-6 cm (1½-2 in)

Family ARCTIIDAE

Species *Proagrotis fuliginosa*

Author Linnaeus

RUBY TIGER


The ruby tiger is recognizable by its translucent, brownish-red forewings and pink or red hindwings with large, black, marginal spots. The forewings can be pale reddish or greyish brown.

• **EARLY STAGES** The brown caterpillar is covered with reddish or yellowish-brown hairs. It feeds on a wide range of low-growing plants,


including docks (*Rumex*).

• **DISTRIBUTION**

Europe to North Africa and Japan; Canada and northern USA.



HOLARCTIC



Time of Flight ☾

Habitat 🌿

Wingspan 3-4 cm (1¼-1½ in)

Family ARCTIIDAE

Species *Rhodogastria crokeri*

Author Macleay

CROKER'S FROTHER

These moths have elongate, brown forewings with a translucent, pale central region and a yellowish-white base. The hindwings are yellowish-white.


• **EARLY STAGES** Little is known of this moth. Some related species are known to feed on the native vine *Gymnanthera nitida*, others feed on plants containing heart poisons, so it may be poisonous.

• **DISTRIBUTION**

North-western Australia to Queensland and northern NSW.



INDO-AUSTRALIAN



Time of Flight ☾

Habitat 🌿

Wingspan 5-7 cm (2½-2¾ in)

Family ARCTIIDAE	Species <i>Pyrrharctia isabella</i>	Author Stål.
------------------	-------------------------------------	--------------

ISABELLA TIGER MOTII


The forewings of this common moth vary in colour from pale orange-yellow to orange-brown, and are sometimes patterned with faint brown lines. There are a few black spots along the outer margins, particularly towards the wing-tips.

• **EARLY STAGES** The hairy caterpillar is black at either end with a broad, central band of reddish brown. It is known to feed on the foliage of a wide range of low-growing plants and broad-leaved trees.

• **DISTRIBUTION** Widespread in Canada and the USA.



NEARCTIC



Time of Flight ☾	Habitat 🌿 🌳 🌲	Wingspan 1.5–7cm (1½–2½in)
------------------	---------------	----------------------------

Family ARCTIIDAE	Species <i>Spilosoma lubricipeda</i>	Author Linnaeus
------------------	--------------------------------------	-----------------

WHITE ERMINE

The common name accurately describes the forewings of this moth, which are white to yellowish white, and variably spotted with small black dots. In some varieties the black markings are much larger and more extensive, joining together to form streaks. Others have no black markings on the forewing at all. The hindwings are white with a few black spots.


• **EARLY STAGES** The hairy, greyish brown caterpillar can be recognized by the presence of an orange or red line along the back. It feeds on the foliage of a wide range of low growing plants. It can move very rapidly, which is reflected in the scientific name *lubricipeda*, meaning fleet footed.

• **DISTRIBUTION** Europe, extending across Asia to Japan.



PALAEARCTIC

CATERPILLAR OF
SPILOSOMA LUBRICIPEDA



Time of Flight ☾	Habitat 🌿 🌳	Wingspan 3–5cm (1½–2in)
------------------	-------------	-------------------------

Family ARCTIIDAE

Species *Ieracotona enprepia*

Author Hampson

VEINED TIGER


This moth has cream-coloured forewings veined with brown. The transverse, brown bands are variable in width and are sometimes entirely absent. The hindwings are dark pink.

• **EARLY STAGES** Little is known of this species, except that it feeds on tobacco (*Nicotiana tubacum*).

• **DISTRIBUTION** Angola and Zimbabwe to Zambia and across to Mozambique



AFROTROPICAL



Time of Flight ☾

Habitat 🌿 🌳

Wingspan 4–5.5 cm (1½–2¼ in)

Family ARCTIIDAE

Species *Utetheisa pulchella*

Author Linnaeus


CRIMSON SPECKLED

This beautiful and distinctive moth has yellowish white forewings patterned with black and red markings. The hindwing is white with irregular, black margins.


• **EARLY STAGES** The hairy, grey caterpillar is marked with transverse, orange bars and longitudinal, white lines.

It feeds on borage (*Borago officinalis*) and forget-me-not (*Myosotis*).

• **DISTRIBUTION** Mediterranean Europe to Africa and Middle East.



PALAEARCTIC



Time of Flight ☼

Habitat 🌿 🌳

Wingspan 3–4 cm (1¼–1½ in)

Family ARCTIIDAE

Species *Utetheisa armatrix*

Author Linnaeus

ORNATE MOTH


This attractive species can be distinguished from the closely related bella moth (*Utetheisa bella*) by the mainly white ground colour of the hindwings. The extent of pink is very variable on the forewing.

• **EARLY STAGES** The hairy caterpillar feeds on the foliage of plants of the pea family (Leguminosae).

• **DISTRIBUTION** Tropical South and Central America, as far north as Florida.



NEOTROPICAL



Time of Flight ☼


Habitat 🌿 🌳

Wingspan 3–4.5 cm (1¼–1¾ in)

Family	ARCTIIDAE	Species	<i>Termessa shepherdis</i>	Author	Newman
SHEPERD'S FOOTMAN This attractively marked moth belongs to a genus of twelve species peculiar to Australia. Most species are boldly marked with patterns of orange and black. The hindwings are a deeper orange-yellow with distinctive black markings on the margins. <ul style="list-style-type: none"> • EARLY STAGES Little seems to be known about this moth. • DISTRIBUTION Occurs in NSW and Victoria in Australia. 					
Time of Flight		Habitat		Wingspan 3-4 cm (1 1/4-1 1/2 in)	




INDO-AUSTRALIAN




black marking on hindwing sometimes lacks curved "tail"


Family	ARCTIIDAE	Species	<i>Polia complana</i>	Author	Linnæus
SCARCE FOOTMAN This is one of a group of footman moths with narrow, shiny, grey forewings with a bold, golden yellow stripe along the leading edge. Scarce footman moths visit flowers of thistles, and related plants, at dusk. <ul style="list-style-type: none"> • EARLY STAGES The hairy, grey caterpillar has rows of alternate orange and white spots along the back, and a yellow stripe along the sides. It feeds on various lichens. • DISTRIBUTION Europe, across temperate Asia to Siberia, and North America. 					
Time of Flight		Habitat		Wingspan 3-4 cm (1 1/4-1 1/2 in)	



HOL ARCTIC



Family	ARCTIIDAE	Species	<i>Lithosta quadra</i>	Author	Linnæus
FOUR-SPOTTED FOOTMAN It is the female of this relatively large footman moth that earns the name, four spotted. Each forewing has two black spots, which vary in size. The forewing of the male is grey, shading to a darker orange-yellow at the base, and over the thorax. <ul style="list-style-type: none"> • EARLY STAGES The caterpillar has a yellowish head, with red spots. It feeds on <i>Peltigera canina</i> and other lichens. • DISTRIBUTION Widespread in Europe, extending to temperate Asia and to Japan. 					
Time of Flight		Habitat		Wingspan 2-5 cm (1 1/4-2 in)	



PALAEARCTIC



Family ARCTIIDAE

Species *Amphicallia bellatrix*


Author Dalman

BEAUTIFUL TIGER

The forewings and hindwings of this moth are bright orange with blue-black, irregular stripes which are outlined with a thin black outline

• **EARLY STAGES** The red-headed caterpillar is white with grey hairs and black, transverse bands. It feeds on *Crotalaria* and plants of the pea family (Leguminosae).

• **DISTRIBUTION** Found from Kenya to Zambia, Mozambique and the Cape Province



AFROTROPICAL



forewing pattern extends onto
• thorax

abdomen
characteristically spotted

Time of Flight ☀

Habitat 🌿 🌳

Wingspan 5.2cm (2-2.1in)

Family ARCTIIDAE

Species *Nyctemera unica*

Author White

AUSTRALIAN MAGPIE MOTH

This is an easily recognized species, having black-brown wings with yellowish white spots. The black and orange ringed abdomen suggests that this moth is distasteful. The sexes are similar, but females tend to be smaller than males.

• **EARLY STAGES** The hairy, black caterpillar of this species has red stripes along the back and sides. It feeds on the foliage of *Senebjo*.

• **DISTRIBUTION** Widespread throughout most of Australia



INDO-AUSTRALIAN



strongly
leathery
antennae

distinctive,
orange fringes

Time of Flight ☀

Habitat 🌿 🌳

Wingspan 4.5cm (1.7-1.4in)

Family ARCTIIDAE

Species *Catimorpha downalis*


Author Linnaeus

SCARLET TIGER

This moth has greenish black forewings, spotted with yellowish white, but sometimes these spots are greatly reduced in size.

• **EARLY STAGES** The caterpillar is black with tufts of black and grey hairs, and broken bands of yellowish white along the back and sides. It feeds on comfrey (*Symphytum officinale*), dock (*Rumex*) and other plants.

• **DISTRIBUTION** Found throughout Europe, and eastwards into temperate Asia.



PALEARCTIC





forewing pattern continues across
thorax



abdomen is red with
black central stripe



Time of Flight ☀

Habitat 🌿 🌳

Wingspan 4.5-5.5cm (1.7-2.1in)

Family ARCTIIDAE	Species <i>Euplagia quadripunctaria</i>	Auth: Podis
<h3>JERSEY TIGER</h3> <p>This species has black stripes on yellowish white forewings. The black-spotted hindwings are usually red, but a yellow variety also exists.</p> <ul style="list-style-type: none">• EARLY STAGES The caterpillar is dark brown, covered with short yellow-brown hair with yellow bands on its back and sides. It feeds on the foliage of a range of low-growing plants.• DISTRIBUTION Europe, extending across temperate Asia.		
<div><p>PALAEARCTIC</p></div> <div><p>♀</p></div>		
Time of Flight ☾ ☀	Habitat 🌿 🌳 🌲	Wingspan 5–6cm (2–2½in)

Family ARCTIIDAE	Species <i>Tyria jacobaeae</i>	Author Linnaeus
<h3>CINNABAR MOTH</h3> <p>This day-flying moth is often mistaken for a butterfly. It is easily recognized by its forewings, which are distinctively streaked and spotted with red. The hindwings are red, though yellow forms occur occasionally.</p> <ul style="list-style-type: none">• EARLY STAGES The orange-yellow caterpillar is boldly ringed with black and feeds openly on ragwort and groundsel (<i>Senecio</i>).• DISTRIBUTION Widespread in Europe and the British Isles.		
<div><p>PALAEARCTIC</p></div> <div><p>♀</p></div>		
Time of Flight ☉	Habitat 🌿 🌳	Wingspan 3–4.5cm (1¼–1½in)

Family ARCTIIDAE	Species <i>Antichloris vindex</i>	Author Druce
<h3>BANANA MOTH</h3> <p>This unusual moth has slender, pointed forewings that are metallic blue-green or black. In many specimens, two small tufts of red, hair-like scales are visible behind the head, indicating that it is a poisonous species.</p> <ul style="list-style-type: none">• EARLY STAGES The caterpillar is covered with pale yellow hairs. It is known to feed on banana foliage (<i>Musa</i>) and is regarded as a pest.• DISTRIBUTION Found in South and Central America.		
<div><p>NEOTROPICAL</p></div> <div><p>♂</p></div>		
Time of Flight ☀	Habitat 🌿	Wingspan 3–4cm (1¼–1½in)

Family ARCTIIDAE

Species *Ctenucha virginica*

Author Esper

VIRGINIAN CTENUCHA

The most distinctive feature of this dark greyish brown moth is its brilliant, metallic blue androgen. When feeding from flowers, the Virginian ctenucha resembles a wasp.

• **EARLY STAGES** The variable, grey caterpillar is covered with yellow and black hairs. It feeds mainly on grasses and sedges.

• **DISTRIBUTION** Canada and northern parts of the USA.



NEARCTIC

metallic blue runs onto forewing base

bright orange head



wings fringed with white

Time of Flight ☾ ☉

Habitat ♂ ♂

Wingspan 4-5cm (1 1/2-2in)

Family ARCTIIDAE

Species *Euchromia lutea*


Author Fabricius

THE BASKER

The wings of this beautiful moth are black with distinctive window-like patches of pale orange-yellow and white. The forewings are marked with small, central flashes of metallic-blue, and the body is ringed with vivid colours.

• **EARLY STAGES** Little is known about this common moth, but the caterpillars are believed to feed on plants of the family Convolvulaceae.

• **DISTRIBUTION** West Africa and the Congo Basin.



AFROTROPICAL

head has a blue spot and an orange-red collar



body is ringed with brilliant orange, black, red, white, and dark metallic blue

Time of Flight ☉

Habitat ♂ ♂

Wingspan 4-5cm (1 1/2-2in)

Family ARCTIIDAE

Species *Syntomis plagiata*


Author Linnaeus

NINE-SPOTTED MOTTH

This blue-black moth has white spots on the fore and hindwings. It is also known as the yellow-bellied burnet because of the broad, yellow band on the abdomen; it does not belong to the same family as other burnet moths (see Zygaenidae, pp. 288-290).

• **EARLY STAGES** The hairy, grey caterpillar is known to feed on various low-growing plants.

• **DISTRIBUTION** Central and southern Europe, extending to central Asia.



PALAEARCTIC

antennae are white at the tips



sex spots on forewing

yellow marking at back of thorax

Time of Flight ☉

Habitat ♂ ♂

Wingspan 3-4cm (1 1/4-1 1/2in)

CASTNIIDAE

THIS IS A RELATIVELY small family of some 200 species of tropical moth occurring mainly in South and Central America. They are generally medium to large, robust, day-flying moths that are often mistaken for butterflies. The forewings are usually dull in colour and provide camouflage when the moths are at rest, but the hindwings are sometimes brilliantly

coloured. These bright colours are revealed quite suddenly, with any wing movement if the moth is disturbed, and can startle potential predators, allowing the moth to make an escape.

The caterpillars of Castniid moths are mainly root and stem borers. They feed while they are concealed within the actual plants.

Family	CASTNIIDAE	Species	<i>Castnia licus</i>	Author	Fabricius
--------	------------	---------	----------------------	--------	-----------

GIANT SUGARCANE-BORER

This distinctive and very butterfly like moth can be recognized by the yellowish white, diagonal bands on the brownish black forewings, although other forewing markings are rather variable. The hindwings are banded with white and have a series of square, red spots along the margin.

- **EARLY STAGES** The white, grub-like caterpillar bores into stems of sugarcane (*Saccharum officinarum*). Discovered to be a sugarcane pest at the turn of the century, it has subsequently also become a pest of cultivated bananas (*Musa*), and probably feeds on the roots of related native plants in the wild.
- **DISTRIBUTION** Widespread in tropical South and Central America, particularly where sugarcane and bananas are grown.




NEOTROPICS

distinctive boring caterpillar



CATERPILLAR OF
CASTNIA LICUS

antennae are thickened and hooked at the tips



♀

large wings make this moth a powerful flier

Time of Flight		Habitat		Wingspan	6-10cm (2 1/2-4in)
----------------	--	---------	--	----------	--------------------

Family CASTNIIDAE

Species *Divana diva*

Author B. H. C.

DIVA MOTH

This species is confined to Central and South America and is notable for its brilliantly coloured hindwings. The forewings of this moth are well camouflaged with a pattern of dark yellowish brown with white spots, resembling a dead leaf. The hindwings are an excellent example of flash coloration with deep, metallic violet blue, bordered with black and orange-red.


• **EARLY STAGES** Nothing appears to be known about the caterpillar or its foodplants.

• **DISTRIBUTION** Wide spread in tropical South and Central America.



NEOTROPICAL

characteristic,
slightly curved
wing-tips •



Time of Flight ☉

• habitat ☿

Wingspan 6–9.5 cm (2 1/4–3 1/4 in)

Family CASTNIIDAE

Species *Synemon parthenoides*

Author J. C. Jer.

ORANGE-SPOTTED CASTNID

This is one of a number of species belonging to this solely Australian genus of Castnid moths. The forewings have a dull pattern of greyish brown and white, while the hindwings are brownish black, spotted with orange-yellow.

• **EARLY STAGES** The pinkish white caterpillar feeds in tussocks of sedge (*Lepidosperma carphoides*).

• **DISTRIBUTION**

This species occurs from Victoria to South Australia.



INDO-AUSTRALIAN

distinctive clubbed antennae
• with sharply pointed tips



• mottled hindwing fringes

Time of Flight ☉



• Habitat ☿



Wingspan 3–4.5 cm (1 1/4–1 3/4 in)

SESIIDAE

THIS worldwide family of over 1,000 species is notable for containing some of the best wasp mimics among all insects. Most of these small- to medium-sized moths have areas of the wings that are lacking in scales, hence the common name clearwings that is applied to the family as a whole. The hind legs are usually clothed with dense, long hairs. These

moths are not only superb wasp mimics in appearance, but also in behaviour, some even producing a buzzing sound when in flight. They are mostly day-flying species and frequently visit flowers. The caterpillars of clearwing moths mostly tunnel in stems of trees, shrubs and other plants, and a number are regarded as pests.

Family Sesiidae	Species <i>Sesia apiformis</i>	Author Clerck
<h3>HORNET MOTH</h3> <p>One of the most convincing of the hornet mimics, this moth is very distinctively banded with black and yellow on the body. The wings are virtually devoid of scales except for the yellowish brown borders. This moth can easily be distinguished by its yellow head.</p> <ul style="list-style-type: none">• EARLY STAGES The yellowish white grub-like caterpillars are known to bore close to or below ground level in the trunks and upper roots of poplars (<i>Populus</i>), and willows (<i>Salix</i>).• DISTRIBUTION Europe, extending eastwards into temperate Asia. Also in North America, where it has been accidentally introduced. <div><p>HOLARCTIC</p></div> <div><p>dark wing veins show clearly</p><p>♀</p><p>large yellow-brown hind legs</p></div>		
Time of Flight ☀	Habitat 🌳 🌿	Wingspan 3-4.5cm (1 1/4-1 1/2in)

Family Sesiidae	Species <i>Albana oberthuri</i>	Author Le Cerf
<h3>GOLDEN CLEARWING</h3> <p>This beautiful little moth is one of only fourteen species of this family known to occur in Australia. It is easily recognized by its brilliant golden forewings margined with black and by the gold bands and tail-tuft on the abdomen. Like most other members of this group it flies rapidly in bright sunlight. Males lack the orange forewing scales of the females.</p> <ul style="list-style-type: none">• EARLY STAGES Very little is known about the biology of this moth, and its caterpillar has not been described.• DISTRIBUTION Occurs in Northern Territory, Australia <div><p>INDO-AUSTRALIAN</p></div> <div><p>golden-yellow head and antennae</p><p>♀</p><p>distinctive yellow bar on clear hindwing</p></div>		
Time of flight ☀	Habitat 🌳	Wingspan 2.5-3cm (1-1 1/4in)

LIMACODIDAE

THIS is a family of about 1,000 species occurring worldwide, but most commonly found in the tropics. They are small- to medium sized and have reduced mouthparts, and rather rounded wings. Some moths are bright green or yellow but most have fairly dull colours and simple patterns. The name Limacodidae, meaning slug-like, derives from the

caterpillars of this family. These caterpillars, which look like slugs and move like them, are often very brightly coloured, indicating that they are poisonous. Many of the Limacodid caterpillars have stinging hairs that can cause a very painful reaction and so are known as nettle caterpillars. A number of species feed on cultivated crops and are often regarded as pests.

Family Limacodidae

Species *Silene strimmar*


Author C. Menes

SADDLE-BACK MOTTH


The forewings of this moth are deep reddish brown with dark purplish grey and black markings. The hindwings are paler greyish brown. The sexes are similar, but females are larger.

• **EARLY STAGES** The common name of the moth refers to the caterpillar, which is purplish brown with a large central saddle of bright green, edged with white. In the middle of the saddle is a white-edged, dark brown oval marking. At either end of the body is a prominent pair of poisonous horns. The caterpillars are known to feed on the foliage of a wide range of plants.

• **DISTRIBUTION** This moth is widespread throughout eastern and southern areas of the USA.



NEARCTIC



Time of flight ☾

Habitat ●

Wingspan 2.5-4cm (1-1.5in)

Family Limacodidae

Species *Apoda limacodes*


Author Hufnagel

THE FESTOON

Males of this species are dark yellowish brown with dark brown hindwings while females are predominantly yellow with brown markings. Although mainly nocturnal they will fly around the tops of oak trees in daylight.

• **EARLY STAGES** The unusual flattened caterpillar is pale green with two yellow longitudinal ridges along the back, that are spotted with pinkish red. Festoon caterpillars feed on the foliage of oak (*Quercus*).

• **DISTRIBUTION** Widely distributed in southern and central Europe and also occurs in southern parts of the British Isles.



PALAEARCTIC



Time of flight ☾ ☼

Habitat ●

Wingspan 2.5-3cm (1-1.5in)

ZYGAENIDAE

THIS WORLDWIDE FAMILY of some 800 species of small- to medium-sized moth is one of the most distinctive groups of all. Most are day-flying and many are brightly coloured, indicating that they are poisonous.

Several of the predominantly red species of the genus *Zygaena* that occur in Europe are known as burnets, while

green species of the genus *Adscita* are known as foresters. Most Zygaenid moths have well-developed tongues, and the antennae are usually thickened towards the tips. While most have normally developed wings, the hindwings of one group, (*Himantopterus* see p. 290), are reduced to slender filaments. The poisonous caterpillars are stout and slug-like.

Family ZYGAENIDAE	Species <i>Zygaena ephialtes</i>	Author Linnæus
-------------------	----------------------------------	----------------

VARIABLE BURNET MOTH

There are many different colour forms and subspecies of this moth. The forewings are variably spotted with white, red, or yellow.

- **EARLY STAGES** The caterpillar is yellow or greenish yellow, with black spots and a line down its back. It feeds on crown vetch (*Coronilla varia*).
- **DISTRIBUTION** Central and southern Europe. Also recorded in Turkey.

♂

♂

distinctive band on abdomen

white spotting on forewings

colour of abdomen reflected on forewing

black & black forewings

PALEARCTIC

Time of Flight ☼	Habitat ♂♂ ♀♀	Wingspan 3-4cm (1¼-1½in)
------------------	---------------	--------------------------

Family ZYGAENIDAE	Species <i>Arminera erythrops</i>	Author Wallengren
-------------------	-----------------------------------	-------------------

FIRE GRID BURNET MOTH

The common name of this distinctive moth refers to the forewing pattern of black-edged, red bands on a metallic blue-green ground colour. The hindwing is pinkish red with a broad, marginal band of black. Males have black hairs covering the head.

- **EARLY STAGES** Very little is recorded or known about the African Zygaenid moths or their caterpillars.
- **DISTRIBUTION** Zimbabwe and Malawi to Mozambique and South Africa.

♀

♂

red hairs covering head of female

contrasting, plain hindwings

bright red abdomen

AFROTROPICAL

Time of Flight ☼	Habitat ♂♂ ♀♀	Wingspan 2.5-3cm (1-1¼in)
------------------	---------------	---------------------------

Family ZYGAEINIDAE

Species *Zygaena celtica*

Author J. E. Villers


PROVENCE BURNET MOTH

The Provence burnet is distinguished by its small size and an all-white, elongate, spot on the outer edge of the forewing. The tip of the abdomen is coloured with a broad band of red.


• **EARLY STAGES** The caterpillar is light green, spotted with yellow, and has black dots on its sides. It feeds on plants of the pea family.

• **DISTRIBUTION**

Southern France and Spain. Similar species occur in southern and eastern Europe.



PALEARCTIC



Time of Flight ☉

Habitat 🌿 🌳

Wingspan 3-4cm (1 1/4 in)

Family ZYGAEINIDAE

Species *Zygaena filipendulae*

Author Linnaeus


SIX-SPOT BURNET

As its common name suggests, this species is distinguished by having six large, red spots on each greenish black forewing.


• **EARLY STAGES** The yellowish green caterpillar has yellow and black spots. It feeds on bird's-foot trefoil (*Lotus corniculatus*) and related plants of the pea family (Leguminosae).

• **DISTRIBUTION**

Widespread and common throughout Europe.



PALEARCTIC



Time of Flight ☉

Habitat 🌿 🌳

Wingspan 2.5-4cm (1-1 1/2 in)

Family ZYGAEINIDAE

Species *Adicta statius*

Author Linnaeus


THE FORESTER

This is one of a group of species with metallic-green wings. Several other species are similar, but are distinguishable by small differences in the structure of the wings and antennae.


• **EARLY STAGES** The caterpillar is pale yellow or greenish white, suffused with pinkish brown on the sides, and has brown, hairy warts. It feeds on sorrel (*Rumex*).

• **DISTRIBUTION**

Europe, extending into temperate Asia.





PALEARCTIC







Time of Flight ☉

Habitat 🌿 🌳

Wingspan 2.5-3cm (1 1/4 in)

Family Zygaenidae	Species <i>Harrisina americana</i>	Author Guérin
<div><div><div><div><h3>EASTERN GRAPELEAF SKELETONIZER</h3><p>This unusual little moth is characterized by its slender, black wings and long, black body. This species has a distinctive red or orange collar behind the head.</p><ul style="list-style-type: none">• EARLY STAGES The caterpillar is yellowish white with black spots that are covered with stinging hairs. The caterpillar feeds on grapevine (<i>Vitis</i>) and Virginia creeper (<i>Parthenocissus</i>).• DISTRIBUTION Widespread in the eastern U.S.A.</div><div><p>NEARCTIC</p></div><div><p>♂</p><p>feathered antennae of male</p><p>tufted tip to the abdomen</p><p>characteristic, small hindwings</p></div></div></div></div>		
Time of Flight ☀	Habitat 🌿	Wingspan 2–3cm (4–1 1/4 in)

Family Zygaenidae	Species <i>Campylotes de godini</i>	Author Oberthür
<div><div><div><div><h3>FIERY CAMPYLOTES</h3><p>This handsome and distinctive moth belongs to a genus of about fifteen species, all brightly coloured with black and red as a warning that they are distasteful and probably poisonous.</p><ul style="list-style-type: none">• EARLY STAGES Nothing is known about the caterpillar or its foodplants.• DISTRIBUTION This species can be found from northern India and Tibet to South China and throughout Borneo.</div><div><p>INDO-AUSTRALIAN</p></div><div><p>♂</p><p>long, almost rectangular forewings</p><p>stender, slightly feathered antennae</p></div></div></div></div>		
Time of Flight ☀	Habitat 🌿	Wingspan 5.5–7cm (2 1/4–2 1/2 in)

Family Zygaenidae	Species <i>Himantopterus dohertyi</i>	Author Flörke
<div><div><div><div><h3>DOHERTY'S LONGTAIL</h3><p>This unusual little moth belongs to a small genus of south-east Asian species that are characterized by their long, streamer-like hindwings. This species has black forewings, its hindwings have strange, black, triangular, flag-like extremities. If disturbed when at rest, the moths drop to the ground and feign death as a defence strategy. These moths have a slow flight.</p><ul style="list-style-type: none">• EARLY STAGES The caterpillars live in the nests of termites.• DISTRIBUTION Can be found throughout India and Malaysia.</div><div><p>INDO-AUSTRALIAN</p></div><div><p>♂</p><p>strongly feathered antennae</p><p>hindwings have slender orange bases</p><p>orange tip to abdomen</p></div></div></div></div>		
Time of Flight ☀	Habitat 🌿	Wingspan 2–2.5cm (3/4–1 in)

COSSIDAE

THIS IS A WORLDWIDE FAMILY of some 500 species of medium-sized to very large moth. They are usually rather dull in colour, ranging from grey and brown to white, and are patterned with contrasting streaks or spots. The caterpillars feed mainly on

wood, boring holes in the branches and trunks of trees, and are therefore commonly known as carpenterworms.

Because of the low nutritional value of their food, some species take several years to complete their development.

Family COSSIDAE

Species *Xyleutes arrix*

Author Linnaeus


ASIAN CARPENTER MOTH

This large and robust moth has a very small head with prominent eyes. The finely mottled, greyish brown markings on the wings provide good camouflage, the paler markings resembling patches of lichen. Females of the Asian carpenter moth have a long, egg-laying tube that can extend to 1cm (½in) and may be mistaken for a sting.

• **EARLY STAGES** Little seems to be known of the biology of this common moth, but a closely related species, *Xyleutes leuconotus*, has a white coloured caterpillar that bores in the wood of *Sesbania grandiflora*.


• **DISTRIBUTION**

Northern India to
Malaysia and Papua
New Guinea



robust wood-eating caterpillar

CATERPILLAR OF
XYLEUTES SPECIES



antennae of the male are
feathered at the base


curved hind
margin to
forewing

abdomen of both sexes
is densely covered in
black felt-like hair

brown and white
banded abdomen

white
marking
at back
of thorax

pointed
tip to
hindwing



INDO-AUSTRALIAN

Time of Flight ☾

Habitat 🌳

Wingspan 9–22cm (3½–8¾in)

Family COSSIDAE

Species *Coisys coisys*

Author Linnaeus

GOAT MOTH


This robust species has pale grey forewings that are finely networked with dark brown lines. The hindwings are dark grey with less distinct markings.

• **EARLY STAGES** The caterpillar is coloured yellowish white, suffused with purplish red on the back.


It bores in the wood of broad leaved trees.

• **DISTRIBUTION**

Can be found from Europe to North Africa and western Asia.



PALAARCTIC



• pale head and collar

• distinctively banded abdomen

Time of Flight ☾

Habitat ●

Wingspan 7-9.5 cm (2 7/8-3 7/8")

Family COSSIDAE

Species *Pronoxystus retinoides*

Author Peck

CARPENTERWORM MOTTH

Males have slender, pointed wings that are slightly translucent pale grey with darker mottling. The triangular hindwings are yellow-coloured with a black border.


• **EARLY STAGES** The caterpillars bore into the wood of oaks (*Quercus*), elms (*Ulmus*), and other hardwoods, taking up to four years to develop.

• **DISTRIBUTION**

Widespread throughout the USA and southern Canada.



NEARCTIC



thick, feathered
• antennae of male

dark brown
abdomen tapers to
• a point in male

Time of Flight ☾

Habitat ●

Wingspan 4.5-8 cm (1 7/8-3 1/4")

Family COSSIDAE

Species *Zenzera pyralis*

Author Linnaeus

LEOPARD MOTTH


Also known as the wood leopard, this striking, white moth has the forewings boldly spotted with black. The larger females have long egg-laying tubes that can be mistaken for stings.

• **EARLY STAGES** The yellowish white caterpillars of this species bore into the branches and trunks of broad-leaved trees, taking from two to three years to complete their growth.

• **DISTRIBUTION** Europe, to North Africa, temperate Asia and North America.



HOLARCTIC



six large, black spots
on white thorax •

slender antennae
• of female moth

hindwings
are rather
translucent

Time of Flight ☾

Habitat ●

Wingspan 4.5-7.5 cm (1 7/8-3 in)

Family COSSIDAE

Species *Acacia carterii*

Author Hermann Schäffer

ACACIA CARPENTER MOTH


This is one of the most attractive and distinctive Australian carpenter moths. The forewings are grey with a fine network pattern of black and dark brown, while the hindwings are reddish brown with fine, dark brown markings. The body is banded with white.

• **EARLY STAGES** The robust, white caterpillar has a large, brown, shield-like plate on its back behind the head. It attacks acacia species.

• **DISTRIBUTION** Occurs in NSW and Queensland



INDO-AUSTRALIAN



Time of flight ☾

Habitat 🌳

Wingspan 13-21cm (5-8in)

Family COSSIDAE

Species *Acacia carterii*

Author Leppe

BOISDUVAL'S CARPENTER MOTHS

This is one of the largest moths in the family Cossidae. The forewings are uniform grey with a few short, dark streaks, while the hindwings are greyish black. The thorax is grey with a distinctive black and white oval marking on the back. The abdomen is

narrowly ringed with greyish white.

• **EARLY STAGES**


The caterpillar bores into the trunks of acacia, taking up to three years to complete its development.

• **DISTRIBUTION**

Queensland to southern NSW.



INDO-AUSTRALIAN



Time of flight ☾

Habitat 🌳

Wingspan 14-21cm (5.5-10in)

HEPIALIDAE

THIS FAMILY OF SOME 300 species of moth displays a number of primitive features that distinguish them from all other large moths. The wings lack the usual bristle-and-catch linking system and instead have a lobe on the forewing that overlaps the hindwing, thus holding them together when in flight. Another more obvious and primitive feature is that the

hindwing and forewing are usually very similar in shape and have a similar arrangement of wing veins.

Hepialid moths vary in size from small to very large. They are worldwide in distribution, and are very strongly represented in Australia where some of the largest species occur. They are generally most active at dusk.

Family	HEPIALIDAE	Species	<i>Zelotypia salicis</i>	Author	Scott
--------	------------	---------	--------------------------	--------	-------

BENT-WING GHOST MOTH

The forewings of this large and beautiful moth are intricately patterned with brown and white and have a distinct eyespot at their centres. The hindwings are orange with brown markings at the extreme tip but are otherwise quite plain. The sexes are alike. These moths are on the wing in summer.

• **EARLY STAGES** The caterpillar is yellowish brown with stout, reddish brown plates on the back immediately behind the head. Along the back is a series of yellowish white, oval markings. Caterpillars bore in the stems and branches of Sydney blue gum (*Eucalyptus saligna*) and related trees. They are sometimes pests of young trees used for paper pulp.


• **DISTRIBUTION** Occurs in eastern Australia from Queensland to NSW



INDIGENOUS AUSTRALIAN

shape of forewing
rips gives rise to the
common name

distinctive forelegs
have the appearance
of pipe-cleaners



fore- and
hindwings are
quite similar
in shape

long slender,
orange abdomen

colour of hindwings
is matched by body

small, brown
spot on elongate
hindwing tip

Time of Flight	☾	Habitat	🌳	Wingspan	19–25cm (7½–10in)
----------------	---	---------	---	----------	-------------------

Family HEPALIDAE

Species *Aenetus eximius*

Author Scott

COMMON AENETUS

There are fifteen Australian species in this genus, often called splendid ghost moths. They are remarkable not only for their large size, but for the difference between the sexes. The males of the common *Aenetus* have pale bluish green forewings and white hindwings tinged with green on the hind margin. The much larger females have rich, mottled, moss-green forewings with a diagonal line of brown-ringed, white markings. The hindwings are a pinkish red which continues onto the abdomen. The abdomen tip is coloured a vivid green.


• **EARLY STAGES** The caterpillar feeds on *Waterhousea*, eucalyptus, *Doryphora*, *Glochidion*, *Nothofagus*, and *Dodonaea* species. They bore into the stem or trunk of the plant, and tunnel down into the main root. Some of the *Aenetus* caterpillars take up to five years to complete their development.

• **DISTRIBUTION** Range extends from Queensland to Victoria and Tasmania in Australia.



100 AUSTRALIAN


male forewings are shorter and more sharply pointed at the tips than those of female



male abdomen is white with a pale green tip

brightly coloured forelegs

brown spotting on forewing edge



yellow margins to hindwings

orange colour of body matches hindwings

abdomen has a green tip

hindwings are dusky orange-red

Time of Flight ☾

Habitat 🌳 🌿

Wingspan 8–12.5cm (3 1/4–4 1/2 in)


Family	HEPIALIDAE	Species	<i>Leto venus</i>	Author	Stoll
--------	------------	---------	-------------------	--------	-------

VENUS MOTH

As its common name suggests, this is probably the most beautiful of all Hepialid moths, with its rich orange-brown forewings brilliantly patterned with silver spots. The hindwings are a uniform salmon-pink with slightly darker veins. Males have long, orange hairs on the underside of the wings.

• **EARLY STAGES** Little is known of the early stages of this moth and the caterpillar appears to be undescribed. It bores into the trunks of Kewboom trees and it probably feeds between the wood and the bark.

• **DISTRIBUTION** Confined to Cape Province, South Africa.



AFROTROPICAL

distinctive, triangular, silver spots along forewing margin



Time of Flight	☾	Habitat	☹	Wingspan	10-16cm (4-6 1/2 in)
----------------	---	---------	---	----------	----------------------

Family	HEPIALIDAE	Species	<i>Hepialus fusconebulosa</i>	Author	De Geer
--------	------------	---------	-------------------------------	--------	---------

MAP-WINGED SWIFT


The intricate pattern of brown and white on the forewings of this moth gives rise to its common name. It is extremely variable and one form is uniform brown with little visible pattern. The hindwings are dark brownish grey with pale fringes. The sexes are similar, but females are larger and paler with the markings less distinct.

• **EARLY STAGES** The caterpillar is yellowish white with pale yellowish brown spots. It feeds on the roots of bracken (*Pteris*) and other plants, living two years.

• **DISTRIBUTION** Occurs from Europe, including the British Isles, to temperate Asia.



PALAEARCTIC



Time of Flight	☾	Habitat	☹☹	Wingspan	3-5cm (1 1/2-2 in)
----------------	---	---------	----	----------	--------------------

Family **HEPIALIDAE**

Species *Hepialus humuli*

Author **Linnaeus**

GHOST MOTH


The silvery white males are appropriately named as they look quite ghostly when hovering over vegetation at dusk. A northern form exists in which the male wings are patterned with brown. Females are generally larger and have pale yellow forewings patterned with pink or pinkish brown.

• **EARLY STAGES** The yellowish white caterpillar has small, dark brown spots. It feeds on the roots of grasses and other plants and is sometimes an agricultural pest.

Presumably because of its burrowing habits, this species is also known as the orter.

• DISTRIBUTION

Widespread from Europe, including the British Isles to Asia.



PALAEARCTIC



Time of Flight ☾

Habitat 🌱 🌿 🍄

Wingspan 4.5–6cm (1¾–2¼in)

Family **HEPIALIDAE**

Species *Sthenopis argentea maculata*

Author **Harris**

SILVER-SPOTTED GHOST MOTH


The forewings of this moth are greyish brown with an intricate pattern of brownish white lines. Towards the base is a silver dot and outside this is a characteristic silver triangle. The sexes are similar, but males have grey hindwings whereas those of females are pale yellow. Males attract mates by flying in dancing swarms near alder groves at dusk.

• **EARLY STAGES** The caterpillar bores in the roots of alder (*Alnus*) that is partially submerged in water. It takes two years to complete its development.

• **DISTRIBUTION** Southern Canada to Minnesota and Virginia in the USA.



NEARCTIC



Time of Flight ○

Habitat 🌱 🌿 🍄

Wingspan 6–10cm (2¼–4in)

GLOSSARY

TECHNICAL EXPRESSIONS have been avoided wherever possible, but a limited use of them is unavoidable in a book of this nature. The terms listed below, many of them peculiar to butterflies and moths, are defined in

a concise manner. Some definitions have been simplified and generalised in order to avoid obscure language, and they are to be regarded as definitive for this book only. Words in bold type are explained elsewhere in the glossary.

• **ABDOMEN**

Rear part of the body behind thorax

• **CARDENOLIDE POISON**

A heart poison

• **CLASPERS**

False, sucker-like legs on the abdomen

• **COCOON**

Protective enclosure for the pupa, usually made of silk

• **EYESPOT**

Circular colour markings found on the wings

• **LUNULE**

Small, moon-like shape

• **MELANIC**

Black or dark form of species, due to increased melanin

• **MIMETIC GROUP**

Species which mimic one another to gain protection

• **PALPS**

Sensory mouthparts used for investigating food

• **SCENT SCALES**

Scales that release an aphrodisiac scent

• **SCLEPHYLL FOREST**

A forest of hard-leaved trees

• **THORAX**

Middle of the body immediately behind the head

USEFUL ADDRESSES

Butterfly Conservation

PO Box 222
Dedham
Colchester CO7 6BY
Tel: 01206 322342/323 102

**National Museums and Galleries
on Merseyside**

William Brown Street
Liverpool L3 8EN
Tel: 0151 207 0001

Worldwide Butterflies

Compton House
Sherborne, Dorset DT9 4QN
Tel: 01935 474608
www.wwb.co.uk/home.html

**Edinburgh Butterfly
and Insect World**

Dobbies Garden Centre
Lasswade nr Edinburgh
Midlothian EH18 1AZ
Tel: 0131 663 4932

Conwy Butterfly Jungle

Rodlonddeb Park
Conwy LL32 8DU
Tel: 01492 393149

www.marketsite.co.uk/uk/bfly/index.htm

London Butterfly House

Syon Park
Brentford, Middlesex
Tel: 020 8560 7272
www.butterflies.org.uk

**Booth Museum
of Natural History**

194 Dyke Road
Brighton, East Sussex BN1 5AA
Tel: 01273 292777

The Natural History Museum

Cromwell Road
London SW7 5BD
Tel: 020 7942 5000
www.nhm.a.uk/

**Stratford-Upon-Avon
Butterfly Farm**

Tramway Walk
Swan's Nest Lane
Stratford-Upon-Avon
Warwickshire CV37 7LS
Tel: 01789 299288

INDEX

A

Abraxas grossulariana 198
 Aeneas Carpenter Moth 293
Acanthobrahmaea europaea 217
Achaea junonia 259
Acherontia atropos 236
Acyra 164, 165, 166
 Acrea Moth 274
Acrantia ps. 256
 Actias 222, 223
Actinote pellene 167
 Adonis Blue 100
Adreia stictica 289
Aedia leucanthes 212
Aeneides eximius 295
 African Giant Swallowtail 150
 African Grass Blue 100
 African Leaf Butterfly 131
 African Migrant 69
 African Monarch 182
 African Moon Moth 224
 African Ringlet 178
 Afrotropical region 28
Agarista agricola 266
Aglaia arctica 141
Aglaia 222
Agrotis punctata 160
Agrotis franklini 101
Agrotis claudia 134
Agrotis cingulata 237
Agrotis diadema 94
Agrotis 252
Alantella silvestris 234
Alibonina argyrea 263
Alibonina arbutus 91
Alibonina alba 286
Alibonina xanthus 196
 Alpine Argus 93
 Alpine Skipper 39
Alsophila pomataria 192
Alysiid acromiata 266
Amathusia amethystina 152
Amantia ochrea 182
Amblyopoda asata 87
 American Copper Underwing 256
 American Moth Moth 222
Amphicallia bellatrix 281
Amphipyra pyramoides 256
Amsacta marginata 273
Anaphaeus 64
Anophe panda 251
Anorthia jutrophia 107
Anomala prunaria 198
Anomala argillacea 263
Anthea florinda 71
Antheta ocellata 213
Anthrenus polyphemus 225
Anthracinus carolinensis 73
Anthracinus laticollis 242
 Antler Moth 254
Apanteles urticae 273
Apanteles 110
 Applefly 77
Aphantopus hyperantus 166
Apoda truncatoides 287
Apodonta nana 104
 Apollo 57
Apollonia speculata 194
Aporia crataegi 66

Appas nero 62
 Apple Maggot 7
Archamia leucana 108
 Arched Hook-tip 189
Archamia infans 192
Archamia 214
 Arctic Skipper 41
Argema unicolor 224
 Argemid and Sabie 197
Argemid 111, 135
Argemid 91
Argemid 93
Argemid 258
Argemid 270
Argemid 263
 Asian Carpenter Moth 291
Asterocampa celus 111
 Atlas Moth 271
Atropa hirsuta 39
Atropa 221
 Australian Cabbage Looper 261
 Australian Magpie Moth 281
Autographa gamma 261
Autographa 270
 Azalea Hairstreak 85

B

Bacana Moth 282
 Banded Bagworm 251
 Banded King Shoemaker 119
 Banded Vapourer 270
 Banksia Moth 247
 Barm 172
Basiliscus archipus 124
 Bath White 72
Battus 55
 Beak Butterfly 145
 Beautiful Tiger 281
 Beloved Underwing 260
Bematistes aganippe 167
 Benz-wing Ghost Moth 294
 B-eckout Corner odore 144
 Big Greasy Butterfly 53
B. villosa phaeides 84
B. villosa 198
 Black Arches 271
 Black Watch 263
 Black-lined Eggar 206
 Black-tipped Moth 254
 Black-veined White 66
 Blanchard's Ideopsis 187
 Blue Admiral 139
 Blue Argus 121
 Blue Dardian 119
 Blue Morpho 148
 Blue Night Butterfly 163
 Blue Pansy 121
 Blue Swallowtail 49
 Blue Throats 103
 Blue Tanager 35
 Blue-green Reflector 142
Boronia rubra 194
 Bongo Moth 252
 Boursuval's A. muralis Moth 249
 Boursuval's Carpenter Moth 293
 Boursuval's False Actaea 140
 Boursuval's Mole 73
Buloria setae 134
Bombocypus ruficornis 205
Bombocypus 214
Brahmaea walrus 216
 Brazilian Dynastor 155
 Brazilian Morpho 147
 Brazilian Skipper 44
Bracon 111
Bracon 97
 Brimble Beauty 200
 Broad-bordered Grass Yellow 71
 Brown Argus 93
 Brown Hairstreak 88
 Brown Hooded Owl 255
 Brown Playboy 81
 Brown Siphon 136
 Brower's Moth 268
 Brown-veined White 64
 Buckeye 121
 Ruddy Lappet 205
 Buff Tip 256
Bumelia alba 231
 Burmese Lancer 107
Bursera 257
 Burling's B. 217
 butchery garden 24

C

Cabbage Moth 254
 Calhoun White 67
 Cairns Birdwing 60
 Cairns Hamadryas 179
Calophrys nuda 105
 California Dog-face 68
Caligo 156, 157
 Calico Silkmoth 226
Calliope marginata 135
Callimorpha dominica 281
Callimorpha 159
Callimorpha 268
Calliphora 90
Callisamia promethes 219
Calpodia 44
Calyptra eustrigata 264
 Cambridge Beauty 122
 camouflage 16
Cantharis despectans 290
Cantharis xanthopis 96
 Caper White 64
 Cardinal 125
 Carolina Sphinx 238
 Carpenterworm Moth 292
Carterocephalus palaemon 41
 Cassius Blue 95
Castanea rosacea 97
Cassius 294
 Castor Semi-loop Moth 259
Cataglyphis 136
 caterpillar 14
Catocala 261
Cataglyphis 139
Cataglyphis 69
 Cecropia Moth 227
 Cedar Rustic 270
Celastrina argentea 96
Cephenopygia cephus 168
Cephaotes 242
Cerapteryx graminis 254
Certeris 69
Certeris 245
Certeris 107

Charaxes 113, 116, 117
Chlorargyreus nylus 120
Chorinea breyeri 177
Chelipieris rufes 212
 Chequered Skipper 41
 Chequered Swallowtail 48
Cheritra freja 79
 Ch of Butterfly 182
Chlorus catus 247
Chlorococcyus dictyornis 193
 Christmas Butterfly 51
Chrysa 15
Chrysiridia riphearia 191
Chrysoderus subulatus 261
Chrysorhynchus sylv 84
 Cinnabar Moth 282
Citharus cemeratus 168
Citharus regius 218
 Citrus Swallowtail 51
Cissaris ardentis 242
 Claret Hawk-moth 242
 Claret Satin Moth 203
 Clearwings 266
Cleopatra 69
 Cliden Norparet 260
 Clipper 145
Cnistera albastris 250
 Cocoon Moth Bleu 157
Cochilus unicus 239
 Cockle Moth 7
Cochilus forsteri 42
Coccyzus 59, 70
Coccyzus triangularis 240
 Colanette's Variegated
 Brown 1269
Colias chryseus 72
Colobura dirce 114
Colotis daniel 73
 Colour herpetus 115
 Common 125
 Common Aeneas 295
 Common Blue 99
 Common Bluebottle 54
 Common Brown 172
 Common Cl. Owl 53
 Common Dotted Border 63
 Common Emperor 231
 Common Epione Moth 25
 Common Faun 151
 Common ... Ring Butterfly 178
 Common Glider 128
 Common Grassblue 100
 Common Glava Blue 80
 Common Imperial 79
 Common Imperial Blue 80
 Common Indian Crow 183
 Common Map 107
 Common Mechanis 180
 Common Mormon 47
 Common Morpho 149
 Common Opa 85
 Common Pierrot 97
 Common Red Flash 85
 Common Rose Swallowtail 54

Common Scorywing 45
 Common Wall Butterfly 176
 Coppery Dysphania 195
Coscinortia hermes 224
Cossus cossus 292
 Cotton Moth 263
 Cramer's Blue Morpho 150
 Cramer's Mesene 102
Cressida cressida 58
 Crimson Speckled 279
 Crimson Tip 73
 Croesus Prominent 247
 Crocker's Frother 227
 Cruiser Butterfly 128
Crypsiphona aculearia 195
Ctenucha c. exans 285
Ctenucha coccinellus 255
Cyber pomonella 7
Cyrtus curat 141
Cyrestis thyodorus 107

D

Dactylocerus sticticus 217
Danaus 182, 183, 184
Danaus hauborum 247
Danaus juno 95
Daphnis nerii 244
 Dark Calcey Butterfly 179
 Dark Chopper 206
 Dark Purple Azure 87
 Dark Sand-glass 252
Dasychira pyrosoma 269
Danaus minor 250
 Death's Head Hawk-moth 236
Deilephila elpenor 245
Delias 65
Dendrolimus pini 204
Desmoceris latex 218
Desoria antia 81
Diathra cymene 133
 Diamond-back Moth 7
Diglossa australis 205
 Dingy Skipper 43
Dione juno 161
Diphthera fellea 264
Disomphala amphimor 74
 Dove Moth 285
Drepana dora 285
 Doherty's Longtail 291
Dolichoptera bisaltis 114
 Donovan's Amata 273
 Dour Butterfly 162
 Dotted Checkerspot 122
 Double-headed Hawk moth 240
 Double-toothed Prominent 248
Doxocopa chryseus 142
Drepana arcuata 189
 Dryad Butterfly 175
Dryas iulia 159
 Duke of Burgundy Fritillary 102
Dynastor napoleon 155
Dysphania cupina 195

E

Eacles mitchellii 219
Eacles lepta 748
 Eastern Alchymist 262
 Eastern Flat 41
 Eastern Grapeleaf Skeletonizer 290
 Eastern Tailed Blue 93
 Eastern Tent Caterpillar Moth 207

Eupanthia scythia 275
 88 Butterfly 133
 Eight-spotted Forester 266
Eilma complana 280
 Elephant Hawk moth 245
 Elm Spanworm Moth 195
Elymnias agestus 171
 Emperor Gnu Moth 231
Enantia subsignaria 199
Enodia parlatia 170
Epanargus clare 37
Epicoma nebulosa 251
Epicoma hectoris 200
Epicoma desolata 230
Epicoma standingi 196
 Eri Salween 254
Erynnis tages 43
Erynnis polydora 158
 Eversley, The 168
Estigmene acra 274
 Eucalyptus Lappet 209
Euchloron megera 2-4
Euchloron ether 285
Euclyptus graminea 235
Euclyptus helena 161
Euclyptus isabella 153
Eumecurus atala 89
Eupackardus callia 221
Euphanta euphanta 132
Euphanta quadripunctata 282
Euphanta unicolor 185
Euphanta 183
Euphanta 268, 269
Euphanta circulator 275
Euphanta cyneta 170
Eurema brigida 71
Eurema arctura 131
 European Map Butterfly 108
Eurytela dryas 112
Eurytela murellus 51
Eurytela rafflesia 38
Euthalia arctura 142
Euxanthia walsbyi 145
 Evening Brown 174
Euxanthia 93
 Eyespot Andiehu 213

F

Fall Cankerworm Moth 192
 Fall Webworm Moth 276
 False Clothes-moth 7
Fauna caenis 151
Fauna largioris 78
 Fecund, The 287
 Fairy Cup Pyralis 230
 Fairy Jewel 83
 Fiercely Tussock 269
 Figtree Blue 87
 Figure-of-eight Butterfly 135
 Fire God Burnet Moth 288
 Flying Pansy 68
 Forester, The 285
 Forest Queen 143
 Four-spotted Frothian 288
 Fox Charaxes 113
Frynia trochilus 98
 Furry Bug 94

G

Gargura thetis 40
 Garden Carpet 197



Garden Tiger 274
Gastrophysa quercifolia 204
 Gaudy Commodore, The 124
 Genoveva Azure 82
Geometra palmatorius 194
 Geometridian, The 201
 Ghost Moth 287
 Giant African Skipper 43
 Giant Agrapt 265
 Giant Anthelid 2-2
 Giant Emperor Moth 235
 Giant Grey Sphinx 243
 Giant Leopard Moth 275
 Giant Redeye 40
 Giant Sphinx 239
 Giant Stigmene-borer 294
 Giant Swallowtail 50
 Gossling 164
Gracopsephus nuxia 93
 Great Moth 292
 Gold-banded Forester 132
 Gold-drop Lichenops 104
 Golden Clearwing 286
 Golden Piper 1, 2
 Gold-spotted Sylph 39
Gnathopryx elopatra 69
Gnometia postica 206
Gracillaria salicifolia 225
Grimmades stolidus 261
Grimmades nigrilimbatu 206
Graptalia surpallens 54
 Grass Jewel 88
 Great Bag-fly 118
 Great Oak Beauty 199
 Great Orange-tip 75
 Great Pouter Moth 235
 Great Purple Hairstreak 89
 Great Spangletail Fairy 138
 Great Spotted Cuckoo 132
 Green Dragonfly 57
 Green Hairstreak 90
 Green Silver-liner 259
 Green-and-side Blue 53
 Grey Dagger 255
 Grey Hairstreak 90
 Grizzled Skipper 45
 Gypsy Skipper 42
 Guinee's Emerald 193
 Gunnsfowl Butterfly 134
 Gulf-butterfly 160
 Gurn Shout Moth 204
Gunda ochracea 215
 Gypsy Moth 267

H

Habrusus scripta 188
 Hackberry Butterfly 1, 1
 Haken Moth 193
Hemidryas archusa 132
Hemimania decedens 174
Hemiaris lucina 102
Hercynia americana 290
 Herring's Brahmaca 217
 Larvester 78
Heliconia cyathippe 75
Heliconius 160, 162, 163
 Heliconius Mimic 162
Heliconius cupido 104
Heliothis armigera 253
Hemaris thysbe 242
Hemerocampa leucostigma 270
Hemerargus isola 101

Hemiteles concolor 35
Hepialis 296, 297
 Herald, The 264
 Hercules Moth 228
 Hermit, The 177
Hesperia picta 40
Heteronympha microps 172
Heteropieris morphens 39
 Hewitson's Blue Hairstreak 88
 Hewitson's Picnic 177
 Hewitson's Princess 105
 Hickory Tiger Moth 276
 Hickory Tussock Moth 276
 Hieroglyphic Moth 264
 High Mountain Blue 101
 Hibernian Jester 141
Himantopus dohrtyi 290
Hipparchia 173
Hipparchia celeris 245
Hofmannophila pseudospretella 7
 Holborn 32
 Holly Blue 56
 Hoop Pine Moth 201
 Hermit Moth 286
 Hummingbird Clearwing 242
 Hummingbird Hawk-moth 243
Hyalophana eripia 225
Hyles lucida 245
Hylesia proboscideus 262
Hypanthia cunea 276
Hypochrysops ignita 83
Hypocysta indiana 175
Hypolimnas 118, 119

I

Idea leucane 186
Ideopsis vitrea 187
 Illud Underwing 260
 Imperial Moth, The 219
Inachis 126
 Infant, The 192
 Indecorous Eggs 205
 Indian Leaf Butterfly 127
 Indian Moon Moth 223
 Indian Red Admiral 138
 Indian Silkmoth 215
 Indo-Australian region 30
 Inquisitive Monkey 211
Inura color 94
 Iolas Blue 94
 Io Moth 220
Iphiclides phalaena 56
 Iron Permittent 248
 Ithalia Tiger Moth 274

J

Junonia alata 92
Junonia westwoodi 211
 Japanese Emperor 129
 Jersey Tiger 282
 Jewelled Nawab 108
 Julia 150
Junonia 120, 121

K

Kallima inachus 127
Kallimoides eumela 136
 King's Bee-hawk 242
 Koh-i-Noor Butterfly 152

L

Lachnocnema bifida 77
Ladona carnifera 137
Lampropteryx lucas 95
Lampropteryx lucas 57
 Lang's Short-corned Blue 98
Lanthoe populi 239
 Lappet Moth 204
 Large Aganista 266
 Large Blue 10
 Large Blue Cuckoo 117
 Large Cuckooed Skipper 39
 Large Copper 91
 Large Emerald 194
 Large Green Appandna 194
 Large Green-handed Blue 95
 Large Head 170
 Large Maple Spanworm Moth 202
 Large Oak Blue 91
 Large Skipper 43
 Large Spotted Acheron 66
 Large Tiger 187
 Large Polyte 209
 Large Tortoiseshell 123
 Large Tree Nymph 186
 Large White 67
 Large Wheel Nymph 164
 Large Yellow Underwing 253
 larva 12
Lasiochrysa quercus 207
 Leaf Blue 67
 Leafwing Butterfly 114
 Leopard Moth 292
Leptidea sinapis 74
Leptochrysa reducta 270
Leptostoma 68
Leptotes cinctus 94
 Lesser Morphid Fairy 117
 Lesser Wanderer 182
Leto 296
 Lettered Habrotyne 148
 Lewis's Bay-shedder Moth 211
Lithytrix 143, 146
Lithytrix carmentis 146
 life-cycle 12
 Lane Hawk moth 263
 Lane Swallowtail 48
Limenitis sayla 144
 Linnaeus 8
Liparis brachyptera 76
Liparis simplicis 77
Lithytrix quadra 240
 Little Wood Sayer 170
 Lobster Moth 249
Loepa laetitia 230
 Long-tailed Blue 95
 Long-tailed Skipper 46
Loplatia incisa 276
Loplatia incisa 74
Loplatia 90, 91
Loplatia 204
Lycodes elodica 187
Lycodes 267, 271
Lycodes bellus 100

M

Macrodactylus delphinus 243
Macrodactylus 11
 Macaronesian Sunset Moth 191
 Magpie Moth 198
 Major Stalk-borer Moth 257

Maach te 144
Malacosoma americanum 207
Manestra brassicae 254
Manuca sexta 238
Mauritia jurtuna 172
 Map-winged Swift 296
 Marbled White 174
Marpesia petraea 123
 Marsh Fritillary 131
 Marshall's Pale Monarch 86
 Meadow Angia 120
 Meadow Brown 172
Mechanitis isthmia 189
Mechanitis mima 181
Megolopaspis agrippa 76
Megathymus junonia 44
Melanargia galathea 174
Melanitis leda 174
Melipotis lutea 181
Melipotis didyma 181
Mentander incandescens 103
menecleus 13
Mesene phareus 102
 Metallic Caerules 92
Metamorphia stelenes 144
 metamorphosis 12
Meteorus 39
 Microlepidoptera 7
Milvina hirsutella 78
Milvina isodora 26
 Minar's Tiger 191
Mimastus marchalis 46
Mimastus tilius 240
 Mima, The 124
 mimicry 17
Mimodes dryas 175
 Mistle-crow Brown-tail Moth 219
 Mitten Swallowtail 49
 Monarch Butterfly 184
 Morgan's Sphinx 238
 Morning-glory Prominent 241
 Morpho 147, 148, 149, 150, 151
 Mosquito Lappet 77
 Moss-green Lappet 208
 Moth Butterflies 76
 Mother-of-pearl Butterfly 121
 Mother-of-pearl Morpho 151
 Mottled Lint 210
 Mourning Cloak 122
 Mustin Bombyx 215
Myiarchus phoebe 63
Myiarchus phoebe 87
Myiarchus morphna 255

N

Nam Meta mark 104
 Napa Barred Blue 81
Natalia flavescens 213
 Neartic region 32
Neophasia menapia 63
 Neotropical region 34
Nepes sappho 128
Nereis indistincta 244
Neretopis repanda 41
 Nettle Caterpillars 287
 Nettle-tree Butterfly 145
 Night Butterfly 176
 Night Moth, the 262
 Night-spined Moth 283
Nuctia procyba 253
 Northern Jungle Queen 153
Nothodonta dromedarius 248

Nudantella cytherea 232
Nidulera amica 281
Nymphalis 122, 23

O

Oak Eggs 207
Ochlodes venia 41
Ochraea 100
Oemona furtiva 214
Oenochroma viaria 193
Oenochroma leucosticta 249
Oxyris 82
 Old World Balloway 253
 Old World Swallowtail 151
 Oleander Hawk-moth 244
 Olive Angle Shades 257
 Olive Prominent 245
Omphax plantaria 194
Oporophris brumata 196
Oporophris euclypti 231
 Orange Albatross 62
 Orange-banded Protea 83
 Orange-banded Giant Sulphur 70
 Orange Moth 198
 Orange Ringlet 173
 Orange Sulphur 72
 Orange Swallow-tailed Moth 204
 Orange Throated Butterfly 102
 Orange Tip 73
 Orange-spotted Cassid 285
 Orchard Swallowtail 46
Oreithys munda 39
Oreithys munda 181
 Oriental Leaf-miner Moth 257
 Ornamental Moth 30
 Ornamental Sulphur 233
 Ornate Moth 279
Oreithys munda 59, 60
Oreithys munda 271
 Otter, The 297
Oreithys munda 201
 Owl Butterfly 156
 Owl Moth 216

P

Pachinotus aristolochiae 54
Pachypasa bilinea 209
 Painted Apple Moth 271
 Painted Lady 41
 Painted Skipper 40
 Palaeartic region 26
Palaeochrysothrips hippothoe 86
Palassa albimaculata 212
 Pale Tussock 268
 Pale Butterfly 26
Pallia ushensis 126
 Pallid Monkey Moth 210
 Palmfly 171
 Palm Skipper 37
Pantodon leucosticta 211
Pantodon pandora 125
Pantoparia hordonia 107
 Papilio 16, 47, 48, 49, 50, 51, 52
Paracles taboureni 216
 Pararge 175, 176
Parathymus neji 115
Parides rosa 53
 Paris Peacocks 47
Parasius apollo 51
Partheneus malthus 92
Partheneus sylvia 141
 Peach Blossom 188
 Peacock 126
 Peacock Royal 33
 Pearl Crescent 113
 Pearly Crescent-spot 113
 Pearly Eve 170
 Pearly Underwing 254
Pentapleura apicalis 215
 Periwinkle Tussock 272
 Peppercod Moth 198
Pezomachus leucosticta 66
Pezomachus saucia 254
Pezomachus 272
Phaenocarpa bucephala 250
Phaenocarpa dula 164
Phaenocarpa sonarensis 97
Phlogophora 175
Phocides polydorus 42
Phocides phoca 70
Pholisora catullus 45
Pholisora catullus 277
Pholisora catullus 113
Pholisora catullus 177
Pholisora 67
Pholisora 208
 Pine Emperor 232
 Pine Porcupine Moth 251
 Pine White 63
 Pine-tree Lappet 204
 Pick-banded Saw 256
 Pick-spotted Hawk-moth 237
 Pigeon Swallowtail 53
 Pirate Butterfly 136
Plagadis doubraria 201
 Plain Ringlet 169
 Plain Tiger 187
 Plane Butterfly 84
Platanus 49
Platanus 7
Platanus 85
Platanus 122
Platanus 125
 Polydorus Swallowtail 55
Polyommatus 99
 Polyommatus Moth 225
 Polyura 103, 109
Pontia daplicia 72
 Poplar Hawk-moth 239
Porthoclis 209
 Postman, The 162
 Prairie Ringlet 162
Pteris 124
Pteris 277
Pteris 119
Pteris 292
 Privet Hawk-moth 237
 proboscis
Prochoreutes transiens 202
 Prometheus Moth 219
Protanippe strigilis 241
 Provence Burnet Moth 289
Prefia africana 272
Pseudocercia leucosticta 140
Pseudops 259
Pseudops 243
 Psyche Butterfly 68
 pupa 15
 Purple Emperor 110
 Purple Hairstreak 86
 Purple Monarch 158
 Purple Thorn 262
 Purple-edged Copper 81
 Puss Moth 246

Pyrgus mulsant 45
Pyrrhastis isabella 278
Pyrrhocalcia iphus 43

Q

Queen Alexandra's Birdwing 59
 Queen Butterfly 183
 Queen Croaker 132
 Queen of Spain Fritillary 111
Quercus quercus 86

R

Rajah Brooke's Birdwing 61
Rapala jacobus 85
 Reakker's Blue 101
 rearing 22
 Red Admiral 138
 Red Lacewing 106
 Red-banded Percus 66
 Red-banded Jexhel 65
 Red-headed Cuckoo-worm 202
 Red-necked Cuckoo-worm 135
 Royal Moth 278
 Regent Skipper 38
Rhynopis hystrix 197
Rhynopis polyura 115
Rhodopis crockeri 211
Rhodopis sylvia 196
 Ringlet, The 166
 Robin Moth 227
Rothschildia orion 233
 Royal Assynia 142
 Royal Wallow Moth 218
 Ruby Tiger 277
 Ruby-spotted Swallowtail 48
 Ruddy Dagger Wing 123


S

Saddle-back Moth 287
Satania pallasii 171
Satania cythra 234
Satania charonda 129
 Saturn Butterfly 155
Saturnia pyri 235
 Scarce Bamboo Pig 164
 Scarce Bordered Swan 243
 Scarce Footman 260
 Scarce Silver-spotted
 butterfly 161
 Scarce Swallowtail 56
 Scarce Tiger 281
Schizura iphonice 249
 Schizura's Agrias 133
Scoliopteryx libatrix 264
Scopis alphas 83
 Scorching Wing 201
Selenia terranovae 202
Semiothisa braggiata 202
 Semiothisa Tiger 277
Semiothisa 286
 Shepard's Footman 280
Silene simulata 287
 Sigmoid Prominent 250
 Silkmoth 211
 Silver Hammer 84
 Silver "Y" Moth 261
 Silver-bordered Fritillary 134
 Silver-spotted Flameback 160
 Silver-spotted Ghost Moth 297

Silver-spotted Skipper 37
 Silver-striped Hawk-moth 245
 Silver-studded Blue 99
 Silver-washed Fritillary 125
 Silvery Crescent-spot 120
Siproeta claphus 135
 Six-spot Burnet 289
 Skar's Urania 191
 Small Copper 99
 Small Flameback 161
 Small Harvester 76
 Small Heliconius 163
 Small Lacewing 167
 Small Mottled Willow Moth 258
 Small Pearl-bordered Fritillary 134
 Small Porcelain 163
 Small Silkmoth 214
 Small Thyridia 181
 Small Tortoiseshell 110
 Small White 67
Smicranthus jamaicensis 241
 Smooth Emerald 194
 Snout, The 262
 Snow-white Lander 199
 Snowy Eupseudosoma 275
 Southern Blue 97
 Southern Cloudywing 38
 Southern Snout Butterfly 146
Spargis pennis 77
 Spangly Pastoon 56
 Spangly Moon Moth 225
 Spangly Moth 255
 Spangly-marked Black 197
 Spangled Wood 175
Speyeria cybele 131
Sphinx agestis 237
Spilosoma lubripada 274
Spilosoma nodulosa 81
 Spiny Bollworm Moth 258
Spodoptera 258, 259
 Spotted Fritillary 137
 Spotted Kingbird 196
Stauronema fiji 244
Stenopis argyromaculatus 297
Stenopis calandria 153
 Streaked Sphinx 241
 Striped Blue Crow 185
 Striped Hawk-moth 245
 Striped Policeman 42
Strymonia sp. albina 81
Strymon melinus 90
 Swallowtail 51
 Swallowtail Moth 251
 Swamp Metalmark 105
 Sweet Potato Acrea 165
 Sweet Potato Hornworm 237
 Swartgrass Brown 178
Synbrenthia hypoleis 141
Synonymia parthenocles 285
Synonymia parthenocles 98
Synthesia nigerrima 256
Syntomis phyllis 283
Syntomis doris 107

T

Tagesia peliada 210
 Tailed Emperor 89
Tajaria zippus 83
 Tau Emperor 222
 Tawny Rajah 116
Taygetis arka 176



Tetrasia anartoides 211
Tetrasia satia 179
Tetrasia euphratica 279
Tetrasia leucophaea 142
Tetrasia shepherdi 280
Tetrasia claus 203
Tetrasia polyantia 251
Tetrasia nigris 154
 The Aala 89
 The Basket 283
Thecla 88
 The Emeralds 164
 The Pastoon 287
 The Forest 289
 The Gandy Commensal 124
 The Geometridian 26
 The Herald 261
 The Hermit 177
 The Imperial Moth 219
 The Infant 192
 The Mimic 124
 The Ni Moth 262
 The Otter 297
 The Postman 167
 The Ringlet 166
 The Snout 262
 The Vestal 196
 The Viceroy 124
 The Wanderer 167
 The White-spark 255
 The Wizard 115
Theophrastus 102
Theophrastus religiosus 215
Thrinopis croceipennis 203
Thrinopis doris 38
Thrinopis hystrix 188
Thrinopis theophrasti 181
Thrinopis agrippina 265
 Tiger Butterfly 180
 Tiger-Picnic 74
 Tiger Swallowtail 52
Tiphonia albus 173
Tiphonia harmonia 180
 Tobacco Hornworm 238
Tolype celtica 209
Trabala carolina 208
 Transparent Tussock 272
Trichoplia 262
Troia 61

- tropical rainforest 19
- 'Tufted Jungle Queen' 154
- 'White-tree Beauty' 200
- 'Twin-rose Lappet' 239
- 'Twin-spotted Sphinx' 241
- 'Two- and Pastel' 113
- 'Yucca jewel' 282

U

Union Jack 65
 Urubers zeabry 107
 Urubers zeabry 191
 Urubers zeabry 36
 Urubers 275

V

Vampire Moth 264
Vannessa 138, 139
 Variorer 274
 Variable Burnet Moth 288
 Velvet Tiger 279
Vernonia canberrae 197
 Venus Moth 206
 Vernal Blue 244
 Vexal, Tree 196
 Viceroy, The 24
 Viennese Empress Moth 235
Vindicta erata 128
Vindicta vincta 86
 Virgin Blue-moth 273
 Virginian Green-cha 283

W

Wandering Tanager 67
 Wattle's Hook 189
 Water Tiger 276
 Wattle Snout Mouth 205
 Welsh Wave 197
 Western Pygmy Blue 97
 White Admiral 37
 White Barred Gypsy 212
 White Butterfly 315
 White Speckle 255
 White "A" Hairstreak 92
 White Peacock 107
 White-angled Sulphur 71
 White-headed Thorn 203
 White-letter Hairstreak 8
 White-marked Tussock Moth 270
 White-spotted Tadpole
 Butterfly 103
 Winter Mite 196
 Wizard, The 115
 Wood Lark 292
 Wood Wren 74
 Woodward Grayling 173
 Woolly Legs 77

X

Xanthoxanthin 246
 Xanthoxanthin acetate 247
 Xanthoxanthin diacetate 248
 Xanthoxanthin diacetate 255

Xanthoxone sturmiata 197
Xyantes 291, 293

Y

Yantfly 79
 Yellow Apricot 70
 Yellow Caster 165
 Yellow-belted Burnet 383
 Yellow-headed Antelope 213
 Yellow-necked Caterpillar Moth 250
 Yellow-spot Blue 96
 Yellow-spotted Conatryx 71
 Ypthima 178
 Yucca Giant Skipper 44

Z

Zebra 16
Zebra Butterfly 114
Zebra Swallow 153
Zelotrypa stacyi 204
Zerrus carpinis 64
Zephania cumina 56
Zenaidura macroura 155
Zenaidura macroura 292
Zenaidura macroura 174
Zenaidura macroura 100
Zenaidura macroura 144
Zenaidura macroura 190
Zenaidura macroura 26
Zenaidura macroura 31
Zenaidura macroura 249

ACKNOWLEDGMENTS

THIS BOOK COULD not have been completed without the help, material and otherwise, of several persons and institutions. The photography of the majority of butterfly and moth specimens was taken at The Natural History Museum of London. For making available additional specimens for photography the publisher would like to thank:

Dr. Gerard Legg, of The Booth Museum Brighton.

Dr. M. Shaw and Dr S. Holmes of the National
Museum of Scotland, Edinburgh

Matthew Ward, the photographer of these additional specimens.

Dorling Kindersley would like to thank:
 Caroline Church for the endpaper illustrations;
 Alastair Wardle for the maps on pages 26-35,
 and Salvo Tomasek for the miniature maps
 throughout the book, Peter Howlett of Lemon
 Graphics for placing the leader lines.

We are indebted to Damien Moore and Polly Joyd for their invaluable editorial help; Paul Dewhurst, Deborah Myatt, Jane Johnson, and Pauline Bayne for their design expertise; and Michael Allaby for compiling the index.

PICTURE CREDITS


a-above, b-below, c-centre, l-left, r-right,
t-top

Oxford Scientific Films: p.12(br), p.08(tr),
p.20(er), p.26(cl), p.28(ul), p.30(cl), p.32(c.),
p.34(cl).

Hutchison Library: p.30(c), p.19(b), (c)

Natura. Science Photographs: p.11(bl), p.07(cr).

Ardea London Ltd: p.24 (b1)









David Carter is an entomologist at the Natural History Museum, London, where he has worked for nearly 40 years, specializing in Lepidoptera. At the museum, he has also managed part of the vast National Collection of World Insects. His many books on the subject include

the *Observer's Book of Caterpillars, Butterflies and Moths in Britain and Europe*, *The Photographic Guide to Identifying Butterflies* and the *Collins Field Guide to Caterpillars of Britain and Europe*. He has also produced technical manuals such as *Pest Lepidoptera of Europe* and *Care and Conservation of Natural History Collections*, as well as many scientific papers. David lives with his wife Brenda in Surrey, England. They have four grown-up children.



ALSO AVAILABLE FROM DORLING KINDERSLEY



*Aquarium Fish • Birds' Eggs • Birds of the World • Cats • Dogs
Fossils • Gemstones • Herbs • Horses • Insects • Mushrooms
Reptiles and Amphibians • Rocks and Minerals • Shells
Stars and Planets • Trees • Whales, Dolphins and Porpoises
Wild Flowers of Britain and Northwest Europe • Wild Flowers
of the Mediterranean*

Available from all good bookshops, your DKFL advisor, or call us on 0870-840-4400 (in the UK only) and (02) 9438-4455 (in Australia only), or visit us worldwide at www.dk.com

see our complete
catalogue at

www.dk.com

ISBN 0 7513 2707 7

Over 5 million copies sold worldwide

DK DORLING KINDERSLEY HANDBOOKS

BUTTERFLIES AND MOTHS

The clearest and sharpest recognition guide to over 500 species of butterflies and moths

Packed with over **600 crystal-clear photographs** with precise annotation to make identification sure and simple

Concise and **jargon-free text** pinpoints the key characteristics of each species and provides **quick, accessible information**



ISBN 0-7513-2707-7



9 780751 327076 >

Dorling **DK** Kindersley

see our complete
catalogue at

www.dk.com